



September 12, 2019

**Mr. Greg Raucci
Bismark Construction
100 Bridgeport Ave.
Milford, CT 06460**

RE: Hart Elementary School
61 Adams Ave.
Stamford, CT 06902

Greenwood Roof Services hereby proposes to furnish all union labor, materials, and equipment necessary to perform the following:

- Hoisting all materials and equipment with Crane to properly perform work.
- Set-up proper Safety Equipment to safely perform work per OSHA specifications.
- Cut & Remove marked wet areas per report: 1- 25' x 15', 1- 20' x 15', 1- 20' x 10', 1- 15' x 15', 3- 5' x 5'.
- Supply and install new insulation to areas to match existing roof thickness.
- Attach new insulation with heavy duty screws and 3" field plates per manufacturer's specifications.
- Supply and install Cold-Applied SBS 2-Ply Granulated Modified Asphalt patches to areas in a fully-adhered manner per manufacturer's specifications.
- Scratch and remove all gravel from perimeter of areas and properly dispose.
- Supply and install Karnak#19 2-Ply membrane, 12" wide to properly tie-in new patches to existing roof systems.
- Inspect all wall flashings, penetrations, drains, scuppers etc. for defects and make necessary repairs.
- Clean and properly dispose of any loose debris on roofs and drainage points.
- Hoisting of all work-related debris and equipment will be necessary, when job is complete.
- Clean and properly dispose of all work-related debris.

Total: \$48,000.00



Excludes: Any work not listed above.

Premium Time

Building Permits

Cutting & Patching of Decking

Winter Conditions

If you have any questions or comments regarding this proposal please contact me at

(860) 999-4598 or by e-mail at staftjones@greenwood-industries.com

Sincerely,

Sarah Jones

Regional Sales Manager