

ROOM NOTES

ROOM 228

SCOPE OF WORK NOTES

- SET UP EDGE GUARD AT ROOM ENTRANCE,
- SET UP CONTAINMENT AND NEGATIVE AIR MACHINE,
- REMOVE MILLWORK,
- INSPECT ROOF DRAIN AND REPAIR IF NEEDED,
- REMOVE APPROXIMATELY 650 SF OF VINYL WALL PAPER;
- REMOVE APPROXIMATELY 30 SF OF DRYWALL AROUND WINDOW SYSTEM;
- INSTALL INSPECTION HOLES WHERE NEEDED
- CLEAN EXPOSED FIN TUBE,
- CLEAN 1 RETURN AND 1 VENT;
- CLEAN 3 CEILING TILE (REMOVE IF UNABLE TO CLEAN);
- REPAIR HVAC INSULATION

ROOM 230

SCOPE OF WORK NOTES

- SET UP EDGE GUARD AT ROOM ENTRANCE,
- SET UP CONTAINMENT AND NEGATIVE AIR MACHINE,
- REMOVE MILLWORK,
- INSPECT ROOF DRAIN AND REPAIR IF NEEDED,
- REMOVE APPROXIMATELY 560 SF OF VINYL WALL PAPER;
- REMOVE APPROXIMATELY 30 SF OF DRYWALL AROUND WINDOW SYSTEM;
- INSTALL INSPECTION HOLES WHERE NEEDED,
- CLEAN EXPOSED FIN TUBE,
- REMOVE 6 CEILING TILE
- CLEAN 4 CEILING TILE (REMOVE IF UNABLE TO CLEAN), CLEAN 1 RETURN AND 1 VENT;
- REPAIR HVAC INSULATION IF NEEDED

ROOM 232

SCOPE OF WORK NOTES

- SET UP EDGE GUARD AT ROOM ENTRANCE,
- SET UP CONTAINMENT AND NEGATIVE AIR MACHINE,
- REMOVE MILLWORK,
- INSPECT ROOF DRAIN AND REPAIR IF NEEDED,
- REMOVE APPROXIMATELY 560 SF OF VINYL WALL PAPER;
- REMOVE APPROXIMATELY 30 SF OF DRYWALL AROUND WINDOW SYSTEM;
- INSTALL INSPECTION HOLES WHERE NEEDED
- CLEAN EXPOSED FIN TUBE,
- REMOVE 1 CEILING TILE
- CLEAN 3 CEILING TILE, (REMOVE IF UNABLE TO CLEAN)
- CLEAN 1 RETURN AND 1 VENT;
- REPAIR HVAC INSULATION IF NEEDED


ROOM 234 (PFO)

SCOPE OF WORK NOTES

- SET UP EDGE GUARD AT ROOM ENTRANCE,
- SET UP CONTAINMENT AND NEGATIVE AIR MACHINE,
- REMOVE APPROXIMATELY 525 SF OF WALL COVERING;
- REMOVE APPROXIMATELY 30 SF OF DRYWALL AROUND WINDOW SYSTEM;
- INSTALL INSPECTION HOLES WHERE NEEDED,
- CLEAN EXPOSED FIN TUBE,
- CLEAN 1 RETURN AND 1 VENT;
- REMOVE 15 CEILING TILE;
- CLEAN AND VAC 3 CEILING TILE (REMOVE IF UNABLE TO CLEAN)
- REPAIR HVAC INSULATION IF NEEDED

LEGEND

- = SET UP EDGE GUARD AT ROOM ENTRANCE
- = REMOVE DRYWALL AROUND WINDOW SYSTEM AND INSTALL INSPECTION HOLE WHERE NEEDED
- = REMOVE VINYL WALL PAPER



AREA SHOWN



SECOND FLOOR

Stark Elementary School

City of Stamford

Stamford, CT

DRAFT

MARK	DATE	DESCRIPTION
PROJECT NO:	S2087	
DATE:	4/1/2019	
FILE:	Stark Mold Remediation2.dwg	
DRAWN BY:	WAC/BG	
CHECKED:	BS	
APPROVED:	XX	

Area 8

SCALE: NTS

Figure 3.5