




LEGEND

 NOTE 1 - REMOVE ASBESTOS-CONTAINING CEILING PLASTER (TWO LAYERS), METAL LATH, AND WOOD FRAMING IN ENTIRETY. DISPOSAL SHALL BE AS FRIABLE ASBESTOS WASTE AND WORK SHALL BE CONDUCTED WITHIN A FULL CONTAINMENT WITH CONTIGUOUS DECONTAMINATION UNIT.

 NOTE 2 - REMOVE NON-ASBESTOS CARPETING AND MULTIPLE LAYERS OF CEILINGS (2'X4' CEILING TILES AND GRID, METAL TIN CEILING, AND NON-ASBESTOS CEILING PLASTER [TWO LAYERS AND METAL/WOOD LATH]) TO WOOD FRAMING. WORK SHALL BE CONDUCTED IN A ONE-LAYER NEGATIVE PRESSURE CONTAINMENT. CLEAN AND DISINFECT SURFACES AND/OR SPACES.

 NOTE 3 REMOVE ASBESTOS-CONTAINING FLOORING AND MASTICS (MULTIPLE LAYERS) DOWN TO SUBSTRATE. DISPOSAL SHALL BE AS FRIABLE AND/OR NON-FRIABLE ASBESTOS WASTE AND WORK SHALL BE CONDUCTED WITHIN A FULL CONTAINMENT WITH CONTIGUOUS DECONTAMINATION UNIT.

 NOTE 4 REMOVE WATER DAMAGED AND/OR MOLD GROWTH IMPACTED DRYWALL WALLS AND CEILINGS IN ENTIRETY WITHIN CUSTODIAN CLOSET. REMOVE WATER DAMAGED AND/OR MOLD GROWTH IMPACTED NON-ASBESTOS WALL PLASTER FROM THE NORTH AND EAST WALLS OF GYM OFFICE IN THE VICINITY OF THE CUSTODIAN CLOSET. CLEAN AND DISINFECT SURFACES AND/OR SPACES.

GENERAL NOTE
 REMOVE WATER DAMAGED AND/OR MOLD GROWTH IMPACTED CEILING TILES. CLEAN AND DISINFECT AREAS.

DRAFT - 6/3/2019
Owner/CM Review

KT MURPHY ELEMENTARY SCHOOL STAMFORD, CT	
SUMMER WORK 2019	
DATE: 5/31/2019	Tighe & Bond Engineers Environmental Specialists
NOT TO SCALE	
FIGURE: 3.3	