

__18" DIA. COVER


PLAN VIEW


SECTION A - A


-6" x 9" COVER

12

3" WALLS







SPECIFICATIONS
CONCRETE MINIMUM STRENGTH - 4,000 PSI @ 28 DAYS STEEL REINFORCEMENT — 6" X 6" X 10 GA. STEEL WIRE MESH CONSTRUCTION JOINT — SEALED WITH ASPHALT CEMENT 1500 GALLON PUMP CHAMBER = 31.17 GAL./INCH PUMP TO BE SET MIN. 5 1/2" OFF THE PUMP CHAMBER FLOOR

2" DRAWDOWN = 62.3 GAL./CYCLE

REQ. STORAGE = 1 DAY DESIGN VOLUME = 5 BEDROOM = 600 GAL.

87.5 LF S-BOX SB1-7-72 STORES 499 GAL.


DOSE © 20% OF 499 GAL. = 100 GAL. MAX.

STORAGE AVAILABLE IN CHAMBER AFTER DISCHARGE = 1152 GAL.

(969 GAL. AFTER HIGH WATER ALARM)





CONCRETESEPTIC TANK





- 1. AREA CHOSEN FOR STOCKPILING OPERATIONS SHALL BE DRY AND
- 2. MAXIMUM SLOPE OF STOCKPILE SHALL BE 1:2. 3. UPON COMPLETION OF SOIL STOCKPILING, EACH PILE SHALL BE SURROUNDED WITH EITHER SILT FENCING OR STRAWBALES, THEN STABILIZED WITH VEGETATION OR COVERED.

TEMPORARY STOCKPILE DETAIL












TREE PROTECTION

FILTER CLOTH SIDE ELEVATION EXISTING GROUND ___ VDOT #1 * MUST EXTEND FULL WIDTH OF INGRESS AND EGRESS OPERATION PLAN VIEW 12' MIN. SECTION A-A CE CONSTRUCTION ENTRANCE







SEPTIC SYSTEM ELEVATION KEY

rench No.	Existing	Proposed	Restrictive	Trench	Trench Top
	Grade	Grade	Layer	Bottom El.	EL.
1	75.4	76.7	73.9 (18" Mottling)	75.4	76.0
2	75.4	76.7	73.9 (18" Mottling)	75.4	76.0

GENERAL CONSTRUCTION NOTES

1. DESIGN DATA: POPULATION: 5-BEDROOM RESIDENCE REPAIR. HOUSE CURRENTLY HAS (1) LARGE

DESIGN PERC RATE: 1" IN 10.1-20 MIN. REQUIRED EFFECTIVE LEACHING AREA: 675 + 2(112.5) = 900 S.F. PROPOSED S-BOX SB1-7-72 UNITS; 2 ROWS 1 @ 41.67 LONG, 1 @ 45.83 LONG. PROPOSED EFFECTIVE LEACHING AREA = 41.67+45.83 = 87.5 LF, (87.5) (15.9) = 1,391 SF

DEPTH TO RESTRICTIVE LAYER: RL = (R1 + R2)/2 (BASED ON TEST HOLES 1&2) R1 = (#1+TOP OF SYSTEM) = (18"+7") = 25"R2 = (#2) = 20" RL = (R1 + R2)/2 (25" + 20") / 2 = 22.5"

M.L.S.S. SLOPE: 4.1-6% => HYDRAULIC FACTOR = 34 FLOW FACTOR (FF) = 1.75 + 0.25 = 2.0

PERCOLATION FACTOR (PF) = 1.25 REQUIRED MLSS = HF X FF X PF = 34 X 2.0 X 1.25 = 85 LF

PROPOSED LEACHING SYSTEM SPREAD = 87.5 LF PROPOSED 1,500 GALLON SEPTIC TANK

2. PRIOR TO CONSTRUCTION OF THE SEPTIC SYSTEM, THE CONTRACTOR SHALL ENLIST THE SERVICES OF "CALL BEFORE YOU DIG" @ 1-800-922-4455 IN ORDER TO LOCATE ANY UNDERGROUND UTILITIES OR STRUCTURES. THE CONTRACTOR SHALL CONTACT THE CERTIFYING ENGINEER AND THE STAMFORD HEALTH DEPARTMENT AT LEAST 24

HOURS PRIOR TO CONSTRUCTION; IF NOT, THE SYSTEM WILL NOT BE CERTIFIED

REQUIRED TANK CAPACITY FOR 5 BEDROOM HOUSE WITH TUB = 1,000 + 2(125) + 125

3. STRIP AND REMOVE THE TOPSOIL PRIOR TO PLACEMENT OF THE SELECT FILL

4. ALL SELECT FILL MATERIAL MUST MEET THE REQUIREMENTS SPECIFIED IN SECTION VIIIA OF THE STATE OF CONNECTICUT PUBLIC HEALTH CODE TECHNICAL STANDARDS. A SIEVE ANALYSIS MUST BE SUBMITTED AND APPROVED BY THE ENGINEER PRIOR TO THE INSTALLATION. SELECT FILL SHALL MEET THE FOLLOWING MINIMUM GRADATION

SIEVE	PERCENT	
SIZE	PASSING	
	WET SIEVE	DRY SIEV
#4	100	100
#10	70-100	70-100
#40	10-50.	10-75.
#100	0-20	0-5
#200	0.5	0.05

5. FILL SHALL BE PLACED ON THE PERIMETER OF THE TRENCH AREA AND SPREAD WITH A SMALL CRAWLER, TRACTOR OR OTHER APPROVED MACHINERY. PLACEMENT OF SELECT FILL AND OTHER RELATED WORK NECESSARY FOR THE CONSTRUCTION OF THE SEPTIC SYSTEM SHALL BE PERFORMED WITH EQUIPMENT THAT WILL NOT ADVERSELY COMPACT THE ORIGINAL SUBGRADE

6. CONTRACTOR SHALL CONTACT THE CERTIFYING ENGINEER AND THE HEALTH ARTMENT AT LEAST 24 HOURS PRIOR TO CONSTRUCTION; IF NOT, THE SYSTEM WILL NOT BE CERTIFIED.

7. ALL SURFACE WATER SHALL BE CHANNELED AWAY FROM THE SEPTIC SYSTEM AREA. 8. A CONNECTICUT LICENSED PROFESSIONAL ENGINEER, ACCEPTABLE TO THE DIRECTOR OF HEALTH, SHALL INSPECT CONSTRUCTION TO INSURE COMPLIANCE WITH THE PROPOSED PLAN.

9. AN "AS BUILT" RECORD PLAN, CERTIFIED BY A PROFESSIONAL ENGINEER, SHALL BE SUBMITTED TO THE DEPARTMENT OF HEALTH BEFORE A "PERMIT TO USE" IS ISSUED. 10. THE AREA SURROUNDING THE SUBJECT SITE IS COMPOSED OF SINGLE FAMILY RESIDENTIAL CONSTRUCTION, SERVED BY PUBLIC WATER SUPPLY AND INDIVIDUAL SEPTIC SYSTEMS. NO WELL ON ANY LOT ADJACENT TO THE SUBJECT PROPERTY IS

11. NO IRRIGATION SYSTEM SHALL BE INSTALLED WITHIN TEN (10) FEET OF THE SEPTIC

12. NO FOOTING DRAINS OR OTHER GROUNDWATER INTERCEPTING DRAINS SHALL BE INSTALLED WITHIN 25' OF PROPOSED SEPTIC SYSTEM OR WITHIN 50 FEET OF THE SEPTIC SYSTEM IF DRAIN IS DOWN GRADIENT

13. THIS SYSTEM IS NOT DESIGNED FOR BACKWASH FROM A WATER SOFTENING SYSTEM OR THE OUTFLOW FROM A GARBAGE DISPOSAL OR TUB (BATHTUB, WHIRLPOOL, JACUZZI, ETC.) IN EXCESS OF 100 GALLONS.

14. PROPOSED SEPTIC TANK AND PUMP CHAMBER SHALL BE COATED SO AS TO BE "WATERTIGHT".

MATERIAL SPECIFICATIONS AND ADDITIONAL NOTES

WITHIN 75' OF THE PROPOSED SEPTIC SYSTEM.

- A. LEACHING SYSTEM SHALL BE S-BOX SB1-7-72 UNITS WITH AN APPROVED EFFECTIVE LEACHING AREA CAPACITY OF NOT LESS THAN 15.9 SF/LF
- B. PIPING MATERIALS SHALL CONFORM TO THE NOMINAL DIAMETERS SHOWN ON THE PLAN AS WELL AS THE FOLLOWING MINIMUM STANDARDS; FROM HOUSE TO SEPTIC TANK
- FROM SEPTIC TANK TO PUMP CHAMBER 4 SCHEDULE 40 PVC ASTM D3034
 FROM PUMP CHAMBER TO LEACHING CHAMBERS 2" SCHEDULE 40 PVC ASTM D1785 ALL SOLID WALL DISTRIBUTION PIPING SHALL BE INSTALLED IN ACCORDANCE WITH DESIGN DETAILS SHOWN. IN GENERAL, THE MATERIALS AND BACKFILLING METHODS SHALL BE SUCH THAT THE COMPLETED SYSTEM CAN WITHSTAND H-20 LOADING.
- C. DISCHARGE PUMP AND RELATED CONTROLS SHALL BE AS FOLLOWS. SEWAGE PUMP, CONTROLS AND RELATED HARDWARE SHALL BE AS MFG. BY THE GOULDS PUMP CO. OR AN APPROVED EQUAL.
 SEWAGE PUMP: MODEL 3885, SERIES WE0511HH, 1/2 HP, SINGLE PHASE, 115 V, 14.5 AMP. CONTROLS SHALL BE MECHANICAL FLOAT SWITCHES. ALARM PANEL TO BE MOUNTED IN THE MECHANICAL ROOM.

GENERAL SEDIMENTATION AND EROSION CONTROL NOTES

1. A SEDIMENT BARRIER WILL BE ERECTED AROUND THE DOWNSLOPE PERIMETER OF ALL CONSTRUCTION ACTIVITIES. IN ADDITION TO THOSE SHOWN ON THE PLAN, ADDITIONAL CONTROLS WILL BE INSTALLED AS DEEMED NECESSARY BY THE GENERAL CONTRACTOR IN RESPONSE TO SITE CONDITIONS.

2. CUT AND/OR FILL SLOPES OF GREATER THAN 2 ON 1 REMAINING IN ROUGH GRADE WILL BE MULCHED AND SEEDED.

3. THE AMOUNT OF NATURAL VEGETATION REMOVED WILL BE MINIMIZED. ALL

DISTURBED AREAS NOT SCHEDULED FOR CONSTRUCTION WITHIN 60 DAYS WILL BE MULCHED WITH UNROTTED STRAW OR HAY AND SEEDED. MULCH WILL BE APPLIED AT 90 LBS. PER 1000 SQ. FT.

4. ALL STOCKPILES LEFT FOR MORE THAN 1 MONTH WILL BE RINGED WITH SEDIMENT

5. AT LEAST 50 FEET OF SILT FENCE AND/OR 50 FT. OF HAYBALES WILL BE STOCKPILED ON SITE FOR EMERGENCY USE.

6. SEDIMENT REMOVED FROM CONTROL STRUCTURES WILL BE PLACED IN AN APPROVED UPLAND SITE, A SUFFICIENT DISTANCE FROM ALL CONTROLLED ENVIRONMENTS.

7. UPON FINAL GRADING THE OPEN SOIL HORIZONS ARE TO BE IMMEDIATELY PLACED IN SEED. OPTIMUM SUCCESS IN ESTABLISHING PLANTS ON SLOPES IS ACHIEVED WHERE SLOPE ANGLES DO NOT EXCEED 3 HORIZONTAL TO ONE VERTICAL. THESE SOILS

SHOULD NOT CONTAIN GREATER THAN 85% CLAY. 8. CONSTRUCTION ENVELOPES ARE TO BE DELINEATED WITH HIGH VISIBILITY BARRICADE TAPE, SNOW FENCE OR PLASTIC NETTING.

9. TREES IN A CLOSE PROXIMITY TO CONSTRUCTION ACTIVITIES ARE TO BE PROTECTED WITH SNOW FENCE OR A COMPARABLE BARRIER PLACED AT THE DRIPLINE. 10. METHODS FOR PROPER DESIGN AND INSTALLATION OF CONTROL MEASURES MAY BE FOUND IN THE CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL. 11. UTILITY TRENCHES ARE TO BE COMPLETED, SEEDED AND MULCHED WITHIN 15 DAYS

AFTER BACKFILL. 12. ANY DISTURBED AREA NOT PAVED, SODDED OR BUILT UPON BY NOVEMBER 1ST IS TO BE SEEDED ON THAT DATE WITH OATS, ABRUZZI RYE, OR EQUIVALENT AND

MULCHED WITH HAY OR STRAW. 13. DRAINAGE OUTLETS ARE TO BE PROTECTED WITH SPLASH GUARDS OR STONE AND/OR LEVEL SPREADERS.

14. ALL EROSION CONTROL DEVICES SHALL BE INSPECTED EVERY TWO WEEKS AND/OR AFTER EVERY RAIN STORM OF 0.5" OR GREATER.

PROJECT NOTES

1. ALL SEDIMENTATION AND EROSION CONTROLS ARE TO BE INSTALLED PRIOR TO START OF DEMOLITION AND CONSTRUCTION. 2. MACHINERY ACCESS WILL BE VIA THE EXISTING DRIVEWAY.

3. ALL FILL & EXCAVATION WILL BE LIMITED TO PROPOSED ACTIVITIES.

4. PROPOSED ACTIVITIES ARE GENERALLY SITED WHERE CONCEPTUALLY APPROVED.

GENERAL CONSTRUCTION SEQUENCE

1. EMPLACEMENT OF THE SEDIMENTATION & EROSION CONTROLS; 2. DELINEATION OF THE CONSTRUCTION ENVELOPES WITH HIGH-VISIBILITY BARRICADE TAPE OR SNOW FENCE:

3. CLEARING WITHIN THE AREA FOR THE PROPOSED ACTIVITY & REMOVE EX. DECK; 4. TOPSOIL REMOVAL AND STOCKPILING IN STABILIZED AREA, STABILIZED WITH MULCH AND/OR RINGED WITH SEDIMENT BARRIER; 5. ABANDON EXISTING LEACHING AREA - EX. GALLERIES TO BE FILLED WITH SELECT

6. CONSTRUCT NEW LEACHING AREA, PUMP CHAMBER & SEPTIC TANK;

7. CRUSH & FILL EX. SEPTIC TANK & CONNECT HOUSE SEWER LINE TO NEW SEPTIC

8. UTILITY & POOL EQUIPMENT RECONSTRUCTION AS NEEDED; 9. DRIVEWAY RE-CONSTRUCTION AS NEEDED:

10. FINAL GRADING & LANDSCAPING; STABILIZING ALL DISTURBED AREAS WITH 4" MINIMUM OF TOPSOIL AND EITHER SOD OR GRASS SEED AND HAY.


11. CONSTRUCTION PHASES WILL OCCUR SIMULTANEOUSLY AS LONG AS THE SITE IS STABLE AND EROSION CONTROLS ARE FUNCTIONING.

TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES - MAINTENANCE REQUIREMENTS:


1. Siltation fence barriers: Accumulated sediment shall be removed when it has reached a height of 25% of

the exposed sediment barrier and disposed off is an appropriate manner.


2. Construction Entrance: Stone for the pad shall be replaced as needed during the construction process to maintain the pad and prevent the tracking of soil onto the road.












PREPARED FOR ALFONSO TAGLIAVIA

9 WEST BANK LANE STAMFORD CONNECTICUT

DETAILS & NOTES

SHEET 2 OF R.M.F. | ACCT. # 002-442 BLOCK NO. 37

:/Drawings/stamford/tagliavia/tagliavia 9 West Bank Site R2.DWG



CIVIL ENGINEERING STRUCTURAL ENGINEERING LAND DEVELOPMENT

15 SNOWBERRY LANE

NEW CANAAN, CT 06840 (203) 554-9551 (PHONE)

(203) 966-6957 (FAX)