

STORMWATER MANAGEMENT REPORT

**800 LONG RIDGE ROAD
STAMFORD, CONNECTICUT**

Prepared by:

CIVIL 1
43 Sherman Hill Road
Suite D-101
Woodbury, CT 06798



October 3, 2023

TABLE OF CONTENTS

SECTION 1 - Stormwater Management Report

1. Project Vicinity Map.....	1
2. Project Introduction.....	2
3. Existing Site Conditions.....	2
4. Proposed Site Conditions.....	3
Project Type & General Design Criteria.....	3
Summary of Low Impact (LID) Site Constraints.....	4
Summary of Proposed Stormwater Treatment Practices.....	4
5. Compliance with Stormwater Management Standards.....	7
Standard 1. Runoff and Pollutant Control.....	7
Standard 2. Peak Flow Control.....	8
Standard 3. Construction Erosion and Sediment Control.....	10
Standard 4. Operation and Maintenance.....	11
Standard 5. Stormwater Management Report.....	12

SECTION 2 – Appendices

Appendix A – Drainage Area Maps	
Appendix B – NOAA Precipitation Data	
Appendix C – Existing Conditions HydroCAD Routing	
Appendix D – Proposed Conditions HydroCAD Routing	
Appendix E – Water Quality Calculations	
Appendix F – Hydrodynamic Separator Sizing Calculations	
Appendix G – Rational Method Sizing for Storm Drainage System	
Appendix H – Outlet Protection Calculations	
Appendix I – USDA Soils Mapping	
Appendix J– Draft Standard Stamford Drainage Maintenance Agreement	
Appendix K – DCIA Tracking Worksheet	
Appendix L - Checklist for Stormwater Management Report & Plan	
Appendix M - LID Review Map	


SECTION I
STORMWATER MANAGEMENT REPORT

1. Project Vicinity Map

800 LONG RIDGE ROAD, STAMFORD



PROJECT SITE VICINITY MAP



ZONE: C-D (DESIGNED COMMERCIAL)

2. Project Introduction

Applications are being submitted to the City of Stamford's land use offices for proposed improvements to a 25.26-acre property located at 800 Long Ridge Road, in the Designed Commercial (C-D) Zoning District. The property is owned by, and being developed by, 800 Long Ridge, LLC, Stamford, CT. Included in the proposed development is the demolition of an existing 4-story office building and 2-level parking garage. The existing driveway, parking areas, and most of the walkways are slated to remain to serve the future buildings. Two proposed multi-family residential buildings will be constructed and will encompass approximately the same footprint as the existing buildings to be demolished.

The proposed project will utilize the existing curb cut on Long Ridge Road and tie into the existing public water supply and sanitary sewer systems that currently serve the site. Significant stormwater management improvements are proposed throughout the property as, currently, there is minimal treatment of stormwater beyond runoff conveyance and piping.

3. Existing Site Conditions

The property at 800 Long Ridge Road currently contains two existing structures: one 4-story office building and one 2-level parking garage. There is a surrounding network of existing parking areas, walkways, and access drives that serve the building. A majority of the site is developed and there is approximately 8.26 acres of impervious area on the 25.26-acre site (32.7% of total property area). There are several walking paths in the rear, westernmost, portion of the site.

The property generally slopes up from Long Ridge Road from east to west. A majority of the site, and a large amount of off-site area, drains to an existing pond on the property along Long Ridge Road. Above the site, there is approximately 82.2 acres of developed land that drains toward the site, entering an existing 60" culvert along the westerly property line. The culvert discharges to a channel, which briefly leaves the property before re-entering the site and entering into the existing pond. This pond discharges under Long Ridge Road through twin 24" culverts, ultimately draining to the Rippowam River that is just across the street to the east. There is a small area near the entrance to the 2-24" culverts that is within the 100-year flood plain as defined by the FEMA mapping for Stamford, CT. No work is proposed within the flood plain area. This discharge point shall be referenced throughout the report as Design Point 1 (DP-1).

Along the northern property line, 2.70 acres of the site is within a different catchment area that drains to a pair of 36" culverts that also discharge under Long Ridge Road and ultimately reach the Rippowam River. The majority of this drainage area is offsite to the north and consists of 501.9 acres of developed land. This area drains to an existing stream that cuts across the northeast corner of the site, under the existing driveway, before entering the 2-36" culverts. The point at which the 36" culverts leave the site is referenced in this report as Design Point 2 (DP-2). There is no work proposed within the small on-site area within Drainage Area 2 and, thus, the stormwater runoff to DP-2 is the same under existing and proposed conditions.

The existing storm drainage system on site consists mainly of catch basins, manholes, and piping. There is little area for stormwater infiltration or water quality treatment prior to discharge to the existing on-site pond. The site is served by public water supply, sanitary sewer, and gas in Long Ridge Road.

Pre- and post-development drainage area mapping for the analyzed design points is included in this report in Appendix A.

The project site is located within the middle subwatershed of the Rippowam River Subregional Drainage Basin. The Rippowam River watershed area is approximately 30.5 square miles in size. It is located within the Southwest Western Complex Regional Drainage Basin in the Southwest Coast Major Basin.

4. Proposed Site Conditions

Project Type & General Design Criteria

The current proposal is for the construction of two multi-family residential buildings, with a total footprint of approximately 151,000 SF, which closely mimics the footprint of the existing commercial building and parking structure. The existing access drive will be maintained, while the parking areas and sidewalks serving the proposed buildings will be removed and replaced to match the proposed building elevations and required parking configuration. The proposed improvements will take place on approximately 13.2 acres of the property, mainly within the area that is already developed. The existing impervious coverage on the site will increase by 24,496 SF from 360,066 SF under existing conditions to 384,562 SF under proposed conditions. Based upon the flowchart in "Standard 1: Runoff and Pollutant Reduction", this project is classified as a non-linear redevelopment project disturbing over ½ acre and with a proposed increase in the directly connected impervious area (DCIA). Therefore, a "full" Stormwater Management Report, as defined on Page 25 of the City of Stamford Stormwater Drainage

Manual (Drainage Manual), is required. The project must, and does, comply with Standards 1 through 5 of the Drainage Manual. In addition, because the existing DCIA covers approximately 32.7% of the property area, the project will be required to infiltrate the full (100%) Water Quality Volume (WQV), as defined by the CT DEEP Stormwater Quality Manual.

Summary of Low Impact Design (LID) Site Constraints

The Drainage Manual highly encourages the use of Low Impact Design (LID) measures to retain, infiltrate, and treat the stormwater runoff from a project site. A project's ability to incorporate such LID measures is contingent upon existing site conditions and constraints but should be incorporated to the extent practicable to satisfy the conditions of the Drainage Manual. A map showing the site constraints and the proposed LID measures is included in Appendix M.

For the proposed re-development projects, the LID constraints are mainly due to existing development on the site such as buildings, parking areas and driveways, existing utility and storm drainage infrastructure, and previous re-grading of the site. The project site has a significant amount of impervious area and an extensive storm drainage system that consists mainly of catch basins, manholes, and piping to convey, but not treat, stormwater runoff. To the extent practicable, the proposed design incorporates LID measures to promote stormwater infiltration while also maintaining the use of as much of the existing infrastructure as possible. This limits overall land disturbance, disturbance of steep slopes, and product waste.

Summary of Proposed Stormwater Treatment Practices

Several stormwater management practices have been incorporated into the proposed project design to meet Standards 1 and 2 of the Design Manual. The proposed stormwater management system is designed to mitigate post development stormwater flow rates and runoff volume, as well as increase water quality, to the existing pond and down-gradient properties. Non-structural practices were incorporated into the design where possible and include limiting clearing/grading to the already developed area of the site to the extent practicable, limiting the disturbance of steep slopes, re-utilizing existing stormwater and utility infrastructure to reduce product waste, and preserving the natural areas on the site. The structural components of the stormwater management system include the installation of two (2) subsurface detention/infiltration chamber systems, two (2) infiltration/retention basins, four (4) subsurface infiltration systems for rooftop runoff, and four (4) hydrodynamic separators for pre-treatment. Drainage area mapping showing the catchment areas to each of the stormwater management areas is included in this report in Appendix A and a detailed description of each system is below:

- **Subsurface Detention/Infiltration Chamber Systems**

Due to topographic and area constraints, subsurface detention/infiltration is proposed to treat the stormwater runoff from the south building (Buildings 3 and 4) rooftop and parking areas. Stormwater from this catchment area will be directed into two subsurface chamber systems prior to discharging to the on-site storm drainage system. Underground infiltration systems are considered a primary treatment measure by the CT DEEP and should be designed with additional pre-treatment measures, which are outlined further in this section.

Infiltration System B1 consists of 165 units of 38" tall Cultec R-902HD chambers. The Water Quality Volume (WQV) for the catchment area is retained in the first 18" of the chamber height, below the outlet invert. The chambers will infiltrate the WQV and drain completely between storm events. The additional 30" of storage above the outlet invert is utilized for detention and peak flow rate attenuation. Infiltration System B2 consists of 240 units of 48" tall Cultec R-902HD chambers. In this system, the first 12" are utilized for WQV storage/infiltration and the upper 36" for detention and peak flow rate reduction. Water Quality Volume calculations can be found in Appendix D of this report. For the HydroCAD models of existing and proposed conditions showing the peak flow rate calculations refer to Appendices C and D.

- **Infiltration Basins**

Two infiltration basins are proposed in the central area of the site. These basins are designed in accordance with the CT Stormwater Quality Manual and are intended to capture and infiltrate stormwater during and shortly after a storm event. They are designed to drain fully within 48 hours after a storm event and not hold a permanent pool of water. The bottom of the infiltration basins will be surfaced and graded in accordance with the Stormwater Quality Manual and will incorporate vegetated cover to promote filtration and nutrient uptake.

Rooftop and driveway runoff currently enters the existing storm drainage system and the on-site wet pond without pre-treatment. The proposed improvements include re-direction of this existing drainage piping into the proposed Infiltration Basins to provide retention, infiltration, and treatment prior to flowing to the existing pond and, ultimately, to the Rippowam River.

Infiltration Basin B3 retains runoff from the discharge of subsurface chamber areas B1 and B2 as well as runoff from a portion of the driveway and parking areas serving Buildings 1 and 2 (north building). Infiltration Basin B4 captures runoff from the remaining parking area and access drive to the north building.

The infiltration basins have been designed to retain and infiltrate 100% of the Water Quality Volume, as defined by the CT DEEP Stormwater Quality Manual, below the outlet invert. The outlet inverts are set 18-24" above the basin bottoms. Water Quality Volume and basin sizing calculations can be found in Appendix E of this report. The basins have additional detention storage above the outlet invert elevation, which is included in the HydroCAD modeling for the site showing the reduction in peak flow rates from existing to proposed conditions. Refer to Appendix C and D for existing and proposed HydroCAD models for all required design storms.

- **Subsurface Infiltration Chambers for Rooftop Runoff**

Four underground infiltration systems are proposed to collect the stormwater runoff from the north building (Buildings 1 and 2). Each of the four (4) infiltration systems consist of 42 units of Cultec R-360HD chambers. These chamber systems have been designed to retain and infiltrate the full WQV for the rooftop area. In larger storm events, the excess flow will discharge through the emergency outlet back into the storm drainage system. These infiltration chambers are included in both the WQV calculations (Appendix E) and the HydroCAD model (Appendices C and D). Rooftop runoff is generally considered clean water by the CT DEEP and, therefore, does not require pre-treatment before prior to infiltration.

- **Hydrodynamic Separators (Pre-Treatment)**

An essential component of an effective stormwater management system is pre-treatment of runoff prior to discharge to an infiltration or detention basin. The pre-treatment reduces the amount of total suspended solids, floatable, and oils/grease and allows the infiltration system to function at its highest capacity. There are four (4) hydrodynamic separators included in the project design as pre-treatment measures. They are incorporated in the drainage manholes/catch basins just upstream of Infiltration Chamber Systems B1 and B2, as well as upstream of Infiltration Basins B3 and B4. The hydrodynamic separator units are designed to remove in excess of 80% of total suspended solids (TSS) and provide oil/grease separation to meet the standards of the CT DEEP Stormwater Quality Manual and the Drainage Manual. The design also

allows for conveyance of the full 25-year storm event runoff without the need for a bypass system or off-line separator. There is currently no water quality treatment provided in the on-site storm drainage system. Sizing calculations for the hydrodynamic separators can be found in Appendix F of this report.

5. Compliance with Stormwater Management Standards

Standard I. Runoff and Pollutant Reduction

- A. The stormwater treatment practices were designed to meet the retention and treatment requirements from the flow chart on Page 5 of the Stormwater Drainage Manual. This was achieved by dividing up the overall drainage area into subcatchment areas that are more easily treated by the various systems proposed throughout the site. The subsurface infiltration chambers and the infiltration basins were designed to retain and infiltrate 100% of the water quality volume. The hydrodynamic separators were included as pre-treatment to further enhance the water quality of the stormwater runoff. Soil mapping for the project site shows that the underlying soils in non-impervious areas are classified as a Type B Sandy Loam/Loam. Infiltration rates were taken from the Rawls infiltration rates listed in Table 5-1 on Page 22 of the Drainage Manual.
- B. N/A
- C. The proposed development has been primarily limited to the area already within the existing development. Care has been taken to minimize work outside of the currently developed areas to protect natural buffers, steep slopes, and landscaping. The limits of the construction area are noted on the plans and will be demarcated the field using silt fence and construction fencing. This will ensure that construction activities stay within the approved construction area. At the end of construction, all disturbed areas that are not paved will be seeded to re-establish a stable vegetated surface.
- D. Noted. Every effort has been taken to comply with City of Stamford regulations and standards and City comments will be incorporated into the design as required throughout the review and approval process.
- E. The proposed stormwater treatment practices, especially in a sequential treatment train as designed, provide in excess of the required 80% of TSS removal. The hydrodynamic separators provide additional storage for oils/grease and floatables. Additionally, the

infiltration basins provide vegetated surfaces for nutrient removal and groundwater recharge.

- F. The proposed design of the project minimizes the disturbance of existing natural features by limiting the construction disturbance mainly to the previously developed area. This minimizes compaction of natural soils outside of the development, protects natural buffers and landscaping, minimizes disturbance to existing steep slopes, and reduces the potential for erosion from the project site. Care shall be taken to leave existing pavement in place during construction until such time as it is to be replaced to minimize erodible soils within the construction area.

The proposed stormwater management system greatly enhances the stormwater treatment from the property. By installing the systems described above in accordance with City and CTDEEP standards and recommendations, water quality to the existing pond and down-gradient Rippowam River will be increased post-development.

Standard II. Peak Flow Control

- A. Stream channel protection is intended to decrease impacts to down-gradient channel beds by increased urbanization upstream. Per the CT Stormwater Quality Manual, there are several limitations to achieving the stream channel protection standard of reducing the 2-year post-development runoff to less than 50% of the pre-development runoff. According to the manual, the stream channel protection criterion may not apply to sites that discharge to a large receiving water body and where the development area is less than 5% of the watershed area upstream. This is the case for the proposed project, where the site discharges across the street to the Rippowam River, which has an upstream watershed area of greater than 30.5 square miles (19,520 acres). The subject property contains 25.26 acres, roughly 0.13% of the watershed area. In this instance, erosion of down-gradient stream channels is not anticipated due to the proximity of the project site to the large river below and the relatively small size in comparison to the overall watershed.
- B. Stormwater conveyance protection on the site is provided catch basins, drainage manholes, and piping (proposed and existing to remain as noted). The pipe sizes have been analyzed to convey the 25-year storm event as required by the City of Stamford Drainage Manual. The overall watershed was subdivided into catchment areas to determine the stormwater runoff to each catch basin. Inlet control capacity was also checked at each structure. The catch basin and pipe sizing calculations are in

accordance with Section 4 of the Drainage Manual and are included in Appendix G of this report. Outlet protection in the form of a riprap energy dissipator is provided at the discharge point into Infiltration Basins B3 and B4 per Section 4.7 of the Drainage Manual. For outlet protection calculations refer to Appendix H.

- C. The post-development peak flow rates from the 1-, 2-, 5-, 10-, 25-, and 50-year storm events are mitigated to under pre-development conditions at all design points. The 100-year storm event increases by approximately 0.5 cfs to DP-1 but is able to be conveyed by the down-gradient culvert and does not negatively impact the function of the Rippowam River below.

The primary method of predicting the surface water runoff rates utilized in this report is a computer program entitled HydroCAD V10 Stormwater Modeling System. HydroCAD combines methodology of technical release No. 55 (TR-55) "Urban Hydrology for Small Watersheds" and technical release No. 20 (TR-20) "Project Formulation-Hydrology". Both TR-55 & TR-20 were originally developed by the USDA Soil Conservation Service (SCS).

The HydroCAD program forecasts the rate of surface water runoff based upon several factors, including information on land use, vegetation, watershed areas, soil types, time of concentration, rainfall data, storage volumes and hydraulic capacities of structures. The program predicts the amount of runoff as a function of time.

Rainfall events with recurrence frequency of 1-, 2-, 5-, 10-, 25-, 50- and 100 years were utilized as input data. NOAA's National Weather Service Center has developed storm events to model extreme precipitation data in New England. Precipitation data is taken from the latest NOAA Atlas 14 Point Precipitation Frequency Estimates and is included in this report in Appendix B.

Soil types in the watershed were determined from the USDA's NRCS Web Soil Survey as mentioned previously. The soil types and hydrologic group are included in Appendix I of this report.

Refer to Appendix C and D for existing and proposed HydroCAD model computations for all required design storms. The following peak flows were obtained from the hydrology analysis.

Table 1. Existing vs. Proposed Peak Flows (Design Point 1)

Return Period (Years)	Existing Peak Flow Rate (cfs)	Proposed Peak Flow Rate (cfs)	Change (cfs)	Percent Change (%)
1	21.15	17.31	-3.84	-18.2%
2	32.97	30.29	-2.68	-8.1%
5	49.31	47.63	-1.68	-3.4%
10	77.90	74.11	-3.79	-4.9%
25	132.15	130.53	-1.62	-1.2%
50	171.46	171.39	-0.07	-0.04%
100	210.04	210.51	+0.47	+0.2%

Table 2. Existing vs. Proposed Peak Flows (Design Point 2)

Return Period (Years)	Existing Peak Flow Rate (cfs)	Proposed Peak Flow Rate (cfs)	Change (cfs)	Percent Change (%)
1	0.64	0.64	0	0
2	1.32	1.32	0	0
5	2.74	2.74	0	0
10	4.10	4.10	0	0
25	6.15	6.15	0	0
50	7.79	7.79	0	0
100	9.60	9.60	0	0

- D. The outlet structures from the proposed Infiltration Basins (B3 and B4) have been designed to convey the 100-year storm event discharge without damage to down-gradient systems or properties.

- E. Detention is proposed within the two subsurface detention/infiltration chamber systems (B1 and B2) and within Infiltration Basins B3 and B4. The detention system design meets the requirements in Section 4 of the Drainage Manual. The setbacks, grading limits, and berm elevation are in accordance with the regulations. These detention systems discharge to an existing on-site wet pond that has twin 24" culverts that exit the site under Long Ridge Road. The existing pond and 24" culverts were included in the HydroCAD model to show the effect of the detention on the existing pond and to demonstrate adequate capacity of the 24" culverts under Long Ridge Road.

Standard III. Construction Erosion and Sediment Control

- A. Soil erosion and sediment controls are measures that are used to reduce the amount of soil particles that are carried from a land area and deposited in receiving waters.

Measures will be maintained during and after the construction activity, until final stabilization of the soil is accomplished. Upon final stabilization of disturbed areas, all temporary soil erosion and sediment control measures will be removed.

The soil and erosion control plan has been developed in accordance with the CT DEEP 2002 Connecticut Guidelines for Soil and Erosion Control, the City of Stamford regulations, and the CT DEEP Stormwater Quality Manual. The proposal includes extensive soil and erosion control measures including both structural control practices and soil stabilization practices of temporary and permanent natures.

Structural control practices divert flows from exposed soils, store water flow, or otherwise limit runoff from exposed areas of the site. Examples of these practices that are incorporated into the Erosion & Sedimentation Control Plan (E&S Plan) for the site include stabilized construction entrances, silt fence, and material stockpiles. Haybales will be utilized around the proposed catch basins and along the toe of critical slopes.

An additional goal of the E&S plan is to maintain separation of clean runoff from runoff within the construction area using temporary diversions. These diversions prevent clean runoff from traveling through a disturbed area and mixing with runoff from the construction site and reduce the burden on the Temporary Sediment Traps as well as maintain the water quality of the off-site runoff.

Due to its size, the project will also register with CT DEEP to obtain a General Permit for the Discharge of Stormwater and Dewatering Wastewaters from Construction Activities.

Standard IV. Operation and Maintenance

- A. A Standard City of Stamford Drainage Maintenance Agreement shall be executed with the Environmental Protection Board. A draft agreement is included in this report in Appendix J.
- B. The permitting plans include detailed descriptions of inspection and maintenance requirements both during and post-construction. These include inspection and maintenance of all components of the proposed stormwater management system including, but not limited to, catch basins and piping, hydrodynamic separators, and infiltration basins. Additional information may be added to the construction plan set as required by the City during the review and approval process.

Standard V. Stormwater Management Report

- A. This document and included appendices serve as the required Stormwater Management Report.
- B. Based on the above information, the proposed improvements are designed in accordance with the City of Stamford Stormwater Drainage Manual and will not adversely impact adjacent or downstream properties or City-owned drainage facilities.


This report was prepared by:

Brian Baker, P.E.
Civil 1
43 Sherman Hill Road
Woodbury, CT 06798
203-266-0778
brian@civil1.com

For:
Building & Land Technology
100 Washington Blvd.
Suite 200
Stamford, CT 06902



SECTION II
APPENDICES

Appendix A - Drainage Area Maps



NO.	REVISION	DATE

Previous Editions Obsolete



**EXISTING DRAINAGE BASIN
AREA MAP**


**BUILDING AND LAND
TECHNOLOGY**
100 WASHINGTON BLVD.
SUITE 200
STAMFORD, CT 06902

800 LONG RIDGE ROAD

STAMFORD CONNECTICUT

CIVIL C1
CORNERSTONE PROFESSIONAL PARK, SUITE D-101
43 SHERMAN HILL ROAD
WOODBURY (203) 266-0778 CONNECTICUT

DRAWING NO. 4084 DAMAP
SCALE: 1" = 300'
DATE: 29 SEP 23
PROJECT: 4084
DRAWING NO.: 4084 DAMAP
1 OF 1



PR-DA1-A (TO 60" CULVERT)
82.15 ACRES

PR-DA2 - ON-SITE
2.70 ACRES

PR-DA1-C
3.93 ACRES

DP-2: 2-36" RCP

DP-1: 2-24" RCP

SITE

PR DA 1B1

PR DA 1B2

PR DA 1B3

PR DA 1B4


ROOF1

ROOF2

ROOF3


ROOF4

PR DA 1BND



NO.	REVISION	DATE

Previous Editions Obsolete



**PROPOSED DRAINAGE BASIN
AREA MAP**

**BUILDING AND LAND
TECHNOLOGY**
100 WASHINGTON BLVD.
SUITE 200
STAMFORD, CT 06902

800 LONG RIDGE ROAD

STAMFORD CONNECTICUT

CIVIL C1
CORNERSTONE PROFESSIONAL PARK, SUITE D-101
43 SHERMAN HILL ROAD
WOODBURY (203) 266-0778 CONNECTICUT

DRAWING NO.	4084 DAMAP
DATE	29 SEP 23
SCALE	1" = 300'
DRAWING NO.	4084 DAMAP
1 OF 1	

Appendix B - NOAA Precipitation Data



NOAA Atlas 14, Volume 10, Version 3
 Location name: Stamford, Connecticut, USA*
 Latitude: 41.0967°, Longitude: -73.5665°
 Elevation: 152 ft**
 * source: ESRI Maps
 ** source: USGS



POINT PRECIPITATION FREQUENCY ESTIMATES

Sanja Perica, Sandra Pavlovic, Michael St. Laurent, Carl Trypaluk, Dale Unruh, Orlan Wilhite

NOAA, National Weather Service, Silver Spring, Maryland

[PF_tabular](#) | [PF_graphical](#) | [Maps & aerials](#)

PF tabular





PDS-based point precipitation frequency estimates with 90% confidence intervals (in inches)¹										
Duration	Average recurrence interval (years)									
	1	2	5	10	25	50	100	200	500	1000
5-min	0.367 (0.279-0.470)	0.426 (0.323-0.545)	0.522 (0.394-0.670)	0.602 (0.452-0.776)	0.711 (0.520-0.945)	0.794 (0.570-1.07)	0.880 (0.615-1.22)	0.973 (0.651-1.38)	1.10 (0.712-1.60)	1.21 (0.763-1.78)
10-min	0.520 (0.395-0.665)	0.603 (0.457-0.772)	0.739 (0.559-0.949)	0.852 (0.641-1.10)	1.01 (0.736-1.34)	1.12 (0.807-1.52)	1.25 (0.871-1.73)	1.38 (0.922-1.95)	1.56 (1.01-2.27)	1.71 (1.08-2.52)
15-min	0.612 (0.464-0.783)	0.710 (0.538-0.909)	0.870 (0.658-1.12)	1.00 (0.754-1.29)	1.18 (0.866-1.58)	1.32 (0.950-1.79)	1.47 (1.02-2.03)	1.62 (1.08-2.29)	1.84 (1.19-2.67)	2.01 (1.27-2.97)
30-min	0.858 (0.651-1.10)	0.995 (0.754-1.27)	1.22 (0.922-1.56)	1.41 (1.06-1.81)	1.66 (1.21-2.21)	1.86 (1.33-2.50)	2.06 (1.44-2.85)	2.27 (1.52-3.21)	2.56 (1.66-3.72)	2.80 (1.77-4.12)
60-min	1.10 (0.837-1.41)	1.28 (0.970-1.64)	1.57 (1.19-2.02)	1.81 (1.36-2.33)	2.14 (1.56-2.84)	2.39 (1.72-3.22)	2.65 (1.85-3.66)	2.92 (1.95-4.13)	3.29 (2.13-4.78)	3.58 (2.27-5.28)
2-hr	1.42 (1.09-1.81)	1.67 (1.28-2.12)	2.07 (1.58-2.64)	2.40 (1.82-3.08)	2.86 (2.10-3.78)	3.21 (2.32-4.30)	3.57 (2.51-4.92)	3.96 (2.66-5.56)	4.50 (2.92-6.50)	4.94 (3.14-7.25)
3-hr	1.64 (1.26-2.08)	1.94 (1.48-2.45)	2.42 (1.84-3.07)	2.81 (2.14-3.58)	3.36 (2.48-4.43)	3.77 (2.73-5.05)	4.20 (2.97-5.78)	4.68 (3.15-6.54)	5.35 (3.48-7.69)	5.90 (3.75-8.61)
6-hr	2.08 (1.60-2.61)	2.46 (1.90-3.10)	3.10 (2.38-3.91)	3.62 (2.77-4.58)	4.34 (3.23-5.69)	4.88 (3.56-6.50)	5.45 (3.88-7.48)	6.09 (4.12-8.48)	7.02 (4.58-10.0)	7.78 (4.96-11.3)
12-hr	2.58 (2.00-3.22)	3.07 (2.39-3.84)	3.88 (3.01-4.86)	4.55 (3.51-5.73)	5.47 (4.10-7.13)	6.16 (4.53-8.16)	6.89 (4.94-9.41)	7.73 (5.24-10.7)	8.94 (5.85-12.7)	9.95 (6.36-14.3)
24-hr	3.04 (2.38-3.77)	3.66 (2.86-4.54)	4.67 (3.65-5.82)	5.51 (4.28-6.89)	6.67 (5.03-8.65)	7.54 (5.58-9.94)	8.46 (6.10-11.5)	9.54 (6.50-13.1)	11.1 (7.31-15.7)	12.5 (8.01-17.9)
2-day	3.41 (2.69-4.20)	4.17 (3.29-5.14)	5.41 (4.26-6.69)	6.44 (5.04-8.00)	7.86 (5.98-10.2)	8.92 (6.66-11.7)	10.1 (7.33-13.7)	11.4 (7.81-15.6)	13.5 (8.90-18.9)	15.3 (9.85-21.7)
3-day	3.69 (2.93-4.53)	4.52 (3.58-5.56)	5.89 (4.65-7.25)	7.02 (5.51-8.68)	8.57 (6.54-11.0)	9.72 (7.28-12.7)	11.0 (8.02-14.9)	12.5 (8.55-17.0)	14.8 (9.76-20.6)	16.8 (10.8-23.7)
4-day	3.96 (3.15-4.84)	4.84 (3.84-5.92)	6.27 (4.97-7.70)	7.47 (5.88-9.21)	9.11 (6.97-11.7)	10.3 (7.75-13.5)	11.6 (8.53-15.7)	13.2 (9.08-17.9)	15.7 (10.3-21.8)	17.7 (11.4-25.0)
7-day	4.73 (3.79-5.76)	5.69 (4.55-6.94)	7.26 (5.79-8.87)	8.57 (6.79-10.5)	10.4 (7.96-13.2)	11.7 (8.81-15.2)	13.1 (9.63-17.6)	14.8 (10.2-20.0)	17.4 (11.5-24.0)	19.5 (12.6-27.4)
10-day	5.49 (4.41-6.66)	6.50 (5.22-7.89)	8.16 (6.53-9.94)	9.54 (7.59-11.7)	11.4 (8.81-14.5)	12.9 (9.70-16.6)	14.4 (10.5-19.1)	16.1 (11.1-21.6)	18.7 (12.4-25.7)	20.8 (13.5-29.1)
20-day	7.74 (6.26-9.32)	8.89 (7.18-10.7)	10.8 (8.67-13.0)	12.3 (9.86-15.0)	14.5 (11.2-18.1)	16.1 (12.2-20.4)	17.8 (13.0-23.2)	19.6 (13.6-26.0)	22.0 (14.7-30.1)	24.0 (15.6-33.3)
30-day	9.58 (7.79-11.5)	10.8 (8.79-13.0)	12.9 (10.4-15.5)	14.5 (11.7-17.6)	16.9 (13.1-21.0)	18.6 (14.1-23.5)	20.4 (14.9-26.4)	22.3 (15.5-29.5)	24.7 (16.5-33.6)	26.5 (17.3-36.7)
45-day	11.8 (9.67-14.1)	13.2 (10.8-15.8)	15.4 (12.5-18.5)	17.2 (13.9-20.7)	19.8 (15.4-24.4)	21.7 (16.5-27.2)	23.6 (17.3-30.3)	25.5 (17.9-33.6)	27.9 (18.7-37.8)	29.7 (19.4-40.9)
60-day	13.7 (11.2-16.3)	15.1 (12.4-18.1)	17.5 (14.3-20.9)	19.4 (15.8-23.3)	22.1 (17.3-27.2)	24.2 (18.4-30.2)	26.3 (19.2-33.4)	28.2 (19.8-37.0)	30.6 (20.6-41.3)	32.3 (21.1-44.4)

¹ Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS). Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values. Please refer to NOAA Atlas 14 document for more information.

[Back to Top](#)

PF graphical


PDS-based depth-duration-frequency (DDF) curves
 Latitude: 41.0967°, Longitude: -73.5665°




[Back to Top](#)

Maps & aerials

Small scale terrain



Large scale terrain



Large scale map



Large scale aerial




[Back to Top](#)


[US Department of Commerce](#)
[National Oceanic and Atmospheric Administration](#)
[National Weather Service](#)
[National Water Center](#)
1325 East West Highway
Silver Spring, MD 20910
Questions?: HDSC.Questions@noaa.gov

[Disclaimer](#)



Appendix C – Existing Conditions HydroCAD Routing



EXISTING POND



EX DP1



Area Listing (selected nodes)

Area (acres)	CN	Description (subcatchment-numbers)
42.920	68	1 acre lots, 20% imp, HSG B (EX-DA 1A, EX-DA 1B)
27.890	79	1 acre lots, 20% imp, HSG C (EX-DA 1A, EX-DA 1B)
6.410	61	>75% Grass cover, Good, HSG B (EX-DA 1A, EX-DA 1B, EX-DA 1C)
0.270	74	>75% Grass cover, Good, HSG C (EX-DA 1A)
8.090	98	Paved parking, HSG B (EX-DA 1A, EX-DA 1B)
0.620	98	Paved parking, HSG C (EX-DA 1A)
0.900	98	Water Surface (EX-DA 1C)
18.020	55	Woods, Good, HSG B (EX-DA 1A, EX-DA 1B, EX-DA 1C)
1.450	70	Woods, Good, HSG C (EX-DA 1A)
106.570	71	TOTAL AREA

Soil Listing (selected nodes)

Area (acres)	Soil Group	Subcatchment Numbers
0.000	HSG A	
75.440	HSG B	EX-DA 1A, EX-DA 1B, EX-DA 1C
30.230	HSG C	EX-DA 1A, EX-DA 1B
0.000	HSG D	
0.900	Other	EX-DA 1C
106.570		TOTAL AREA

Ground Covers (selected nodes)

HSG-A (acres)	HSG-B (acres)	HSG-C (acres)	HSG-D (acres)	Other (acres)	Total (acres)	Ground Cover	Subcatchment Numbers
0.000	42.920	27.890	0.000	0.000	70.810	1 acre lots, 20% imp	EX-DA 1A, EX-DA 1B
0.000	6.410	0.270	0.000	0.000	6.680	>75% Grass cover, Good	EX-DA 1A, EX-DA 1B, EX-DA 1C
0.000	8.090	0.620	0.000	0.000	8.710	Paved parking	EX-DA 1A, EX-DA 1B
0.000	0.000	0.000	0.000	0.900	0.900	Water Surface	EX-DA 1C
0.000	18.020	1.450	0.000	0.000	19.470	Woods, Good	EX-DA 1A, EX-DA 1B, EX-DA 1C
0.000	75.440	30.230	0.000	0.900	106.570	TOTAL AREA	

Summary for Subcatchment EX-DA 1A: EX-DA 1A

Runoff = 23.39 cfs @ 12.96 hrs, Volume= 4.400 af, Depth> 0.64"
 Routed to Pond EX-POND : EXISTING POND


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 1-yr Rainfall=3.04"

Area (ac)	CN	Description
40.280	68	1 acre lots, 20% imp, HSG B
27.540	79	1 acre lots, 20% imp, HSG C
0.180	98	Paved parking, HSG B
11.690	55	Woods, Good, HSG B
0.120	61	>75% Grass cover, Good, HSG B
0.620	98	Paved parking, HSG C
1.450	70	Woods, Good, HSG C
0.270	74	>75% Grass cover, Good, HSG C
82.150	70	Weighted Average
67.786		82.51% Pervious Area
14.364		17.49% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
49.3	200	0.0100	0.07		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
0.8	130	0.0200	2.87		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
5.4	200	0.0150	0.61		Shallow Concentrated Flow, Shallow Concentrated Forest Woodland Kv= 5.0 fps
3.4	630	0.0230	3.08		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
4.6	2,300	0.0510	8.39	83.90	Channel Flow, Channel Flow Wooded Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.040 Winding stream, pools & shoals
63.5	3,460	Total			

Subcatchment EX-DA 1A: EX-DA 1A

Hydrograph



Summary for Subcatchment EX-DA 1B: EX-DA 1B

Runoff = 13.17 cfs @ 12.42 hrs, Volume= 1.522 af, Depth> 0.89"
 Routed to Pond EX-POND : EXISTING POND


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 1-yr Rainfall=3.04"

Area (ac)	CN	Description
2.640	68	1 acre lots, 20% imp, HSG B
0.350	79	1 acre lots, 20% imp, HSG C
7.910	98	Paved parking, HSG B
3.650	55	Woods, Good, HSG B
5.940	61	>75% Grass cover, Good, HSG B
20.490	75	Weighted Average
11.982		58.48% Pervious Area
8.508		41.52% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
22.5	150	0.0400	0.11		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
3.8	950	0.0660	4.14		Shallow Concentrated Flow, Shallow Concentrated Woods Unpaved Kv= 16.1 fps
1.1	910	0.0660	14.15	44.44	Pipe Channel, RCP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.017 Concrete sewer w/manholes & inlets
27.4	2,010	Total			

Subcatchment EX-DA 1B: EX-DA 1B

Hydrograph



Summary for Subcatchment EX-DA 1C: EX-DA 1C


Runoff = 1.56 cfs @ 12.17 hrs, Volume= 0.152 af, Depth> 0.46"
 Routed to Pond EX-POND : EXISTING POND

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 1-yr Rainfall=3.04"

Area (ac)	CN	Description
* 0.900	98	Water Surface
2.680	55	Woods, Good, HSG B
0.350	61	>75% Grass cover, Good, HSG B
3.930	65	Weighted Average
3.030		77.10% Pervious Area
0.900		22.90% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
8.1	90	0.1833	0.18		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
1.3	140	0.1290	1.80		Shallow Concentrated Flow, Shallow Concentrated Woods Woodland Kv= 5.0 fps
0.3	210	0.0660	12.73	127.25	Channel Flow, Stream Channel Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.030 Stream, clean & straight
9.7	440	Total			

Subcatchment EX-DA 1C: EX-DA 1C



Summary for Pond EX-POND: EXISTING POND

Inflow Area = 106.570 ac, 22.31% Impervious, Inflow Depth > 0.68" for 1-yr event
 Inflow = 29.51 cfs @ 12.82 hrs, Volume= 6.074 af
 Outflow = 21.15 cfs @ 13.37 hrs, Volume= 5.597 af, Atten= 28%, Lag= 32.7 min
 Primary = 21.15 cfs @ 13.37 hrs, Volume= 5.597 af
 Routed to Link EX DP-1 : EX DP1

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 73.30' @ 13.37 hrs Surf.Area= 0.994 ac Storage= 1.452 af

Plug-Flow detention time= 63.3 min calculated for 5.597 af (92% of inflow)
 Center-of-Mass det. time= 39.9 min (903.0 - 863.1)

Volume	Invert	Avail.Storage	Storage Description		
#1	71.80'	7.556 af	Existing Pond (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (acres)	Perim. (feet)	Inc.Store (acre-feet)	Cum.Store (acre-feet)	Wet.Area (acres)
71.80	0.938	1,000.1	0.000	0.000	0.938
74.00	1.020	1,016.0	2.153	2.153	1.016
76.00	1.320	1,692.0	2.334	4.487	4.360
78.00	1.760	1,652.0	3.069	7.556	4.617


Device	Routing	Invert	Outlet Devices
#1	Primary	71.80'	24.0" Round Culvert X 2.00 L= 100.0' Ke= 0.500 Inlet / Outlet Invert= 71.80' / 70.00' S= 0.0180 ' S Cc= 0.900 n= 0.011 Concrete pipe, straight & clean, Flow Area= 3.14 sf
#2	Primary	75.75'	12.0' long + 3.0 ' SideZ x 12.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.57 2.62 2.70 2.67 2.66 2.67 2.66 2.64
#3	Primary	76.75'	30.0' long + 3.0 ' SideZ x 30.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63

Primary OutFlow Max=21.14 cfs @ 13.37 hrs HW=73.30' (Free Discharge)

- 1=Culvert (Inlet Controls 21.14 cfs @ 4.17 fps)
- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)
- 3=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Pond EX-POND: EXISTING POND

Hydrograph




Summary for Link EX DP-1: EX DP1

Inflow Area = 106.570 ac, 22.31% Impervious, Inflow Depth > 0.63" for 1-yr event
Inflow = 21.15 cfs @ 13.37 hrs, Volume= 5.597 af
Primary = 21.15 cfs @ 13.37 hrs, Volume= 5.597 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link EX DP-1: EX DP1

Hydrograph



Summary for Subcatchment EX-DA 1A: EX-DA 1A

Runoff = 37.49 cfs @ 12.92 hrs, Volume= 6.708 af, Depth> 0.98"
 Routed to Pond EX-POND : EXISTING POND


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 2-yr Rainfall=3.66"

Area (ac)	CN	Description
40.280	68	1 acre lots, 20% imp, HSG B
27.540	79	1 acre lots, 20% imp, HSG C
0.180	98	Paved parking, HSG B
11.690	55	Woods, Good, HSG B
0.120	61	>75% Grass cover, Good, HSG B
0.620	98	Paved parking, HSG C
1.450	70	Woods, Good, HSG C
0.270	74	>75% Grass cover, Good, HSG C
82.150	70	Weighted Average
67.786		82.51% Pervious Area
14.364		17.49% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
49.3	200	0.0100	0.07		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
0.8	130	0.0200	2.87		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
5.4	200	0.0150	0.61		Shallow Concentrated Flow, Shallow Concentrated Forest Woodland Kv= 5.0 fps
3.4	630	0.0230	3.08		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
4.6	2,300	0.0510	8.39	83.90	Channel Flow, Channel Flow Wooded Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.040 Winding stream, pools & shoals
63.5	3,460	Total			

Subcatchment EX-DA 1A: EX-DA 1A

Hydrograph



Summary for Subcatchment EX-DA 1B: EX-DA 1B

Runoff = 19.46 cfs @ 12.40 hrs, Volume= 2.202 af, Depth> 1.29"
 Routed to Pond EX-POND : EXISTING POND


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 2-yr Rainfall=3.66"

Area (ac)	CN	Description
2.640	68	1 acre lots, 20% imp, HSG B
0.350	79	1 acre lots, 20% imp, HSG C
7.910	98	Paved parking, HSG B
3.650	55	Woods, Good, HSG B
5.940	61	>75% Grass cover, Good, HSG B
20.490	75	Weighted Average
11.982		58.48% Pervious Area
8.508		41.52% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
22.5	150	0.0400	0.11		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
3.8	950	0.0660	4.14		Shallow Concentrated Flow, Shallow Concentrated Woods Unpaved Kv= 16.1 fps
1.1	910	0.0660	14.15	44.44	Pipe Channel, RCP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.017 Concrete sewer w/manholes & inlets
27.4	2,010	Total			

Subcatchment EX-DA 1B: EX-DA 1B

Hydrograph



Summary for Subcatchment EX-DA 1C: EX-DA 1C


Runoff = 2.87 cfs @ 12.16 hrs, Volume= 0.246 af, Depth> 0.75"
 Routed to Pond EX-POND : EXISTING POND

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 2-yr Rainfall=3.66"

Area (ac)	CN	Description
* 0.900	98	Water Surface
2.680	55	Woods, Good, HSG B
0.350	61	>75% Grass cover, Good, HSG B
3.930	65	Weighted Average
3.030		77.10% Pervious Area
0.900		22.90% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
8.1	90	0.1833	0.18		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
1.3	140	0.1290	1.80		Shallow Concentrated Flow, Shallow Concentrated Woods Woodland Kv= 5.0 fps
0.3	210	0.0660	12.73	127.25	Channel Flow, Stream Channel Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.030 Stream, clean & straight
9.7	440	Total			

Subcatchment EX-DA 1C: EX-DA 1C



Summary for Pond EX-POND: EXISTING POND

Inflow Area = 106.570 ac, 22.31% Impervious, Inflow Depth > 1.03" for 2-yr event
 Inflow = 46.72 cfs @ 12.79 hrs, Volume= 9.156 af
 Outflow = 32.97 cfs @ 13.33 hrs, Volume= 8.599 af, Atten= 29%, Lag= 32.8 min
 Primary = 32.97 cfs @ 13.33 hrs, Volume= 8.599 af
 Routed to Link EX DP-1 : EX DP1

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 73.99' @ 13.33 hrs Surf.Area= 1.020 ac Storage= 2.141 af

Plug-Flow detention time= 55.2 min calculated for 8.571 af (94% of inflow)
 Center-of-Mass det. time= 36.5 min (891.1 - 854.6)

Volume	Invert	Avail.Storage	Storage Description		
#1	71.80'	7.556 af	Existing Pond (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (acres)	Perim. (feet)	Inc.Store (acre-feet)	Cum.Store (acre-feet)	Wet.Area (acres)
71.80	0.938	1,000.1	0.000	0.000	0.938
74.00	1.020	1,016.0	2.153	2.153	1.016
76.00	1.320	1,692.0	2.334	4.487	4.360
78.00	1.760	1,652.0	3.069	7.556	4.617


Device	Routing	Invert	Outlet Devices
#1	Primary	71.80'	24.0" Round Culvert X 2.00 L= 100.0' Ke= 0.500 Inlet / Outlet Invert= 71.80' / 70.00' S= 0.0180 '/' Cc= 0.900 n= 0.011 Concrete pipe, straight & clean, Flow Area= 3.14 sf
#2	Primary	75.75'	12.0' long + 3.0 ' SideZ x 12.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.57 2.62 2.70 2.67 2.66 2.67 2.66 2.64
#3	Primary	76.75'	30.0' long + 3.0 ' SideZ x 30.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63

Primary OutFlow Max=32.96 cfs @ 13.33 hrs HW=73.99' (Free Discharge)

- 1=Culvert (Inlet Controls 32.96 cfs @ 5.25 fps)
- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)
- 3=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Pond EX-POND: EXISTING POND

Hydrograph




Summary for Link EX DP-1: EX DP1

Inflow Area = 106.570 ac, 22.31% Impervious, Inflow Depth > 0.97" for 2-yr event
Inflow = 32.97 cfs @ 13.33 hrs, Volume= 8.599 af
Primary = 32.97 cfs @ 13.33 hrs, Volume= 8.599 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link EX DP-1: EX DP1

Hydrograph



Summary for Subcatchment EX-DA 1A: EX-DA 1A

Runoff = 63.57 cfs @ 12.90 hrs, Volume= 11.010 af, Depth> 1.61"
 Routed to Pond EX-POND : EXISTING POND


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 5-yr Rainfall=4.67"

Area (ac)	CN	Description
40.280	68	1 acre lots, 20% imp, HSG B
27.540	79	1 acre lots, 20% imp, HSG C
0.180	98	Paved parking, HSG B
11.690	55	Woods, Good, HSG B
0.120	61	>75% Grass cover, Good, HSG B
0.620	98	Paved parking, HSG C
1.450	70	Woods, Good, HSG C
0.270	74	>75% Grass cover, Good, HSG C
82.150	70	Weighted Average
67.786		82.51% Pervious Area
14.364		17.49% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
49.3	200	0.0100	0.07		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
0.8	130	0.0200	2.87		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
5.4	200	0.0150	0.61		Shallow Concentrated Flow, Shallow Concentrated Forest Woodland Kv= 5.0 fps
3.4	630	0.0230	3.08		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
4.6	2,300	0.0510	8.39	83.90	Channel Flow, Channel Flow Wooded Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.040 Winding stream, pools & shoals
63.5	3,460	Total			

Subcatchment EX-DA 1A: EX-DA 1A

Hydrograph



Summary for Subcatchment EX-DA 1B: EX-DA 1B

Runoff = 30.61 cfs @ 12.39 hrs, Volume= 3.427 af, Depth> 2.01"
 Routed to Pond EX-POND : EXISTING POND


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 5-yr Rainfall=4.67"

Area (ac)	CN	Description
2.640	68	1 acre lots, 20% imp, HSG B
0.350	79	1 acre lots, 20% imp, HSG C
7.910	98	Paved parking, HSG B
3.650	55	Woods, Good, HSG B
5.940	61	>75% Grass cover, Good, HSG B
20.490	75	Weighted Average
11.982		58.48% Pervious Area
8.508		41.52% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
22.5	150	0.0400	0.11		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
3.8	950	0.0660	4.14		Shallow Concentrated Flow, Shallow Concentrated Woods Unpaved Kv= 16.1 fps
1.1	910	0.0660	14.15	44.44	Pipe Channel, RCP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.017 Concrete sewer w/manholes & inlets
27.4	2,010	Total			

Subcatchment EX-DA 1B: EX-DA 1B

Hydrograph



Summary for Subcatchment EX-DA 1C: EX-DA 1C


Runoff = 5.40 cfs @ 12.15 hrs, Volume= 0.428 af, Depth> 1.31"
 Routed to Pond EX-POND : EXISTING POND

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 5-yr Rainfall=4.67"

Area (ac)	CN	Description
* 0.900	98	Water Surface
2.680	55	Woods, Good, HSG B
0.350	61	>75% Grass cover, Good, HSG B
3.930	65	Weighted Average
3.030		77.10% Pervious Area
0.900		22.90% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
8.1	90	0.1833	0.18		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
1.3	140	0.1290	1.80		Shallow Concentrated Flow, Shallow Concentrated Woods Woodland Kv= 5.0 fps
0.3	210	0.0660	12.73	127.25	Channel Flow, Stream Channel Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.030 Stream, clean & straight
9.7	440	Total			

Subcatchment EX-DA 1C: EX-DA 1C



Summary for Pond EX-POND: EXISTING POND

Inflow Area = 106.570 ac, 22.31% Impervious, Inflow Depth > 1.67" for 5-yr event
 Inflow = 78.44 cfs @ 12.76 hrs, Volume= 14.865 af
 Outflow = 49.31 cfs @ 13.40 hrs, Volume= 14.192 af, Atten= 37%, Lag= 38.1 min
 Primary = 49.31 cfs @ 13.40 hrs, Volume= 14.192 af
 Routed to Link EX DP-1 : EX DP1

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 75.46' @ 13.40 hrs Surf.Area= 1.235 ac Storage= 3.793 af

Plug-Flow detention time= 53.9 min calculated for 14.192 af (95% of inflow)
 Center-of-Mass det. time= 39.2 min (883.9 - 844.7)

Volume	Invert	Avail.Storage	Storage Description		
#1	71.80'	7.556 af	Existing Pond (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (acres)	Perim. (feet)	Inc.Store (acre-feet)	Cum.Store (acre-feet)	Wet.Area (acres)
71.80	0.938	1,000.1	0.000	0.000	0.938
74.00	1.020	1,016.0	2.153	2.153	1.016
76.00	1.320	1,692.0	2.334	4.487	4.360
78.00	1.760	1,652.0	3.069	7.556	4.617


Device	Routing	Invert	Outlet Devices
#1	Primary	71.80'	24.0" Round Culvert X 2.00 L= 100.0' Ke= 0.500 Inlet / Outlet Invert= 71.80' / 70.00' S= 0.0180 ' S Cc= 0.900 n= 0.011 Concrete pipe, straight & clean, Flow Area= 3.14 sf
#2	Primary	75.75'	12.0' long + 3.0 ' SideZ x 12.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.57 2.62 2.70 2.67 2.66 2.67 2.66 2.64
#3	Primary	76.75'	30.0' long + 3.0 ' SideZ x 30.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63

Primary OutFlow Max=49.31 cfs @ 13.40 hrs HW=75.46' (Free Discharge)

- 1=Culvert (Inlet Controls 49.31 cfs @ 7.85 fps)
- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)
- 3=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Pond EX-POND: EXISTING POND

Hydrograph




Summary for Link EX DP-1: EX DP1

Inflow Area = 106.570 ac, 22.31% Impervious, Inflow Depth > 1.60" for 5-yr event
Inflow = 49.31 cfs @ 13.40 hrs, Volume= 14.192 af
Primary = 49.31 cfs @ 13.40 hrs, Volume= 14.192 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link EX DP-1: EX DP1



Summary for Subcatchment EX-DA 1A: EX-DA 1A

[47] Hint: Peak is 104% of capacity of segment #5

Runoff = 87.24 cfs @ 12.89 hrs, Volume= 14.963 af, Depth> 2.19"
 Routed to Pond EX-POND : EXISTING POND


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-yr Rainfall=5.51"

Area (ac)	CN	Description
40.280	68	1 acre lots, 20% imp, HSG B
27.540	79	1 acre lots, 20% imp, HSG C
0.180	98	Paved parking, HSG B
11.690	55	Woods, Good, HSG B
0.120	61	>75% Grass cover, Good, HSG B
0.620	98	Paved parking, HSG C
1.450	70	Woods, Good, HSG C
0.270	74	>75% Grass cover, Good, HSG C
82.150	70	Weighted Average
67.786		82.51% Pervious Area
14.364		17.49% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
49.3	200	0.0100	0.07		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
0.8	130	0.0200	2.87		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
5.4	200	0.0150	0.61		Shallow Concentrated Flow, Shallow Concentrated Forest Woodland Kv= 5.0 fps
3.4	630	0.0230	3.08		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
4.6	2,300	0.0510	8.39	83.90	Channel Flow, Channel Flow Wooded Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.040 Winding stream, pools & shoals
63.5	3,460	Total			

Subcatchment EX-DA 1A: EX-DA 1A

Hydrograph



Summary for Subcatchment EX-DA 1B: EX-DA 1B

Runoff = 40.45 cfs @ 12.39 hrs, Volume= 4.522 af, Depth> 2.65"
 Routed to Pond EX-POND : EXISTING POND


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-yr Rainfall=5.51"

Area (ac)	CN	Description
2.640	68	1 acre lots, 20% imp, HSG B
0.350	79	1 acre lots, 20% imp, HSG C
7.910	98	Paved parking, HSG B
3.650	55	Woods, Good, HSG B
5.940	61	>75% Grass cover, Good, HSG B
20.490	75	Weighted Average
11.982		58.48% Pervious Area
8.508		41.52% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
22.5	150	0.0400	0.11		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
3.8	950	0.0660	4.14		Shallow Concentrated Flow, Shallow Concentrated Woods Unpaved Kv= 16.1 fps
1.1	910	0.0660	14.15	44.44	Pipe Channel, RCP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.017 Concrete sewer w/manholes & inlets
27.4	2,010	Total			

Subcatchment EX-DA 1B: EX-DA 1B

Hydrograph



Summary for Subcatchment EX-DA 1C: EX-DA 1C

Runoff = 7.75 cfs @ 12.15 hrs, Volume= 0.600 af, Depth> 1.83"
 Routed to Pond EX-POND : EXISTING POND


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-yr Rainfall=5.51"

Area (ac)	CN	Description
* 0.900	98	Water Surface
2.680	55	Woods, Good, HSG B
0.350	61	>75% Grass cover, Good, HSG B
3.930	65	Weighted Average
3.030		77.10% Pervious Area
0.900		22.90% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
8.1	90	0.1833	0.18		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
1.3	140	0.1290	1.80		Shallow Concentrated Flow, Shallow Concentrated Woods Woodland Kv= 5.0 fps
0.3	210	0.0660	12.73	127.25	Channel Flow, Stream Channel Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.030 Stream, clean & straight
9.7	440	Total			

Subcatchment EX-DA 1C: EX-DA 1C

Hydrograph



Summary for Pond EX-POND: EXISTING POND

Inflow Area = 106.570 ac, 22.31% Impervious, Inflow Depth > 2.26" for 10-yr event
 Inflow = 107.09 cfs @ 12.75 hrs, Volume= 20.085 af
 Outflow = 77.90 cfs @ 13.25 hrs, Volume= 19.323 af, Atten= 27%, Lag= 29.9 min
 Primary = 77.90 cfs @ 13.25 hrs, Volume= 19.323 af
 Routed to Link EX DP-1 : EX DP1

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 76.42' @ 13.25 hrs Surf.Area= 1.408 ac Storage= 5.066 af

Plug-Flow detention time= 52.9 min calculated for 19.323 af (96% of inflow)
 Center-of-Mass det. time= 40.4 min (878.9 - 838.6)


Volume	Invert	Avail.Storage	Storage Description		
#1	71.80'	7.556 af	Existing Pond (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (acres)	Perim. (feet)	Inc.Store (acre-feet)	Cum.Store (acre-feet)	Wet.Area (acres)
71.80	0.938	1,000.1	0.000	0.000	0.938
74.00	1.020	1,016.0	2.153	2.153	1.016
76.00	1.320	1,692.0	2.334	4.487	4.360
78.00	1.760	1,652.0	3.069	7.556	4.617

Device	Routing	Invert	Outlet Devices
#1	Primary	71.80'	24.0" Round Culvert X 2.00 L= 100.0' Ke= 0.500 Inlet / Outlet Invert= 71.80' / 70.00' S= 0.0180 ' S= 0.0180 ' Cc= 0.900 n= 0.011 Concrete pipe, straight & clean, Flow Area= 3.14 sf
#2	Primary	75.75'	12.0' long + 3.0 ' SideZ x 12.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.57 2.62 2.70 2.67 2.66 2.67 2.66 2.64
#3	Primary	76.75'	30.0' long + 3.0 ' SideZ x 30.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63

Primary OutFlow Max=77.87 cfs @ 13.25 hrs HW=76.42' (Free Discharge)
 1=Culvert (Inlet Controls 57.60 cfs @ 9.17 fps)
 2=Broad-Crested Rectangular Weir (Weir Controls 20.28 cfs @ 2.14 fps)
 3=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Pond EX-POND: EXISTING POND

Hydrograph




Summary for Link EX DP-1: EX DP1

Inflow Area = 106.570 ac, 22.31% Impervious, Inflow Depth > 2.18" for 10-yr event
Inflow = 77.90 cfs @ 13.25 hrs, Volume= 19.323 af
Primary = 77.90 cfs @ 13.25 hrs, Volume= 19.323 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link EX DP-1: EX DP1

Hydrograph



Summary for Subcatchment EX-DA 1A: EX-DA 1A

[47] Hint: Peak is 145% of capacity of segment #5

Runoff = 121.83 cfs @ 12.88 hrs, Volume= 20.816 af, Depth> 3.04"
 Routed to Pond EX-POND : EXISTING POND


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 25-yr Rainfall=6.67"

Area (ac)	CN	Description
40.280	68	1 acre lots, 20% imp, HSG B
27.540	79	1 acre lots, 20% imp, HSG C
0.180	98	Paved parking, HSG B
11.690	55	Woods, Good, HSG B
0.120	61	>75% Grass cover, Good, HSG B
0.620	98	Paved parking, HSG C
1.450	70	Woods, Good, HSG C
0.270	74	>75% Grass cover, Good, HSG C
82.150	70	Weighted Average
67.786		82.51% Pervious Area
14.364		17.49% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
49.3	200	0.0100	0.07		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
0.8	130	0.0200	2.87		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
5.4	200	0.0150	0.61		Shallow Concentrated Flow, Shallow Concentrated Forest Woodland Kv= 5.0 fps
3.4	630	0.0230	3.08		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
4.6	2,300	0.0510	8.39	83.90	Channel Flow, Channel Flow Wooded Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.040 Winding stream, pools & shoals
63.5	3,460	Total			

Subcatchment EX-DA 1A: EX-DA 1A

Hydrograph



Summary for Subcatchment EX-DA 1B: EX-DA 1B

[47] Hint: Peak is 123% of capacity of segment #3

Runoff = 54.51 cfs @ 12.38 hrs, Volume= 6.113 af, Depth> 3.58"
 Routed to Pond EX-POND : EXISTING POND


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 25-yr Rainfall=6.67"

Area (ac)	CN	Description
2.640	68	1 acre lots, 20% imp, HSG B
0.350	79	1 acre lots, 20% imp, HSG C
7.910	98	Paved parking, HSG B
3.650	55	Woods, Good, HSG B
5.940	61	>75% Grass cover, Good, HSG B
20.490	75	Weighted Average
11.982		58.48% Pervious Area
8.508		41.52% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
22.5	150	0.0400	0.11		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
3.8	950	0.0660	4.14		Shallow Concentrated Flow, Shallow Concentrated Woods Unpaved Kv= 16.1 fps
1.1	910	0.0660	14.15	44.44	Pipe Channel, RCP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.017 Concrete sewer w/manholes & inlets
27.4	2,010	Total			

Subcatchment EX-DA 1B: EX-DA 1B

Hydrograph



Summary for Subcatchment EX-DA 1C: EX-DA 1C


Runoff = 11.27 cfs @ 12.15 hrs, Volume= 0.860 af, Depth> 2.63"
 Routed to Pond EX-POND : EXISTING POND

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 25-yr Rainfall=6.67"

Area (ac)	CN	Description
* 0.900	98	Water Surface
2.680	55	Woods, Good, HSG B
0.350	61	>75% Grass cover, Good, HSG B
3.930	65	Weighted Average
3.030		77.10% Pervious Area
0.900		22.90% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
8.1	90	0.1833	0.18		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
1.3	140	0.1290	1.80		Shallow Concentrated Flow, Shallow Concentrated Woods Woodland Kv= 5.0 fps
0.3	210	0.0660	12.73	127.25	Channel Flow, Stream Channel Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.030 Stream, clean & straight
9.7	440	Total			

Subcatchment EX-DA 1C: EX-DA 1C



Summary for Pond EX-POND: EXISTING POND

Inflow Area = 106.570 ac, 22.31% Impervious, Inflow Depth > 3.13" for 25-yr event
 Inflow = 148.84 cfs @ 12.74 hrs, Volume= 27.789 af
 Outflow = 132.15 cfs @ 13.04 hrs, Volume= 26.916 af, Atten= 11%, Lag= 17.6 min
 Primary = 132.15 cfs @ 13.04 hrs, Volume= 26.916 af
 Routed to Link EX DP-1 : EX DP1

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 77.03' @ 13.04 hrs Surf.Area= 1.538 ac Storage= 5.952 af

Plug-Flow detention time= 47.5 min calculated for 26.826 af (97% of inflow)
 Center-of-Mass det. time= 36.9 min (868.7 - 831.8)

Volume	Invert	Avail.Storage	Storage Description		
#1	71.80'	7.556 af	Existing Pond (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (acres)	Perim. (feet)	Inc.Store (acre-feet)	Cum.Store (acre-feet)	Wet.Area (acres)
71.80	0.938	1,000.1	0.000	0.000	0.938
74.00	1.020	1,016.0	2.153	2.153	1.016
76.00	1.320	1,692.0	2.334	4.487	4.360
78.00	1.760	1,652.0	3.069	7.556	4.617


Device	Routing	Invert	Outlet Devices
#1	Primary	71.80'	24.0" Round Culvert X 2.00 L= 100.0' Ke= 0.500 Inlet / Outlet Invert= 71.80' / 70.00' S= 0.0180 ' S Cc= 0.900 n= 0.011 Concrete pipe, straight & clean, Flow Area= 3.14 sf
#2	Primary	75.75'	12.0' long + 3.0 ' SideZ x 12.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.57 2.62 2.70 2.67 2.66 2.67 2.66 2.64
#3	Primary	76.75'	30.0' long + 3.0 ' SideZ x 30.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63

Primary OutFlow Max=131.90 cfs @ 13.04 hrs HW=77.03' (Free Discharge)

- 1=Culvert (Inlet Controls 62.19 cfs @ 9.90 fps)
- 2=Broad-Crested Rectangular Weir (Weir Controls 57.82 cfs @ 2.87 fps)
- 3=Broad-Crested Rectangular Weir (Weir Controls 11.89 cfs @ 1.40 fps)

Pond EX-POND: EXISTING POND

Hydrograph




Summary for Link EX DP-1: EX DP1

Inflow Area = 106.570 ac, 22.31% Impervious, Inflow Depth > 3.03" for 25-yr event
Inflow = 132.15 cfs @ 13.04 hrs, Volume= 26.916 af
Primary = 132.15 cfs @ 13.04 hrs, Volume= 26.916 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link EX DP-1: EX DP1

Hydrograph



Summary for Subcatchment EX-DA 1A: EX-DA 1A

[47] Hint: Peak is 177% of capacity of segment #5

Runoff = 148.67 cfs @ 12.87 hrs, Volume= 25.430 af, Depth> 3.71"
 Routed to Pond EX-POND : EXISTING POND


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 50-yr Rainfall=7.54"

Area (ac)	CN	Description
40.280	68	1 acre lots, 20% imp, HSG B
27.540	79	1 acre lots, 20% imp, HSG C
0.180	98	Paved parking, HSG B
11.690	55	Woods, Good, HSG B
0.120	61	>75% Grass cover, Good, HSG B
0.620	98	Paved parking, HSG C
1.450	70	Woods, Good, HSG C
0.270	74	>75% Grass cover, Good, HSG C
82.150	70	Weighted Average
67.786		82.51% Pervious Area
14.364		17.49% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
49.3	200	0.0100	0.07		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
0.8	130	0.0200	2.87		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
5.4	200	0.0150	0.61		Shallow Concentrated Flow, Shallow Concentrated Forest Woodland Kv= 5.0 fps
3.4	630	0.0230	3.08		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
4.6	2,300	0.0510	8.39	83.90	Channel Flow, Channel Flow Wooded Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.040 Winding stream, pools & shoals
63.5	3,460	Total			

Subcatchment EX-DA 1A: EX-DA 1A

Hydrograph



Summary for Subcatchment EX-DA 1B: EX-DA 1B

[47] Hint: Peak is 147% of capacity of segment #3

Runoff = 65.28 cfs @ 12.38 hrs, Volume= 7.350 af, Depth> 4.30"
 Routed to Pond EX-POND : EXISTING POND


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 50-yr Rainfall=7.54"

Area (ac)	CN	Description
2.640	68	1 acre lots, 20% imp, HSG B
0.350	79	1 acre lots, 20% imp, HSG C
7.910	98	Paved parking, HSG B
3.650	55	Woods, Good, HSG B
5.940	61	>75% Grass cover, Good, HSG B
20.490	75	Weighted Average
11.982		58.48% Pervious Area
8.508		41.52% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
22.5	150	0.0400	0.11		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
3.8	950	0.0660	4.14		Shallow Concentrated Flow, Shallow Concentrated Woods Unpaved Kv= 16.1 fps
1.1	910	0.0660	14.15	44.44	Pipe Channel, RCP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.017 Concrete sewer w/manholes & inlets
27.4	2,010	Total			

Subcatchment EX-DA 1B: EX-DA 1B

Hydrograph



Summary for Subcatchment EX-DA 1C: EX-DA 1C


Runoff = 14.05 cfs @ 12.14 hrs, Volume= 1.068 af, Depth> 3.26"
 Routed to Pond EX-POND : EXISTING POND

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 50-yr Rainfall=7.54"

Area (ac)	CN	Description
* 0.900	98	Water Surface
2.680	55	Woods, Good, HSG B
0.350	61	>75% Grass cover, Good, HSG B
3.930	65	Weighted Average
3.030		77.10% Pervious Area
0.900		22.90% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
8.1	90	0.1833	0.18		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
1.3	140	0.1290	1.80		Shallow Concentrated Flow, Shallow Concentrated Woods Woodland Kv= 5.0 fps
0.3	210	0.0660	12.73	127.25	Channel Flow, Stream Channel Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.030 Stream, clean & straight
9.7	440	Total			

Subcatchment EX-DA 1C: EX-DA 1C



Summary for Pond EX-POND: EXISTING POND

Inflow Area = 106.570 ac, 22.31% Impervious, Inflow Depth > 3.81" for 50-yr event
 Inflow = 181.29 cfs @ 12.74 hrs, Volume= 33.848 af
 Outflow = 171.46 cfs @ 12.94 hrs, Volume= 32.895 af, Atten= 5%, Lag= 11.8 min
 Primary = 171.46 cfs @ 12.94 hrs, Volume= 32.895 af
 Routed to Link EX DP-1 : EX DP1

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 77.26' @ 12.94 hrs Surf.Area= 1.590 ac Storage= 6.318 af

Plug-Flow detention time= 44.0 min calculated for 32.895 af (97% of inflow)
 Center-of-Mass det. time= 34.3 min (861.9 - 827.6)

Volume	Invert	Avail.Storage	Storage Description		
#1	71.80'	7.556 af	Existing Pond (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (acres)	Perim. (feet)	Inc.Store (acre-feet)	Cum.Store (acre-feet)	Wet.Area (acres)
71.80	0.938	1,000.1	0.000	0.000	0.938
74.00	1.020	1,016.0	2.153	2.153	1.016
76.00	1.320	1,692.0	2.334	4.487	4.360
78.00	1.760	1,652.0	3.069	7.556	4.617


Device	Routing	Invert	Outlet Devices
#1	Primary	71.80'	24.0" Round Culvert X 2.00 L= 100.0' Ke= 0.500 Inlet / Outlet Invert= 71.80' / 70.00' S= 0.0180 ' S Cc= 0.900 n= 0.011 Concrete pipe, straight & clean, Flow Area= 3.14 sf
#2	Primary	75.75'	12.0' long + 3.0 ' SideZ x 12.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.57 2.62 2.70 2.67 2.66 2.67 2.66 2.64
#3	Primary	76.75'	30.0' long + 3.0 ' SideZ x 30.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63

Primary OutFlow Max=171.23 cfs @ 12.94 hrs HW=77.26' (Free Discharge)

- 1=Culvert (Inlet Controls 63.88 cfs @ 10.17 fps)
- 2=Broad-Crested Rectangular Weir (Weir Controls 76.72 cfs @ 3.08 fps)
- 3=Broad-Crested Rectangular Weir (Weir Controls 30.62 cfs @ 1.91 fps)

Pond EX-POND: EXISTING POND

Hydrograph




Summary for Link EX DP-1: EX DP1

Inflow Area = 106.570 ac, 22.31% Impervious, Inflow Depth > 3.70" for 50-yr event
Inflow = 171.46 cfs @ 12.94 hrs, Volume= 32.895 af
Primary = 171.46 cfs @ 12.94 hrs, Volume= 32.895 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link EX DP-1: EX DP1



Summary for Subcatchment EX-DA 1A: EX-DA 1A

[47] Hint: Peak is 212% of capacity of segment #5

Runoff = 177.76 cfs @ 12.87 hrs, Volume= 30.466 af, Depth> 4.45"
 Routed to Pond EX-POND : EXISTING POND


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 100-yr Rainfall=8.46"

Area (ac)	CN	Description
40.280	68	1 acre lots, 20% imp, HSG B
27.540	79	1 acre lots, 20% imp, HSG C
0.180	98	Paved parking, HSG B
11.690	55	Woods, Good, HSG B
0.120	61	>75% Grass cover, Good, HSG B
0.620	98	Paved parking, HSG C
1.450	70	Woods, Good, HSG C
0.270	74	>75% Grass cover, Good, HSG C
82.150	70	Weighted Average
67.786		82.51% Pervious Area
14.364		17.49% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
49.3	200	0.0100	0.07		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
0.8	130	0.0200	2.87		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
5.4	200	0.0150	0.61		Shallow Concentrated Flow, Shallow Concentrated Forest Woodland Kv= 5.0 fps
3.4	630	0.0230	3.08		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
4.6	2,300	0.0510	8.39	83.90	Channel Flow, Channel Flow Wooded Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.040 Winding stream, pools & shoals
63.5	3,460	Total			

Subcatchment EX-DA 1A: EX-DA 1A

Hydrograph



Summary for Subcatchment EX-DA 1B: EX-DA 1B

[47] Hint: Peak is 173% of capacity of segment #3

Runoff = 76.80 cfs @ 12.38 hrs, Volume= 8.687 af, Depth> 5.09"
 Routed to Pond EX-POND : EXISTING POND


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 100-yr Rainfall=8.46"

Area (ac)	CN	Description
2.640	68	1 acre lots, 20% imp, HSG B
0.350	79	1 acre lots, 20% imp, HSG C
7.910	98	Paved parking, HSG B
3.650	55	Woods, Good, HSG B
5.940	61	>75% Grass cover, Good, HSG B
20.490	75	Weighted Average
11.982		58.48% Pervious Area
8.508		41.52% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
22.5	150	0.0400	0.11		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
3.8	950	0.0660	4.14		Shallow Concentrated Flow, Shallow Concentrated Woods Unpaved Kv= 16.1 fps
1.1	910	0.0660	14.15	44.44	Pipe Channel, RCP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.017 Concrete sewer w/manholes & inlets
27.4	2,010	Total			

Subcatchment EX-DA 1B: EX-DA 1B

Hydrograph



Summary for Subcatchment EX-DA 1C: EX-DA 1C


Runoff = 17.08 cfs @ 12.14 hrs, Volume= 1.297 af, Depth> 3.96"
 Routed to Pond EX-POND : EXISTING POND

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 100-yr Rainfall=8.46"

Area (ac)	CN	Description
* 0.900	98	Water Surface
2.680	55	Woods, Good, HSG B
0.350	61	>75% Grass cover, Good, HSG B
3.930	65	Weighted Average
3.030		77.10% Pervious Area
0.900		22.90% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
8.1	90	0.1833	0.18		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
1.3	140	0.1290	1.80		Shallow Concentrated Flow, Shallow Concentrated Woods Woodland Kv= 5.0 fps
0.3	210	0.0660	12.73	127.25	Channel Flow, Stream Channel Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.030 Stream, clean & straight
9.7	440	Total			

Subcatchment EX-DA 1C: EX-DA 1C



Summary for Pond EX-POND: EXISTING POND

Inflow Area = 106.570 ac, 22.31% Impervious, Inflow Depth > 4.55" for 100-yr event
 Inflow = 216.30 cfs @ 12.74 hrs, Volume= 40.451 af
 Outflow = 210.04 cfs @ 12.87 hrs, Volume= 39.417 af, Atten= 3%, Lag= 8.3 min
 Primary = 210.04 cfs @ 12.87 hrs, Volume= 39.417 af
 Routed to Link EX DP-1 : EX DP1

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 77.46' @ 12.87 hrs Surf.Area= 1.634 ac Storage= 6.632 af

Plug-Flow detention time= 40.9 min calculated for 39.417 af (97% of inflow)
 Center-of-Mass det. time= 32.0 min (855.8 - 823.8)

Volume	Invert	Avail.Storage	Storage Description		
#1	71.80'	7.556 af	Existing Pond (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (acres)	Perim. (feet)	Inc.Store (acre-feet)	Cum.Store (acre-feet)	Wet.Area (acres)
71.80	0.938	1,000.1	0.000	0.000	0.938
74.00	1.020	1,016.0	2.153	2.153	1.016
76.00	1.320	1,692.0	2.334	4.487	4.360
78.00	1.760	1,652.0	3.069	7.556	4.617


Device	Routing	Invert	Outlet Devices
#1	Primary	71.80'	24.0" Round Culvert X 2.00 L= 100.0' Ke= 0.500 Inlet / Outlet Invert= 71.80' / 70.00' S= 0.0180 ' S= 0.0180 ' Cc= 0.900 n= 0.011 Concrete pipe, straight & clean, Flow Area= 3.14 sf
#2	Primary	75.75'	12.0' long + 3.0 ' SideZ x 12.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.57 2.62 2.70 2.67 2.66 2.67 2.66 2.64
#3	Primary	76.75'	30.0' long + 3.0 ' SideZ x 30.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63

Primary OutFlow Max=209.70 cfs @ 12.87 hrs HW=77.45' (Free Discharge)

- 1=Culvert (Inlet Controls 65.27 cfs @ 10.39 fps)
- 2=Broad-Crested Rectangular Weir (Weir Controls 94.48 cfs @ 3.24 fps)
- 3=Broad-Crested Rectangular Weir (Weir Controls 49.95 cfs @ 2.21 fps)

Pond EX-POND: EXISTING POND

Hydrograph




Summary for Link EX DP-1: EX DP1

Inflow Area = 106.570 ac, 22.31% Impervious, Inflow Depth > 4.44" for 100-yr event
Inflow = 210.04 cfs @ 12.87 hrs, Volume= 39.417 af
Primary = 210.04 cfs @ 12.87 hrs, Volume= 39.417 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link EX DP-1: EX DP1

Hydrograph







EX-DA 2



EX DP2



Area Listing (selected nodes)

Area (acres)	CN	Description (subcatchment-numbers)
0.660	61	>75% Grass cover, Good, HSG B (EX-DA2)
0.350	98	Paved parking, HSG B (EX-DA2)
1.690	55	Woods, Good, HSG B (EX-DA2)
2.700	62	TOTAL AREA

Soil Listing (selected nodes)

Area (acres)	Soil Group	Subcatchment Numbers
0.000	HSG A	
2.700	HSG B	EX-DA2
0.000	HSG C	
0.000	HSG D	
0.000	Other	
2.700		TOTAL AREA

Ground Covers (selected nodes)

HSG-A (acres)	HSG-B (acres)	HSG-C (acres)	HSG-D (acres)	Other (acres)	Total (acres)	Ground Cover	Subcatchment Numbers
0.000	0.660	0.000	0.000	0.000	0.660	>75% Grass cover, Good	EX-DA2
0.000	0.350	0.000	0.000	0.000	0.350	Paved parking	EX-DA2
0.000	1.690	0.000	0.000	0.000	1.690	Woods, Good	EX-DA2
0.000	2.700	0.000	0.000	0.000	2.700	TOTAL AREA	

Summary for Subcatchment EX-DA2: EX-DA 2

Runoff = 0.64 cfs @ 12.27 hrs, Volume= 0.081 af, Depth> 0.36"
 Routed to Link EX-DP2 : EX DP2


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 1-yr Rainfall=3.04"

Area (ac)	CN	Description
0.350	98	Paved parking, HSG B
1.690	55	Woods, Good, HSG B
0.660	61	>75% Grass cover, Good, HSG B
2.700	62	Weighted Average
2.350		87.04% Pervious Area
0.350		12.96% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.7	100	0.2600	0.22		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
5.7	620	0.1300	1.80		Shallow Concentrated Flow, Shallow Concentrated Woods Woodland Kv= 5.0 fps
0.1	45	0.0100	6.75	67.55	Channel Flow, Stream Channel Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.022 Earth, clean & straight
13.5	765	Total			

Subcatchment EX-DA2: EX-DA 2

Hydrograph




Summary for Link EX-DP2: EX DP2

Inflow Area = 2.700 ac, 12.96% Impervious, Inflow Depth > 0.36" for 1-yr event
Inflow = 0.64 cfs @ 12.27 hrs, Volume= 0.081 af
Primary = 0.64 cfs @ 12.27 hrs, Volume= 0.081 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link EX-DP2: EX DP2



Summary for Subcatchment EX-DA2: EX-DA 2


Runoff = 1.32 cfs @ 12.23 hrs, Volume= 0.138 af, Depth> 0.61"
 Routed to Link EX-DP2 : EX DP2

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 2-yr Rainfall=3.66"

Area (ac)	CN	Description
0.350	98	Paved parking, HSG B
1.690	55	Woods, Good, HSG B
0.660	61	>75% Grass cover, Good, HSG B
2.700	62	Weighted Average
2.350		87.04% Pervious Area
0.350		12.96% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.7	100	0.2600	0.22		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
5.7	620	0.1300	1.80		Shallow Concentrated Flow, Shallow Concentrated Woods Woodland Kv= 5.0 fps
0.1	45	0.0100	6.75	67.55	Channel Flow, Stream Channel Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.022 Earth, clean & straight
13.5	765	Total			

Subcatchment EX-DA2: EX-DA 2




Summary for Link EX-DP2: EX DP2

Inflow Area = 2.700 ac, 12.96% Impervious, Inflow Depth > 0.61" for 2-yr event
Inflow = 1.32 cfs @ 12.23 hrs, Volume= 0.138 af
Primary = 1.32 cfs @ 12.23 hrs, Volume= 0.138 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link EX-DP2: EX DP2

Hydrograph



Summary for Subcatchment EX-DA2: EX-DA 2


Runoff = 2.74 cfs @ 12.21 hrs, Volume= 0.251 af, Depth> 1.12"
 Routed to Link EX-DP2 : EX DP2

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 5-yr Rainfall=4.67"

Area (ac)	CN	Description
0.350	98	Paved parking, HSG B
1.690	55	Woods, Good, HSG B
0.660	61	>75% Grass cover, Good, HSG B
2.700	62	Weighted Average
2.350		87.04% Pervious Area
0.350		12.96% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.7	100	0.2600	0.22		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
5.7	620	0.1300	1.80		Shallow Concentrated Flow, Shallow Concentrated Woods Woodland Kv= 5.0 fps
0.1	45	0.0100	6.75	67.55	Channel Flow, Stream Channel Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.022 Earth, clean & straight
13.5	765	Total			

Subcatchment EX-DA2: EX-DA 2




Summary for Link EX-DP2: EX DP2

Inflow Area = 2.700 ac, 12.96% Impervious, Inflow Depth > 1.12" for 5-yr event
Inflow = 2.74 cfs @ 12.21 hrs, Volume= 0.251 af
Primary = 2.74 cfs @ 12.21 hrs, Volume= 0.251 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link EX-DP2: EX DP2

Hydrograph



Summary for Subcatchment EX-DA2: EX-DA 2


Runoff = 4.10 cfs @ 12.20 hrs, Volume= 0.360 af, Depth> 1.60"
 Routed to Link EX-DP2 : EX DP2

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-yr Rainfall=5.51"

Area (ac)	CN	Description
0.350	98	Paved parking, HSG B
1.690	55	Woods, Good, HSG B
0.660	61	>75% Grass cover, Good, HSG B
2.700	62	Weighted Average
2.350		87.04% Pervious Area
0.350		12.96% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.7	100	0.2600	0.22		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
5.7	620	0.1300	1.80		Shallow Concentrated Flow, Shallow Concentrated Woods Woodland Kv= 5.0 fps
0.1	45	0.0100	6.75	67.55	Channel Flow, Stream Channel Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.022 Earth, clean & straight
13.5	765	Total			

Subcatchment EX-DA2: EX-DA 2




Summary for Link EX-DP2: EX DP2

Inflow Area = 2.700 ac, 12.96% Impervious, Inflow Depth > 1.60" for 10-yr event
Inflow = 4.10 cfs @ 12.20 hrs, Volume= 0.360 af
Primary = 4.10 cfs @ 12.20 hrs, Volume= 0.360 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link EX-DP2: EX DP2



Summary for Subcatchment EX-DA2: EX-DA 2


Runoff = 6.15 cfs @ 12.20 hrs, Volume= 0.528 af, Depth> 2.35"
 Routed to Link EX-DP2 : EX DP2

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 25-yr Rainfall=6.67"

Area (ac)	CN	Description
0.350	98	Paved parking, HSG B
1.690	55	Woods, Good, HSG B
0.660	61	>75% Grass cover, Good, HSG B
2.700	62	Weighted Average
2.350		87.04% Pervious Area
0.350		12.96% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.7	100	0.2600	0.22		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
5.7	620	0.1300	1.80		Shallow Concentrated Flow, Shallow Concentrated Woods Woodland Kv= 5.0 fps
0.1	45	0.0100	6.75	67.55	Channel Flow, Stream Channel Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.022 Earth, clean & straight
13.5	765	Total			

Subcatchment EX-DA2: EX-DA 2




Summary for Link EX-DP2: EX DP2

Inflow Area = 2.700 ac, 12.96% Impervious, Inflow Depth > 2.35" for 25-yr event
Inflow = 6.15 cfs @ 12.20 hrs, Volume= 0.528 af
Primary = 6.15 cfs @ 12.20 hrs, Volume= 0.528 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link EX-DP2: EX DP2

Hydrograph



Summary for Subcatchment EX-DA2: EX-DA 2

Runoff = 7.79 cfs @ 12.20 hrs, Volume= 0.663 af, Depth> 2.95"
 Routed to Link EX-DP2 : EX DP2


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 50-yr Rainfall=7.54"

Area (ac)	CN	Description
0.350	98	Paved parking, HSG B
1.690	55	Woods, Good, HSG B
0.660	61	>75% Grass cover, Good, HSG B
2.700	62	Weighted Average
2.350		87.04% Pervious Area
0.350		12.96% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.7	100	0.2600	0.22		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
5.7	620	0.1300	1.80		Shallow Concentrated Flow, Shallow Concentrated Woods Woodland Kv= 5.0 fps
0.1	45	0.0100	6.75	67.55	Channel Flow, Stream Channel Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.022 Earth, clean & straight
13.5	765	Total			

Subcatchment EX-DA2: EX-DA 2

Hydrograph




Summary for Link EX-DP2: EX DP2

Inflow Area = 2.700 ac, 12.96% Impervious, Inflow Depth > 2.95" for 50-yr event
Inflow = 7.79 cfs @ 12.20 hrs, Volume= 0.663 af
Primary = 7.79 cfs @ 12.20 hrs, Volume= 0.663 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link EX-DP2: EX DP2

Hydrograph



Summary for Subcatchment EX-DA2: EX-DA 2

Runoff = 9.60 cfs @ 12.19 hrs, Volume= 0.813 af, Depth> 3.62"
 Routed to Link EX-DP2 : EX DP2


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 100-yr Rainfall=8.46"

Area (ac)	CN	Description
0.350	98	Paved parking, HSG B
1.690	55	Woods, Good, HSG B
0.660	61	>75% Grass cover, Good, HSG B
2.700	62	Weighted Average
2.350		87.04% Pervious Area
0.350		12.96% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.7	100	0.2600	0.22		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
5.7	620	0.1300	1.80		Shallow Concentrated Flow, Shallow Concentrated Woods Woodland Kv= 5.0 fps
0.1	45	0.0100	6.75	67.55	Channel Flow, Stream Channel Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.022 Earth, clean & straight
13.5	765	Total			

Subcatchment EX-DA2: EX-DA 2

Hydrograph




Summary for Link EX-DP2: EX DP2

Inflow Area = 2.700 ac, 12.96% Impervious, Inflow Depth > 3.62" for 100-yr event
Inflow = 9.60 cfs @ 12.19 hrs, Volume= 0.813 af
Primary = 9.60 cfs @ 12.19 hrs, Volume= 0.813 af, Atten= 0%, Lag= 0.0 min




Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link EX-DP2: EX DP2

Hydrograph



Appendix D – Proposed Conditions HydroCAD Routing



Routing Diagram for 4084
 Prepared by Civil 1, Inc, Printed 10/3/2023
 HydroCAD® 10.20-2g s/n 08208 © 2022 HydroCAD Software Solutions LLC

Area Listing (selected nodes)

Area (acres)	CN	Description (subcatchment-numbers)
42.920	68	1 acre lots, 20% imp, HSG B (PR-DA 1A, PR-DA-1B4)
27.890	79	1 acre lots, 20% imp, HSG C (PR-DA 1A, PR-DA-1B4)
6.660	61	>75% Grass cover, Good, HSG B (PR-DA 1A, PR-DA 1B1, PR-DA 1B2, PR-DA 1B3, PR-DA 1BND, PR-DA 1C, PR-DA-1B4)
0.270	74	>75% Grass cover, Good, HSG C (PR-DA 1A)
8.648	98	Paved parking, HSG B (NO ROOF 1, NO ROOF 2, NO ROOF 3, NO ROOF 4, PR-DA 1A, PR-DA 1B1, PR-DA 1B2, PR-DA 1B3, PR-DA 1BND, PR-DA-1B4)
0.620	98	Paved parking, HSG C (PR-DA 1A)
0.900	98	Water Surface (PR-DA 1C)
17.587	55	Woods, Good, HSG B (PR-DA 1A, PR-DA 1B1, PR-DA 1B2, PR-DA 1B3, PR-DA 1C, PR-DA-1B4)
1.450	70	Woods, Good, HSG C (PR-DA 1A)
106.945	71	TOTAL AREA

Soil Listing (selected nodes)

Area (acres)	Soil Group	Subcatchment Numbers
0.000	HSG A	
75.815	HSG B	NO ROOF 1, NO ROOF 2, NO ROOF 3, NO ROOF 4, PR-DA 1A, PR-DA 1B1, PR-DA 1B2, PR-DA 1B3, PR-DA 1BND, PR-DA 1C, PR-DA-1B4
30.230	HSG C	PR-DA 1A, PR-DA-1B4
0.000	HSG D	
0.900	Other	PR-DA 1C
106.945		TOTAL AREA

Ground Covers (selected nodes)

HSG-A (acres)	HSG-B (acres)	HSG-C (acres)	HSG-D (acres)	Other (acres)	Total (acres)	Ground Cover	Subcatchment Numbers
0.000	42.920	27.890	0.000	0.000	70.810	1 acre lots, 20% imp	PR-DA 1A, PR-DA-1 B4
0.000	6.660	0.270	0.000	0.000	6.930	>75% Grass cover, Good	PR-DA 1A, PR-DA 1B1, PR-DA 1B2, PR-DA 1B3, PR-DA 1BND, PR-DA 1C, PR-DA-1 B4
0.000	8.648	0.620	0.000	0.000	9.268	Paved parking	NO ROOF 1, NO ROOF 2, NO ROOF 3, NO ROOF 4, PR-DA 1A, PR-DA 1B1, PR-DA 1B2, PR-DA 1B3, PR-DA 1BND, PR-DA-1 B4
0.000	0.000	0.000	0.000	0.900	0.900	Water Surface	PR-DA 1C
0.000	17.587	1.450	0.000	0.000	19.037	Woods, Good	PR-DA 1A, PR-DA 1B1, PR-DA 1B2,

Ground Covers (selected nodes) (continued)

HSG-A (acres)	HSG-B (acres)	HSG-C (acres)	HSG-D (acres)	Other (acres)	Total (acres)	Ground Cover	Subcatchment Numbers
0.000	75.815	30.230	0.000	0.900	106.945	TOTAL AREA	

Summary for Subcatchment NO ROOF 1: NO ROOF 1

Runoff = 1.28 cfs @ 12.07 hrs, Volume= 0.094 af, Depth> 2.63"

Routed to Pond U.G. INFIL ROOF 1 : U.G. INFIL ROOF 1


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 1-yr Rainfall=3.04"

Area (ac)	CN	Description
0.430	98	Paved parking, HSG B
0.430		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, ROOF 1

Subcatchment NO ROOF 1: NO ROOF 1

Hydrograph



Summary for Subcatchment NO ROOF 2: NO ROOF 2

Runoff = 1.28 cfs @ 12.07 hrs, Volume= 0.094 af, Depth> 2.63"


Routed to Pond U.G. INFIL ROOF 2 : U.G. INFIL ROOF 2

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 1-yr Rainfall=3.04"

Area (ac)	CN	Description
0.430	98	Paved parking, HSG B
0.430		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, ROOF 1

Subcatchment NO ROOF 2: NO ROOF 2



Summary for Subcatchment NO ROOF 3: NO ROOF 3

Runoff = 1.28 cfs @ 12.07 hrs, Volume= 0.094 af, Depth> 2.63"


Routed to Pond U.G. INFIL ROOF 3 : U.G. INFIL ROOF 3

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 1-yr Rainfall=3.04"

Area (ac)	CN	Description
0.430	98	Paved parking, HSG B
0.430		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, ROOF 1

Subcatchment NO ROOF 3: NO ROOF 3



Summary for Subcatchment NO ROOF 4: NO ROOF 4

Runoff = 1.28 cfs @ 12.07 hrs, Volume= 0.094 af, Depth> 2.63"


Routed to Pond U.G. INFIL ROOF 4 : U.G. INFIL ROOF 4

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 1-yr Rainfall=3.04"

Area (ac)	CN	Description
0.430	98	Paved parking, HSG B
0.430		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, ROOF 1

Subcatchment NO ROOF 4: NO ROOF 4



Summary for Subcatchment PR-DA 1A: PR-DA 1A

Runoff = 23.39 cfs @ 12.96 hrs, Volume= 4.400 af, Depth> 0.64"

Routed to Pond EXISTING POND : EXISTING POND


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 1-yr Rainfall=3.04"

Area (ac)	CN	Description
40.280	68	1 acre lots, 20% imp, HSG B
27.540	79	1 acre lots, 20% imp, HSG C
0.180	98	Paved parking, HSG B
11.690	55	Woods, Good, HSG B
0.120	61	>75% Grass cover, Good, HSG B
0.620	98	Paved parking, HSG C
1.450	70	Woods, Good, HSG C
0.270	74	>75% Grass cover, Good, HSG C
82.150	70	Weighted Average
67.786		82.51% Pervious Area
14.364		17.49% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
49.3	200	0.0100	0.07		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
0.8	130	0.0200	2.87		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
5.4	200	0.0150	0.61		Shallow Concentrated Flow, Shallow Concentrated Forest Woodland Kv= 5.0 fps
3.4	630	0.0230	3.08		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
4.6	2,300	0.0510	8.39	83.90	Channel Flow, Channel Flow Wooded Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.040 Winding stream, pools & shoals
63.5	3,460	Total			

Subcatchment PR-DA 1A: PR-DA 1A

Hydrograph



Summary for Subcatchment PR-DA 1B1: PR-DA 1B1

Runoff = 3.87 cfs @ 12.17 hrs, Volume= 0.311 af, Depth> 1.37"
 Routed to Pond INFIL 1B1 : INFILTRATOR 1B1


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 1-yr Rainfall=3.04"

Area (ac)	CN	Description
1.758	98	Paved parking, HSG B
0.697	55	Woods, Good, HSG B
0.270	61	>75% Grass cover, Good, HSG B
2.725	83	Weighted Average
0.967		35.49% Pervious Area
1.758		64.51% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.2	150	0.2300	0.22		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
0.5	80	0.0200	2.87		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
11.7	230	Total			

Subcatchment PR-DA 1B1: PR-DA 1B1

Hydrograph



Summary for Subcatchment PR-DA 1B2: PR-DA 1B2

Runoff = 4.25 cfs @ 12.15 hrs, Volume= 0.332 af, Depth> 1.66"
 Routed to Pond INFIL 1B2 : INFILTRATOR 1B2


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 1-yr Rainfall=3.04"

Area (ac)	CN	Description
1.760	98	Paved parking, HSG B
0.310	55	Woods, Good, HSG B
0.340	61	>75% Grass cover, Good, HSG B
2.410	87	Weighted Average
0.650		26.97% Pervious Area
1.760		73.03% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.0	70	0.0850	0.13		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
1.7	300	0.0200	2.87		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
10.7	370	Total			

Subcatchment PR-DA 1B2: PR-DA 1B2

Hydrograph



Summary for Subcatchment PR-DA 1B3: PR-DA 1B3


Runoff = 2.75 cfs @ 12.26 hrs, Volume= 0.279 af, Depth> 0.62"
 Routed to Pond INFIL BASIN B3 : INFIL BASIN B3

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 1-yr Rainfall=3.04"

Area (ac)	CN	Description
1.340	98	Paved parking, HSG B
1.200	55	Woods, Good, HSG B
2.890	61	>75% Grass cover, Good, HSG B
5.430	69	Weighted Average
4.090		75.32% Pervious Area
1.340		24.68% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
13.6	150	0.0200	0.18		Sheet Flow, Sheet Flow Grass Grass: Short n= 0.150 P2= 3.20"
0.7	90	0.0200	2.28		Shallow Concentrated Flow, Shallow Concentrated Grass Unpaved Kv= 16.1 fps
1.4	1,170	0.0600	13.49	42.37	Pipe Channel, RCP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.017 Concrete sewer w/manholes & inlets
15.7	1,410	Total			

Subcatchment PR-DA 1B3: PR-DA 1B3



Summary for Subcatchment PR-DA 1BND: PR-DA 1BND

Runoff = 0.89 cfs @ 12.08 hrs, Volume= 0.059 af, Depth> 1.66"


Routed to Pond EXISTING POND : EXISTING POND

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 1-yr Rainfall=3.04"

Area (ac)	CN	Description
0.300	98	Paved parking, HSG B
0.130	61	>75% Grass cover, Good, HSG B
0.430	87	Weighted Average
0.130		30.23% Pervious Area
0.300		69.77% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Not Detained-Direct Entry

Subcatchment PR-DA 1BND: PR-DA 1BND



Summary for Subcatchment PR-DA 1C: PR-DA 1C


Runoff = 1.56 cfs @ 12.17 hrs, Volume= 0.152 af, Depth> 0.46"
 Routed to Pond EXISTING POND : EXISTING POND

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 1-yr Rainfall=3.04"

Area (ac)	CN	Description
* 0.900	98	Water Surface
2.680	55	Woods, Good, HSG B
0.350	61	>75% Grass cover, Good, HSG B
3.930	65	Weighted Average
3.030		77.10% Pervious Area
0.900		22.90% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
8.1	90	0.1833	0.18		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
1.3	140	0.1290	1.80		Shallow Concentrated Flow, Shallow Concentrated Woods Woodland Kv= 5.0 fps
0.3	210	0.0660	12.73	127.25	Channel Flow, Stream Channel Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.030 Stream, clean & straight
9.7	440	Total			

Subcatchment PR-DA 1C: PR-DA 1C



Summary for Subcatchment PR-DA-1B4: PR-DA 1B4

Runoff = 3.93 cfs @ 12.44 hrs, Volume= 0.475 af, Depth> 0.70"
 Routed to Pond INFIL BASIN B4 : INFIL BASIN B4


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 1-yr Rainfall=3.04"

Area (ac)	CN	Description
2.640	68	1 acre lots, 20% imp, HSG B
0.350	79	1 acre lots, 20% imp, HSG C
1.590	98	Paved parking, HSG B
1.010	55	Woods, Good, HSG B
2.560	61	>75% Grass cover, Good, HSG B
8.150	71	Weighted Average
5.962		73.15% Pervious Area
2.188		26.85% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
22.5	150	0.0400	0.11		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
3.8	950	0.0660	4.14		Shallow Concentrated Flow, Shallow Concentrated Woods Unpaved Kv= 16.1 fps
1.1	910	0.0660	14.15	44.44	Pipe Channel, RCP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.017 Concrete sewer w/manholes & inlets
27.4	2,010	Total			

Subcatchment PR-DA-1B4: PR-DA 1B4

Hydrograph



Summary for Pond EXISTING POND: EXISTING POND

Inflow Area = 106.945 ac, 22.75% Impervious, Inflow Depth > 0.59" for 1-yr event
 Inflow = 26.68 cfs @ 12.92 hrs, Volume= 5.225 af
 Outflow = 17.31 cfs @ 13.53 hrs, Volume= 4.770 af, Atten= 35%, Lag= 36.6 min
 Primary = 17.31 cfs @ 13.53 hrs, Volume= 4.770 af
 Routed to Link PR DP1 : PR DP1

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 73.12' @ 13.53 hrs Surf.Area= 0.987 ac Storage= 1.275 af

Plug-Flow detention time= 66.8 min calculated for 4.770 af (91% of inflow)
 Center-of-Mass det. time= 42.0 min (916.5 - 874.5)


Volume	Invert	Avail.Storage	Storage Description		
#1	71.80'	7.556 af	Existing Pond (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (acres)	Perim. (feet)	Inc.Store (acre-feet)	Cum.Store (acre-feet)	Wet.Area (acres)
71.80	0.938	1,000.1	0.000	0.000	0.938
74.00	1.020	1,016.0	2.153	2.153	1.016
76.00	1.320	1,692.0	2.334	4.487	4.360
78.00	1.760	1,652.0	3.069	7.556	4.617

Device	Routing	Invert	Outlet Devices
#1	Primary	71.80'	24.0" Round Culvert X 2.00 L= 100.0' Ke= 0.500 Inlet / Outlet Invert= 71.80' / 70.00' S= 0.0180 ' S Cc= 0.900 n= 0.011 Concrete pipe, straight & clean, Flow Area= 3.14 sf
#2	Primary	75.75'	12.0' long + 3.0 ' SideZ x 12.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.57 2.62 2.70 2.67 2.66 2.67 2.66 2.64
#3	Primary	76.75'	30.0' long + 3.0 ' SideZ x 30.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63

Primary OutFlow Max=17.30 cfs @ 13.53 hrs HW=73.12' (Free Discharge)

- 1=Culvert (Inlet Controls 17.30 cfs @ 3.92 fps)
- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)
- 3=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Pond EXISTING POND: EXISTING POND



Summary for Pond INFIL 1B1: INFILTRATOR 1B1

Inflow Area = 2.725 ac, 64.51% Impervious, Inflow Depth > 1.37" for 1-yr event
 Inflow = 3.87 cfs @ 12.17 hrs, Volume= 0.311 af
 Outflow = 0.27 cfs @ 14.73 hrs, Volume= 0.117 af, Atten= 93%, Lag= 154.0 min
 Discarded = 0.08 cfs @ 14.73 hrs, Volume= 0.062 af
 Primary = 0.19 cfs @ 14.73 hrs, Volume= 0.056 af
 Routed to Pond INFIL 1B2 : INFILTRATOR 1B2

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 129.95' @ 14.73 hrs Surf.Area= 0.114 ac Storage= 0.205 af

Plug-Flow detention time= 220.3 min calculated for 0.117 af (38% of inflow)
 Center-of-Mass det. time= 130.7 min (933.1 - 802.4)

Volume	Invert	Avail.Storage	Storage Description
#1A	127.50'	0.170 af	23.00'W x 215.70'L x 6.00'H Field A 0.683 af Overall - 0.259 af Embedded = 0.424 af x 40.0% Voids
#2A	128.00'	0.259 af	Cultec R-902HD x 174 Inside #1 Effective Size= 69.8"W x 48.0"H => 17.65 sf x 3.67'L = 64.7 cf Overall Size= 78.0"W x 48.0"H x 4.10'L with 0.44' Overlap 174 Chambers in 3 Rows Cap Storage= 2.8 cf x 2 x 3 rows = 16.6 cf
		0.429 af	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	129.75'	15.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	127.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 120.00'

Discarded OutFlow Max=0.08 cfs @ 14.73 hrs HW=129.95' (Free Discharge)
 ↳ **2=Exfiltration** (Controls 0.08 cfs)

Primary OutFlow Max=0.19 cfs @ 14.73 hrs HW=129.95' (Free Discharge)
 ↳ **1=Orifice/Grate** (Orifice Controls 0.19 cfs @ 1.52 fps)

Pond INFIL 1B1: INFILTRATOR 1B1



Summary for Pond INFIL 1B2: INFILTRATOR 1B2

Inflow Area = 5.135 ac, 68.51% Impervious, Inflow Depth > 0.91" for 1-yr event
 Inflow = 4.25 cfs @ 12.15 hrs, Volume= 0.388 af
 Outflow = 0.45 cfs @ 14.87 hrs, Volume= 0.213 af, Atten= 90%, Lag= 162.8 min
 Discarded = 0.14 cfs @ 14.87 hrs, Volume= 0.111 af
 Primary = 0.30 cfs @ 14.87 hrs, Volume= 0.102 af
 Routed to Pond EXISTING POND : EXISTING POND

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 124.24' @ 14.87 hrs Surf.Area= 0.160 ac Storage= 0.198 af

Plug-Flow detention time= 199.6 min calculated for 0.213 af (55% of inflow)
 Center-of-Mass det. time= 103.9 min (917.6 - 813.7)

Volume	Invert	Avail.Storage	Storage Description
#1A	122.50'	0.236 af	30.25'W x 230.37'L x 6.00'H Field A 0.960 af Overall - 0.369 af Embedded = 0.591 af x 40.0% Voids
#2A	123.00'	0.369 af	Cultec R-902HD x 248 Inside #1 Effective Size= 69.8"W x 48.0"H => 17.65 sf x 3.67'L = 64.7 cf Overall Size= 78.0"W x 48.0"H x 4.10'L with 0.44' Overlap 248 Chambers in 4 Rows Cap Storage= 2.8 cf x 2 x 4 rows = 22.1 cf
		0.605 af	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	124.00'	18.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	122.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 120.00'

Discarded OutFlow Max=0.14 cfs @ 14.87 hrs HW=124.24' (Free Discharge)
 ↳ **2=Exfiltration** (Controls 0.14 cfs)

Primary OutFlow Max=0.30 cfs @ 14.87 hrs HW=124.24' (Free Discharge)
 ↳ **1=Orifice/Grate** (Orifice Controls 0.30 cfs @ 1.67 fps)

Pond INFIL 1B2: INFILTRATOR 1B2



Summary for Pond INFIL BASIN B3: INFIL BASIN B3

Inflow Area = 6.290 ac, 34.98% Impervious, Inflow Depth > 0.67" for 1-yr event
 Inflow = 3.73 cfs @ 12.27 hrs, Volume= 0.349 af
 Outflow = 0.73 cfs @ 13.18 hrs, Volume= 0.214 af, Atten= 80%, Lag= 54.7 min
 Discarded = 0.06 cfs @ 13.18 hrs, Volume= 0.039 af
 Primary = 0.67 cfs @ 13.18 hrs, Volume= 0.175 af
 Routed to Pond EXISTING POND : EXISTING POND

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 101.33' @ 13.18 hrs Surf.Area= 4,437 sf Storage= 6,842 cf

Plug-Flow detention time= 160.1 min calculated for 0.214 af (61% of inflow)
 Center-of-Mass det. time= 80.1 min (915.9 - 835.8)


Volume	Invert	Avail.Storage	Storage Description		
#1	99.50'	25,262 cf	Existing Pond (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
99.50	3,074	220.0	0	0	3,074
100.00	3,428	230.0	1,625	1,625	3,449
102.00	4,993	267.0	8,372	9,997	4,995
104.00	6,798	305.0	11,745	21,741	6,817
104.50	7,285	315.0	3,520	25,262	7,334

Device	Routing	Invert	Outlet Devices
#1	Primary	101.00'	24.0" Round Culvert L= 50.0' Ke= 0.500 Inlet / Outlet Invert= 101.00' / 100.00' S= 0.0200 ' S= 0.0200 ' Cc= 0.900 n= 0.011 Concrete pipe, straight & clean, Flow Area= 3.14 sf
#2	Primary	103.50'	12.0' long + 3.0 ' SideZ x 6.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.37 2.51 2.70 2.68 2.68 2.67 2.65 2.65 2.65 2.65 2.66 2.66 2.67 2.69 2.72 2.76 2.83
#3	Discarded	99.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 89.00'

Discarded OutFlow Max=0.06 cfs @ 13.18 hrs HW=101.33' (Free Discharge)
 ↳3=Exfiltration (Controls 0.06 cfs)

Primary OutFlow Max=0.67 cfs @ 13.18 hrs HW=101.33' (Free Discharge)
 ↳1=Culvert (Inlet Controls 0.67 cfs @ 1.96 fps)
 ↳2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Pond INFIL BASIN B3: INFIL BASIN B3



Summary for Pond INFIL BASIN B4: INFIL BASIN B4

Inflow Area = 9.010 ac, 33.83% Impervious, Inflow Depth > 0.73" for 1-yr event
 Inflow = 4.73 cfs @ 12.40 hrs, Volume= 0.545 af
 Outflow = 2.84 cfs @ 12.77 hrs, Volume= 0.378 af, Atten= 40%, Lag= 21.7 min
 Discarded = 0.06 cfs @ 12.77 hrs, Volume= 0.041 af
 Primary = 2.77 cfs @ 12.77 hrs, Volume= 0.337 af
 Routed to Pond EXISTING POND : EXISTING POND

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 94.19' @ 12.77 hrs Surf.Area= 4,574 sf Storage= 8,064 cf

Plug-Flow detention time= 117.8 min calculated for 0.378 af (69% of inflow)
 Center-of-Mass det. time= 48.6 min (889.2 - 840.6)


Volume	Invert	Avail.Storage	Storage Description			
#1	92.00'	17,673 cf	Infil Basin B4 (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)	
92.00	2,832	377.0	0	0	2,832	
94.00	4,424	403.0	7,197	7,197	4,624	
96.00	6,097	428.0	10,476	17,673	6,475	

Device	Routing	Invert	Outlet Devices									
#1	Primary	94.00'	24.0" x 36.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads									
#2	Primary	95.50'	12.0' long + 3.0 ' SideZ x 6.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.37 2.51 2.70 2.68 2.68 2.67 2.65 2.65 2.65									
#3	Discarded	92.00'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 82.00'									

Discarded OutFlow Max=0.06 cfs @ 12.77 hrs HW=94.19' (Free Discharge)
 ↳3=Exfiltration (Controls 0.06 cfs)

Primary OutFlow Max=2.73 cfs @ 12.77 hrs HW=94.19' (Free Discharge)
 ↳1=Orifice/Grate (Weir Controls 2.73 cfs @ 1.43 fps)
 ↳2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Pond INFIL BASIN B4: INFIL BASIN B4



Summary for Pond U.G. INFIL ROOF 1: U.G. INFIL ROOF 1

Inflow Area = 0.430 ac, 100.00% Impervious, Inflow Depth > 2.63" for 1-yr event
 Inflow = 1.28 cfs @ 12.07 hrs, Volume= 0.094 af
 Outflow = 0.50 cfs @ 12.29 hrs, Volume= 0.053 af, Atten= 60%, Lag= 12.9 min
 Discarded = 0.02 cfs @ 12.29 hrs, Volume= 0.017 af
 Primary = 0.49 cfs @ 12.29 hrs, Volume= 0.035 af
 Routed to Pond INFIL BASIN B3 : INFIL BASIN B3

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 151.35' @ 12.29 hrs Surf.Area= 1,033 sf Storage= 2,035 cf

Plug-Flow detention time= 149.6 min calculated for 0.052 af (56% of inflow)
 Center-of-Mass det. time= 65.0 min (803.3 - 738.3)

Volume	Invert	Avail.Storage	Storage Description
#1A	148.50'	1,228 cf	18.50'W x 55.83'L x 4.50'H Field A 4,648 cf Overall - 1,578 cf Embedded = 3,070 cf x 40.0% Voids
#2A	149.00'	1,578 cf	Cultec R-360HD x 42 Inside #1 Effective Size= 54.9"W x 36.0"H => 9.99 sf x 3.67'L = 36.6 cf Overall Size= 60.0"W x 36.0"H x 4.17'L with 0.50' Overlap 42 Chambers in 3 Rows Cap Storage= 6.5 cf x 2 x 3 rows = 38.8 cf
		2,806 cf	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	151.00'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	148.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 138.00'

Discarded OutFlow Max=0.02 cfs @ 12.29 hrs HW=151.35' (Free Discharge)
 ↳ **2=Exfiltration** (Controls 0.02 cfs)

Primary OutFlow Max=0.48 cfs @ 12.29 hrs HW=151.35' (Free Discharge)
 ↳ **1=Orifice/Grate** (Orifice Controls 0.48 cfs @ 2.00 fps)

Pond U.G. INFIL ROOF 1: U.G. INFIL ROOF 1



Summary for Pond U.G. INFIL ROOF 2: U.G. INFIL ROOF 2

Inflow Area = 0.430 ac, 100.00% Impervious, Inflow Depth > 2.63" for 1-yr event
 Inflow = 1.28 cfs @ 12.07 hrs, Volume= 0.094 af
 Outflow = 0.50 cfs @ 12.29 hrs, Volume= 0.053 af, Atten= 60%, Lag= 12.9 min
 Discarded = 0.02 cfs @ 12.29 hrs, Volume= 0.017 af
 Primary = 0.49 cfs @ 12.29 hrs, Volume= 0.035 af
 Routed to Pond INFIL BASIN B3 : INFIL BASIN B3

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 151.35' @ 12.29 hrs Surf.Area= 1,033 sf Storage= 2,035 cf

Plug-Flow detention time= 149.6 min calculated for 0.052 af (56% of inflow)
 Center-of-Mass det. time= 65.0 min (803.3 - 738.3)

Volume	Invert	Avail.Storage	Storage Description
#1A	148.50'	1,228 cf	18.50'W x 55.83'L x 4.50'H Field A 4,648 cf Overall - 1,578 cf Embedded = 3,070 cf x 40.0% Voids
#2A	149.00'	1,578 cf	Cultec R-360HD x 42 Inside #1 Effective Size= 54.9"W x 36.0"H => 9.99 sf x 3.67'L = 36.6 cf Overall Size= 60.0"W x 36.0"H x 4.17'L with 0.50' Overlap 42 Chambers in 3 Rows Cap Storage= 6.5 cf x 2 x 3 rows = 38.8 cf
		2,806 cf	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	151.00'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	148.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 138.00'

Discarded OutFlow Max=0.02 cfs @ 12.29 hrs HW=151.35' (Free Discharge)
 ↳ **2=Exfiltration** (Controls 0.02 cfs)

Primary OutFlow Max=0.48 cfs @ 12.29 hrs HW=151.35' (Free Discharge)
 ↳ **1=Orifice/Grate** (Orifice Controls 0.48 cfs @ 2.00 fps)

Pond U.G. INFIL ROOF 2: U.G. INFIL ROOF 2



Summary for Pond U.G. INFIL ROOF 3: U.G. INFIL ROOF 3

Inflow Area = 0.430 ac, 100.00% Impervious, Inflow Depth > 2.63" for 1-yr event
 Inflow = 1.28 cfs @ 12.07 hrs, Volume= 0.094 af
 Outflow = 0.50 cfs @ 12.29 hrs, Volume= 0.053 af, Atten= 60%, Lag= 12.9 min
 Discarded = 0.02 cfs @ 12.29 hrs, Volume= 0.017 af
 Primary = 0.49 cfs @ 12.29 hrs, Volume= 0.035 af
 Routed to Pond INFIL BASIN B4 : INFIL BASIN B4

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 151.35' @ 12.29 hrs Surf.Area= 1,033 sf Storage= 2,035 cf

Plug-Flow detention time= 149.6 min calculated for 0.052 af (56% of inflow)
 Center-of-Mass det. time= 65.0 min (803.3 - 738.3)

Volume	Invert	Avail.Storage	Storage Description
#1A	148.50'	1,228 cf	18.50'W x 55.83'L x 4.50'H Field A 4,648 cf Overall - 1,578 cf Embedded = 3,070 cf x 40.0% Voids
#2A	149.00'	1,578 cf	Cultec R-360HD x 42 Inside #1 Effective Size= 54.9"W x 36.0"H => 9.99 sf x 3.67'L = 36.6 cf Overall Size= 60.0"W x 36.0"H x 4.17'L with 0.50' Overlap 42 Chambers in 3 Rows Cap Storage= 6.5 cf x 2 x 3 rows = 38.8 cf
		2,806 cf	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	151.00'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	148.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 138.00'

Discarded OutFlow Max=0.02 cfs @ 12.29 hrs HW=151.35' (Free Discharge)
 ↳ **2=Exfiltration** (Controls 0.02 cfs)

Primary OutFlow Max=0.48 cfs @ 12.29 hrs HW=151.35' (Free Discharge)
 ↳ **1=Orifice/Grate** (Orifice Controls 0.48 cfs @ 2.00 fps)

Pond U.G. INFIL ROOF 3: U.G. INFIL ROOF 3



Summary for Pond U.G. INFIL ROOF 4: U.G. INFIL ROOF 4

Inflow Area = 0.430 ac, 100.00% Impervious, Inflow Depth > 2.63" for 1-yr event
 Inflow = 1.28 cfs @ 12.07 hrs, Volume= 0.094 af
 Outflow = 0.50 cfs @ 12.29 hrs, Volume= 0.053 af, Atten= 60%, Lag= 12.9 min
 Discarded = 0.02 cfs @ 12.29 hrs, Volume= 0.017 af
 Primary = 0.49 cfs @ 12.29 hrs, Volume= 0.035 af
 Routed to Pond INFIL BASIN B4 : INFIL BASIN B4

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 151.35' @ 12.29 hrs Surf.Area= 1,033 sf Storage= 2,035 cf

Plug-Flow detention time= 149.6 min calculated for 0.052 af (56% of inflow)
 Center-of-Mass det. time= 65.0 min (803.3 - 738.3)

Volume	Invert	Avail.Storage	Storage Description
#1A	148.50'	1,228 cf	18.50'W x 55.83'L x 4.50'H Field A 4,648 cf Overall - 1,578 cf Embedded = 3,070 cf x 40.0% Voids
#2A	149.00'	1,578 cf	Cultec R-360HD x 42 Inside #1 Effective Size= 54.9"W x 36.0"H => 9.99 sf x 3.67'L = 36.6 cf Overall Size= 60.0"W x 36.0"H x 4.17'L with 0.50' Overlap 42 Chambers in 3 Rows Cap Storage= 6.5 cf x 2 x 3 rows = 38.8 cf
		2,806 cf	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	151.00'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	148.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 138.00'

Discarded OutFlow Max=0.02 cfs @ 12.29 hrs HW=151.35' (Free Discharge)
 ↳ **2=Exfiltration** (Controls 0.02 cfs)

Primary OutFlow Max=0.48 cfs @ 12.29 hrs HW=151.35' (Free Discharge)
 ↳ **1=Orifice/Grate** (Orifice Controls 0.48 cfs @ 2.00 fps)

Pond U.G. INFIL ROOF 4: U.G. INFIL ROOF 4




Summary for Link PR DP1: PR DP1

Inflow Area = 106.945 ac, 22.75% Impervious, Inflow Depth > 0.54" for 1-yr event
Inflow = 17.31 cfs @ 13.53 hrs, Volume= 4.770 af
Primary = 17.31 cfs @ 13.53 hrs, Volume= 4.770 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link PR DP1: PR DP1

Hydrograph



Summary for Subcatchment NO ROOF 1: NO ROOF 1

Runoff = 1.54 cfs @ 12.07 hrs, Volume= 0.114 af, Depth> 3.20"


Routed to Pond U.G. INFIL ROOF 1 : U.G. INFIL ROOF 1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 2-yr Rainfall=3.66"

Area (ac)	CN	Description
0.430	98	Paved parking, HSG B
0.430		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, ROOF 1

Subcatchment NO ROOF 1: NO ROOF 1



Summary for Subcatchment NO ROOF 2: NO ROOF 2

Runoff = 1.54 cfs @ 12.07 hrs, Volume= 0.114 af, Depth> 3.20"


Routed to Pond U.G. INFIL ROOF 2 : U.G. INFIL ROOF 2

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 2-yr Rainfall=3.66"

Area (ac)	CN	Description
0.430	98	Paved parking, HSG B
0.430		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, ROOF 1

Subcatchment NO ROOF 2: NO ROOF 2



Summary for Subcatchment NO ROOF 3: NO ROOF 3

Runoff = 1.54 cfs @ 12.07 hrs, Volume= 0.114 af, Depth> 3.20"


Routed to Pond U.G. INFIL ROOF 3 : U.G. INFIL ROOF 3

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 2-yr Rainfall=3.66"

Area (ac)	CN	Description
0.430	98	Paved parking, HSG B
0.430		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, ROOF 1

Subcatchment NO ROOF 3: NO ROOF 3



Summary for Subcatchment NO ROOF 4: NO ROOF 4

Runoff = 1.54 cfs @ 12.07 hrs, Volume= 0.114 af, Depth> 3.20"


Routed to Pond U.G. INFIL ROOF 4 : U.G. INFIL ROOF 4

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 2-yr Rainfall=3.66"

Area (ac)	CN	Description
0.430	98	Paved parking, HSG B
0.430		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, ROOF 1

Subcatchment NO ROOF 4: NO ROOF 4



Summary for Subcatchment PR-DA 1A: PR-DA 1A

Runoff = 37.49 cfs @ 12.92 hrs, Volume= 6.708 af, Depth> 0.98"

Routed to Pond EXISTING POND : EXISTING POND


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 2-yr Rainfall=3.66"

Area (ac)	CN	Description
40.280	68	1 acre lots, 20% imp, HSG B
27.540	79	1 acre lots, 20% imp, HSG C
0.180	98	Paved parking, HSG B
11.690	55	Woods, Good, HSG B
0.120	61	>75% Grass cover, Good, HSG B
0.620	98	Paved parking, HSG C
1.450	70	Woods, Good, HSG C
0.270	74	>75% Grass cover, Good, HSG C
82.150	70	Weighted Average
67.786		82.51% Pervious Area
14.364		17.49% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
49.3	200	0.0100	0.07		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
0.8	130	0.0200	2.87		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
5.4	200	0.0150	0.61		Shallow Concentrated Flow, Shallow Concentrated Forest Woodland Kv= 5.0 fps
3.4	630	0.0230	3.08		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
4.6	2,300	0.0510	8.39	83.90	Channel Flow, Channel Flow Wooded Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.040 Winding stream, pools & shoals
63.5	3,460	Total			

Subcatchment PR-DA 1A: PR-DA 1A

Hydrograph



Summary for Subcatchment PR-DA 1B1: PR-DA 1B1

Runoff = 5.25 cfs @ 12.16 hrs, Volume= 0.421 af, Depth> 1.85"
 Routed to Pond INFIL 1B1 : INFILTRATOR 1B1


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 2-yr Rainfall=3.66"

Area (ac)	CN	Description
1.758	98	Paved parking, HSG B
0.697	55	Woods, Good, HSG B
0.270	61	>75% Grass cover, Good, HSG B
2.725	83	Weighted Average
0.967		35.49% Pervious Area
1.758		64.51% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.2	150	0.2300	0.22		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
0.5	80	0.0200	2.87		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
11.7	230	Total			

Subcatchment PR-DA 1B1: PR-DA 1B1

Hydrograph



Summary for Subcatchment PR-DA 1B2: PR-DA 1B2

Runoff = 5.55 cfs @ 12.15 hrs, Volume= 0.438 af, Depth> 2.18"
 Routed to Pond INFIL 1B2 : INFILTRATOR 1B2


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 2-yr Rainfall=3.66"

Area (ac)	CN	Description
1.760	98	Paved parking, HSG B
0.310	55	Woods, Good, HSG B
0.340	61	>75% Grass cover, Good, HSG B
2.410	87	Weighted Average
0.650		26.97% Pervious Area
1.760		73.03% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.0	70	0.0850	0.13		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
1.7	300	0.0200	2.87		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
10.7	370	Total			

Subcatchment PR-DA 1B2: PR-DA 1B2

Hydrograph



Summary for Subcatchment PR-DA 1B3: PR-DA 1B3


Runoff = 4.51 cfs @ 12.24 hrs, Volume= 0.430 af, Depth> 0.95"
 Routed to Pond INFIL BASIN B3 : INFIL BASIN B3

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 2-yr Rainfall=3.66"

Area (ac)	CN	Description
1.340	98	Paved parking, HSG B
1.200	55	Woods, Good, HSG B
2.890	61	>75% Grass cover, Good, HSG B
5.430	69	Weighted Average
4.090		75.32% Pervious Area
1.340		24.68% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
13.6	150	0.0200	0.18		Sheet Flow, Sheet Flow Grass Grass: Short n= 0.150 P2= 3.20"
0.7	90	0.0200	2.28		Shallow Concentrated Flow, Shallow Concentrated Grass Unpaved Kv= 16.1 fps
1.4	1,170	0.0600	13.49	42.37	Pipe Channel, RCP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.017 Concrete sewer w/manholes & inlets
15.7	1,410	Total			

Subcatchment PR-DA 1B3: PR-DA 1B3



Summary for Subcatchment PR-DA 1BND: PR-DA 1BND

Runoff = 1.17 cfs @ 12.08 hrs, Volume= 0.078 af, Depth> 2.18"


Routed to Pond EXISTING POND : EXISTING POND

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 2-yr Rainfall=3.66"

Area (ac)	CN	Description
0.300	98	Paved parking, HSG B
0.130	61	>75% Grass cover, Good, HSG B
0.430	87	Weighted Average
0.130		30.23% Pervious Area
0.300		69.77% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Not Detained-Direct Entry

Subcatchment PR-DA 1BND: PR-DA 1BND



Summary for Subcatchment PR-DA 1C: PR-DA 1C


Runoff = 2.87 cfs @ 12.16 hrs, Volume= 0.246 af, Depth> 0.75"
 Routed to Pond EXISTING POND : EXISTING POND

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 2-yr Rainfall=3.66"

Area (ac)	CN	Description
* 0.900	98	Water Surface
2.680	55	Woods, Good, HSG B
0.350	61	>75% Grass cover, Good, HSG B
3.930	65	Weighted Average
3.030		77.10% Pervious Area
0.900		22.90% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
8.1	90	0.1833	0.18		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
1.3	140	0.1290	1.80		Shallow Concentrated Flow, Shallow Concentrated Woods Woodland Kv= 5.0 fps
0.3	210	0.0660	12.73	127.25	Channel Flow, Stream Channel Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.030 Stream, clean & straight
9.7	440	Total			

Subcatchment PR-DA 1C: PR-DA 1C



Summary for Subcatchment PR-DA-1B4: PR-DA 1B4

Runoff = 6.17 cfs @ 12.42 hrs, Volume= 0.715 af, Depth> 1.05"
 Routed to Pond INFIL BASIN B4 : INFIL BASIN B4


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 2-yr Rainfall=3.66"

Area (ac)	CN	Description
2.640	68	1 acre lots, 20% imp, HSG B
0.350	79	1 acre lots, 20% imp, HSG C
1.590	98	Paved parking, HSG B
1.010	55	Woods, Good, HSG B
2.560	61	>75% Grass cover, Good, HSG B
8.150	71	Weighted Average
5.962		73.15% Pervious Area
2.188		26.85% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
22.5	150	0.0400	0.11		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
3.8	950	0.0660	4.14		Shallow Concentrated Flow, Shallow Concentrated Woods Unpaved Kv= 16.1 fps
1.1	910	0.0660	14.15	44.44	Pipe Channel, RCP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.017 Concrete sewer w/manholes & inlets
27.4	2,010	Total			

Subcatchment PR-DA-1B4: PR-DA 1B4

Hydrograph



Summary for Pond EXISTING POND: EXISTING POND

Inflow Area = 106.945 ac, 22.75% Impervious, Inflow Depth > 0.93" for 2-yr event
 Inflow = 44.65 cfs @ 12.88 hrs, Volume= 8.302 af
 Outflow = 30.29 cfs @ 13.41 hrs, Volume= 7.766 af, Atten= 32%, Lag= 32.1 min
 Primary = 30.29 cfs @ 13.41 hrs, Volume= 7.766 af
 Routed to Link PR DP1 : PR DP1

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 73.80' @ 13.41 hrs Surf.Area= 1.012 ac Storage= 1.948 af

Plug-Flow detention time= 56.3 min calculated for 7.766 af (94% of inflow)
 Center-of-Mass det. time= 36.9 min (899.3 - 862.4)


Volume	Invert	Avail.Storage	Storage Description		
#1	71.80'	7.556 af	Existing Pond (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (acres)	Perim. (feet)	Inc.Store (acre-feet)	Cum.Store (acre-feet)	Wet.Area (acres)
71.80	0.938	1,000.1	0.000	0.000	0.938
74.00	1.020	1,016.0	2.153	2.153	1.016
76.00	1.320	1,692.0	2.334	4.487	4.360
78.00	1.760	1,652.0	3.069	7.556	4.617

Device	Routing	Invert	Outlet Devices
#1	Primary	71.80'	24.0" Round Culvert X 2.00 L= 100.0' Ke= 0.500 Inlet / Outlet Invert= 71.80' / 70.00' S= 0.0180 ' S= 0.0180 ' Cc= 0.900 n= 0.011 Concrete pipe, straight & clean, Flow Area= 3.14 sf
#2	Primary	75.75'	12.0' long + 3.0 ' SideZ x 12.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.57 2.62 2.70 2.67 2.66 2.67 2.66 2.64
#3	Primary	76.75'	30.0' long + 3.0 ' SideZ x 30.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63

Primary OutFlow Max=30.23 cfs @ 13.41 hrs HW=73.80' (Free Discharge)

- 1=Culvert (Inlet Controls 30.23 cfs @ 4.81 fps)
- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)
- 3=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Pond EXISTING POND: EXISTING POND



Summary for Pond INFIL 1B1: INFILTRATOR 1B1

Inflow Area = 2.725 ac, 64.51% Impervious, Inflow Depth > 1.85" for 2-yr event
 Inflow = 5.25 cfs @ 12.16 hrs, Volume= 0.421 af
 Outflow = 0.86 cfs @ 12.81 hrs, Volume= 0.225 af, Atten= 84%, Lag= 39.0 min
 Discarded = 0.08 cfs @ 12.81 hrs, Volume= 0.066 af
 Primary = 0.78 cfs @ 12.81 hrs, Volume= 0.159 af
 Routed to Pond INFIL 1B2 : INFILTRATOR 1B2

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 130.17' @ 12.81 hrs Surf.Area= 0.114 ac Storage= 0.224 af

Plug-Flow detention time= 167.0 min calculated for 0.225 af (53% of inflow)
 Center-of-Mass det. time= 88.0 min (883.5 - 795.5)

Volume	Invert	Avail.Storage	Storage Description
#1A	127.50'	0.170 af	23.00'W x 215.70'L x 6.00'H Field A 0.683 af Overall - 0.259 af Embedded = 0.424 af x 40.0% Voids
#2A	128.00'	0.259 af	Cultec R-902HD x 174 Inside #1 Effective Size= 69.8"W x 48.0"H => 17.65 sf x 3.67'L = 64.7 cf Overall Size= 78.0"W x 48.0"H x 4.10'L with 0.44' Overlap 174 Chambers in 3 Rows Cap Storage= 2.8 cf x 2 x 3 rows = 16.6 cf
		0.429 af	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	129.75'	15.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	127.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 120.00'

Discarded OutFlow Max=0.08 cfs @ 12.81 hrs HW=130.17' (Free Discharge)
 ↳ **2=Exfiltration** (Controls 0.08 cfs)

Primary OutFlow Max=0.78 cfs @ 12.81 hrs HW=130.17' (Free Discharge)
 ↳ **1=Orifice/Grate** (Orifice Controls 0.78 cfs @ 2.19 fps)

Pond INFIL 1B1: INFILTRATOR 1B1



Summary for Pond INFIL 1B2: INFILTRATOR 1B2

Inflow Area = 5.135 ac, 68.51% Impervious, Inflow Depth > 1.39" for 2-yr event
 Inflow = 5.55 cfs @ 12.15 hrs, Volume= 0.597 af
 Outflow = 1.47 cfs @ 12.95 hrs, Volume= 0.416 af, Atten= 74%, Lag= 47.9 min
 Discarded = 0.15 cfs @ 12.95 hrs, Volume= 0.119 af
 Primary = 1.31 cfs @ 12.95 hrs, Volume= 0.297 af
 Routed to Pond EXISTING POND : EXISTING POND

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 124.52' @ 12.95 hrs Surf.Area= 0.160 ac Storage= 0.234 af

Plug-Flow detention time= 137.3 min calculated for 0.415 af (70% of inflow)
 Center-of-Mass det. time= 68.0 min (877.2 - 809.2)

Volume	Invert	Avail.Storage	Storage Description
#1A	122.50'	0.236 af	30.25'W x 230.37'L x 6.00'H Field A 0.960 af Overall - 0.369 af Embedded = 0.591 af x 40.0% Voids
#2A	123.00'	0.369 af	Cultec R-902HD x 248 Inside #1 Effective Size= 69.8"W x 48.0"H => 17.65 sf x 3.67'L = 64.7 cf Overall Size= 78.0"W x 48.0"H x 4.10'L with 0.44' Overlap 248 Chambers in 4 Rows Cap Storage= 2.8 cf x 2 x 4 rows = 22.1 cf
		0.605 af	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	124.00'	18.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	122.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 120.00'

Discarded OutFlow Max=0.15 cfs @ 12.95 hrs HW=124.52' (Free Discharge)
 ↳ **2=Exfiltration** (Controls 0.15 cfs)

Primary OutFlow Max=1.31 cfs @ 12.95 hrs HW=124.52' (Free Discharge)
 ↳ **1=Orifice/Grate** (Orifice Controls 1.31 cfs @ 2.44 fps)

Pond INFIL 1B2: INFILTRATOR 1B2



Summary for Pond INFIL BASIN B3: INFIL BASIN B3

Inflow Area = 6.290 ac, 34.98% Impervious, Inflow Depth > 1.03" for 2-yr event
 Inflow = 6.32 cfs @ 12.21 hrs, Volume= 0.540 af
 Outflow = 2.68 cfs @ 12.61 hrs, Volume= 0.401 af, Atten= 58%, Lag= 24.1 min
 Discarded = 0.07 cfs @ 12.61 hrs, Volume= 0.041 af
 Primary = 2.61 cfs @ 12.61 hrs, Volume= 0.360 af
 Routed to Pond EXISTING POND : EXISTING POND

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 101.67' @ 12.61 hrs Surf.Area= 4,719 sf Storage= 8,418 cf

Plug-Flow detention time= 110.7 min calculated for 0.401 af (74% of inflow)
 Center-of-Mass det. time= 49.0 min (874.1 - 825.2)


Volume	Invert	Avail.Storage	Storage Description		
#1	99.50'	25,262 cf	Existing Pond (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
99.50	3,074	220.0	0	0	3,074
100.00	3,428	230.0	1,625	1,625	3,449
102.00	4,993	267.0	8,372	9,997	4,995
104.00	6,798	305.0	11,745	21,741	6,817
104.50	7,285	315.0	3,520	25,262	7,334

Device	Routing	Invert	Outlet Devices
#1	Primary	101.00'	24.0" Round Culvert L= 50.0' Ke= 0.500 Inlet / Outlet Invert= 101.00' / 100.00' S= 0.0200 ' S= 0.0200 ' Cc= 0.900 n= 0.011 Concrete pipe, straight & clean, Flow Area= 3.14 sf
#2	Primary	103.50'	12.0' long + 3.0 ' SideZ x 6.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.37 2.51 2.70 2.68 2.68 2.67 2.65 2.65 2.65 2.65 2.66 2.66 2.67 2.69 2.72 2.76 2.83
#3	Discarded	99.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 89.00'

Discarded OutFlow Max=0.07 cfs @ 12.61 hrs HW=101.67' (Free Discharge)
 ↳ **3=Exfiltration** (Controls 0.07 cfs)

Primary OutFlow Max=2.60 cfs @ 12.61 hrs HW=101.67' (Free Discharge)
 ↳ **1=Culvert** (Inlet Controls 2.60 cfs @ 2.79 fps)
 ↳ **2=Broad-Crested Rectangular Weir** (Controls 0.00 cfs)

Pond INFIL BASIN B3: INFIL BASIN B3



Summary for Pond INFIL BASIN B4: INFIL BASIN B4

Inflow Area = 9.010 ac, 33.83% Impervious, Inflow Depth > 1.10" for 2-yr event
 Inflow = 7.19 cfs @ 12.39 hrs, Volume= 0.825 af
 Outflow = 6.44 cfs @ 12.53 hrs, Volume= 0.657 af, Atten= 10%, Lag= 8.4 min
 Discarded = 0.07 cfs @ 12.53 hrs, Volume= 0.043 af
 Primary = 6.37 cfs @ 12.53 hrs, Volume= 0.613 af
 Routed to Pond EXISTING POND : EXISTING POND

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 94.34' @ 12.53 hrs Surf.Area= 4,686 sf Storage= 8,726 cf

Plug-Flow detention time= 82.0 min calculated for 0.657 af (80% of inflow)
 Center-of-Mass det. time= 29.6 min (860.4 - 830.8)

Volume	Invert	Avail.Storage	Storage Description			
#1	92.00'	17,673 cf	Infil Basin B4 (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)	
92.00	2,832	377.0	0	0	2,832	
94.00	4,424	403.0	7,197	7,197	4,624	
96.00	6,097	428.0	10,476	17,673	6,475	

Device	Routing	Invert	Outlet Devices									
#1	Primary	94.00'	24.0" x 36.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads									
#2	Primary	95.50'	12.0' long + 3.0 ' SideZ x 6.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.37 2.51 2.70 2.68 2.68 2.67 2.65 2.65 2.65									
#3	Discarded	92.00'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 82.00'									

Discarded OutFlow Max=0.07 cfs @ 12.53 hrs HW=94.33' (Free Discharge)


↳ **3=Exfiltration** (Controls 0.07 cfs)

Primary OutFlow Max=6.32 cfs @ 12.53 hrs HW=94.33' (Free Discharge)

↳ **1=Orifice/Grate** (Weir Controls 6.32 cfs @ 1.89 fps)

↳ **2=Broad-Crested Rectangular Weir** (Controls 0.00 cfs)

Pond INFIL BASIN B4: INFIL BASIN B4



Summary for Pond U.G. INFIL ROOF 1: U.G. INFIL ROOF 1

Inflow Area = 0.430 ac, 100.00% Impervious, Inflow Depth > 3.20" for 2-yr event
 Inflow = 1.54 cfs @ 12.07 hrs, Volume= 0.114 af
 Outflow = 1.11 cfs @ 12.16 hrs, Volume= 0.073 af, Atten= 28%, Lag= 5.4 min
 Discarded = 0.02 cfs @ 12.16 hrs, Volume= 0.018 af
 Primary = 1.10 cfs @ 12.16 hrs, Volume= 0.055 af
 Routed to Pond INFIL BASIN B3 : INFIL BASIN B3

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 151.54' @ 12.16 hrs Surf.Area= 1,033 sf Storage= 2,159 cf

Plug-Flow detention time= 135.6 min calculated for 0.073 af (63% of inflow)
 Center-of-Mass det. time= 59.4 min (796.0 - 736.6)

Volume	Invert	Avail.Storage	Storage Description
#1A	148.50'	1,228 cf	18.50'W x 55.83'L x 4.50'H Field A 4,648 cf Overall - 1,578 cf Embedded = 3,070 cf x 40.0% Voids
#2A	149.00'	1,578 cf	Cultec R-360HD x 42 Inside #1 Effective Size= 54.9"W x 36.0"H => 9.99 sf x 3.67'L = 36.6 cf Overall Size= 60.0"W x 36.0"H x 4.17'L with 0.50' Overlap 42 Chambers in 3 Rows Cap Storage= 6.5 cf x 2 x 3 rows = 38.8 cf
		2,806 cf	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	151.00'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	148.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 138.00'

Discarded OutFlow Max=0.02 cfs @ 12.16 hrs HW=151.53' (Free Discharge)
 ↳ **2=Exfiltration** (Controls 0.02 cfs)

Primary OutFlow Max=1.06 cfs @ 12.16 hrs HW=151.53' (Free Discharge)
 ↳ **1=Orifice/Grate** (Orifice Controls 1.06 cfs @ 2.49 fps)

Pond U.G. INFIL ROOF 1: U.G. INFIL ROOF 1



Summary for Pond U.G. INFIL ROOF 2: U.G. INFIL ROOF 2

Inflow Area = 0.430 ac, 100.00% Impervious, Inflow Depth > 3.20" for 2-yr event
 Inflow = 1.54 cfs @ 12.07 hrs, Volume= 0.114 af
 Outflow = 1.11 cfs @ 12.16 hrs, Volume= 0.073 af, Atten= 28%, Lag= 5.4 min
 Discarded = 0.02 cfs @ 12.16 hrs, Volume= 0.018 af
 Primary = 1.10 cfs @ 12.16 hrs, Volume= 0.055 af
 Routed to Pond INFIL BASIN B3 : INFIL BASIN B3

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 151.54' @ 12.16 hrs Surf.Area= 1,033 sf Storage= 2,159 cf

Plug-Flow detention time= 135.6 min calculated for 0.073 af (63% of inflow)
 Center-of-Mass det. time= 59.4 min (796.0 - 736.6)

Volume	Invert	Avail.Storage	Storage Description
#1A	148.50'	1,228 cf	18.50'W x 55.83'L x 4.50'H Field A 4,648 cf Overall - 1,578 cf Embedded = 3,070 cf x 40.0% Voids
#2A	149.00'	1,578 cf	Cultec R-360HD x 42 Inside #1 Effective Size= 54.9"W x 36.0"H => 9.99 sf x 3.67'L = 36.6 cf Overall Size= 60.0"W x 36.0"H x 4.17'L with 0.50' Overlap 42 Chambers in 3 Rows Cap Storage= 6.5 cf x 2 x 3 rows = 38.8 cf
		2,806 cf	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	151.00'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	148.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 138.00'

Discarded OutFlow Max=0.02 cfs @ 12.16 hrs HW=151.53' (Free Discharge)
 ↑**2=Exfiltration** (Controls 0.02 cfs)

Primary OutFlow Max=1.06 cfs @ 12.16 hrs HW=151.53' (Free Discharge)
 ↑**1=Orifice/Grate** (Orifice Controls 1.06 cfs @ 2.49 fps)

Pond U.G. INFIL ROOF 2: U.G. INFIL ROOF 2



Summary for Pond U.G. INFIL ROOF 3: U.G. INFIL ROOF 3

Inflow Area = 0.430 ac, 100.00% Impervious, Inflow Depth > 3.20" for 2-yr event
 Inflow = 1.54 cfs @ 12.07 hrs, Volume= 0.114 af
 Outflow = 1.11 cfs @ 12.16 hrs, Volume= 0.073 af, Atten= 28%, Lag= 5.4 min
 Discarded = 0.02 cfs @ 12.16 hrs, Volume= 0.018 af
 Primary = 1.10 cfs @ 12.16 hrs, Volume= 0.055 af
 Routed to Pond INFIL BASIN B4 : INFIL BASIN B4

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 151.54' @ 12.16 hrs Surf.Area= 1,033 sf Storage= 2,159 cf

Plug-Flow detention time= 135.6 min calculated for 0.073 af (63% of inflow)
 Center-of-Mass det. time= 59.4 min (796.0 - 736.6)

Volume	Invert	Avail.Storage	Storage Description
#1A	148.50'	1,228 cf	18.50'W x 55.83'L x 4.50'H Field A 4,648 cf Overall - 1,578 cf Embedded = 3,070 cf x 40.0% Voids
#2A	149.00'	1,578 cf	Cultec R-360HD x 42 Inside #1 Effective Size= 54.9"W x 36.0"H => 9.99 sf x 3.67'L = 36.6 cf Overall Size= 60.0"W x 36.0"H x 4.17'L with 0.50' Overlap 42 Chambers in 3 Rows Cap Storage= 6.5 cf x 2 x 3 rows = 38.8 cf
		2,806 cf	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	151.00'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	148.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 138.00'

Discarded OutFlow Max=0.02 cfs @ 12.16 hrs HW=151.53' (Free Discharge)
 ↑**2=Exfiltration** (Controls 0.02 cfs)

Primary OutFlow Max=1.06 cfs @ 12.16 hrs HW=151.53' (Free Discharge)
 ↑**1=Orifice/Grate** (Orifice Controls 1.06 cfs @ 2.49 fps)

Pond U.G. INFIL ROOF 3: U.G. INFIL ROOF 3



Summary for Pond U.G. INFIL ROOF 4: U.G. INFIL ROOF 4

Inflow Area = 0.430 ac, 100.00% Impervious, Inflow Depth > 3.20" for 2-yr event
 Inflow = 1.54 cfs @ 12.07 hrs, Volume= 0.114 af
 Outflow = 1.11 cfs @ 12.16 hrs, Volume= 0.073 af, Atten= 28%, Lag= 5.4 min
 Discarded = 0.02 cfs @ 12.16 hrs, Volume= 0.018 af
 Primary = 1.10 cfs @ 12.16 hrs, Volume= 0.055 af
 Routed to Pond INFIL BASIN B4 : INFIL BASIN B4

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 151.54' @ 12.16 hrs Surf.Area= 1,033 sf Storage= 2,159 cf

Plug-Flow detention time= 135.6 min calculated for 0.073 af (63% of inflow)
 Center-of-Mass det. time= 59.4 min (796.0 - 736.6)

Volume	Invert	Avail.Storage	Storage Description
#1A	148.50'	1,228 cf	18.50'W x 55.83'L x 4.50'H Field A 4,648 cf Overall - 1,578 cf Embedded = 3,070 cf x 40.0% Voids
#2A	149.00'	1,578 cf	Cultec R-360HD x 42 Inside #1 Effective Size= 54.9"W x 36.0"H => 9.99 sf x 3.67'L = 36.6 cf Overall Size= 60.0"W x 36.0"H x 4.17'L with 0.50' Overlap 42 Chambers in 3 Rows Cap Storage= 6.5 cf x 2 x 3 rows = 38.8 cf
		2,806 cf	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	151.00'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	148.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 138.00'

Discarded OutFlow Max=0.02 cfs @ 12.16 hrs HW=151.53' (Free Discharge)
 ↑**2=Exfiltration** (Controls 0.02 cfs)

Primary OutFlow Max=1.06 cfs @ 12.16 hrs HW=151.53' (Free Discharge)
 ↑**1=Orifice/Grate** (Orifice Controls 1.06 cfs @ 2.49 fps)

Pond U.G. INFIL ROOF 4: U.G. INFIL ROOF 4




Summary for Link PR DP1: PR DP1

Inflow Area = 106.945 ac, 22.75% Impervious, Inflow Depth > 0.87" for 2-yr event
Inflow = 30.29 cfs @ 13.41 hrs, Volume= 7.766 af
Primary = 30.29 cfs @ 13.41 hrs, Volume= 7.766 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link PR DP1: PR DP1

Hydrograph



Summary for Subcatchment NO ROOF 1: NO ROOF 1

Runoff = 1.98 cfs @ 12.07 hrs, Volume= 0.148 af, Depth> 4.12"

Routed to Pond U.G. INFIL ROOF 1 : U.G. INFIL ROOF 1


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 5-yr Rainfall=4.67"

Area (ac)	CN	Description
0.430	98	Paved parking, HSG B
0.430		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, ROOF 1

Subcatchment NO ROOF 1: NO ROOF 1

Hydrograph



Summary for Subcatchment NO ROOF 2: NO ROOF 2

Runoff = 1.98 cfs @ 12.07 hrs, Volume= 0.148 af, Depth> 4.12"

Routed to Pond U.G. INFIL ROOF 2 : U.G. INFIL ROOF 2


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 5-yr Rainfall=4.67"

Area (ac)	CN	Description
0.430	98	Paved parking, HSG B
0.430		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, ROOF 1

Subcatchment NO ROOF 2: NO ROOF 2

Hydrograph



Summary for Subcatchment NO ROOF 3: NO ROOF 3

Runoff = 1.98 cfs @ 12.07 hrs, Volume= 0.148 af, Depth> 4.12"

Routed to Pond U.G. INFIL ROOF 3 : U.G. INFIL ROOF 3


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 5-yr Rainfall=4.67"

Area (ac)	CN	Description
0.430	98	Paved parking, HSG B
0.430		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, ROOF 1

Subcatchment NO ROOF 3: NO ROOF 3

Hydrograph



Summary for Subcatchment NO ROOF 4: NO ROOF 4

Runoff = 1.98 cfs @ 12.07 hrs, Volume= 0.148 af, Depth> 4.12"

Routed to Pond U.G. INFIL ROOF 4 : U.G. INFIL ROOF 4


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 5-yr Rainfall=4.67"

Area (ac)	CN	Description
0.430	98	Paved parking, HSG B
0.430		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, ROOF 1

Subcatchment NO ROOF 4: NO ROOF 4

Hydrograph



Summary for Subcatchment PR-DA 1A: PR-DA 1A

Runoff = 63.57 cfs @ 12.90 hrs, Volume= 11.010 af, Depth> 1.61"

Routed to Pond EXISTING POND : EXISTING POND


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 5-yr Rainfall=4.67"

Area (ac)	CN	Description
40.280	68	1 acre lots, 20% imp, HSG B
27.540	79	1 acre lots, 20% imp, HSG C
0.180	98	Paved parking, HSG B
11.690	55	Woods, Good, HSG B
0.120	61	>75% Grass cover, Good, HSG B
0.620	98	Paved parking, HSG C
1.450	70	Woods, Good, HSG C
0.270	74	>75% Grass cover, Good, HSG C
82.150	70	Weighted Average
67.786		82.51% Pervious Area
14.364		17.49% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
49.3	200	0.0100	0.07		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
0.8	130	0.0200	2.87		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
5.4	200	0.0150	0.61		Shallow Concentrated Flow, Shallow Concentrated Forest Woodland Kv= 5.0 fps
3.4	630	0.0230	3.08		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
4.6	2,300	0.0510	8.39	83.90	Channel Flow, Channel Flow Wooded Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.040 Winding stream, pools & shoals
63.5	3,460	Total			

Subcatchment PR-DA 1A: PR-DA 1A

Hydrograph



Summary for Subcatchment PR-DA 1B1: PR-DA 1B1

Runoff = 7.56 cfs @ 12.16 hrs, Volume= 0.611 af, Depth> 2.69"
 Routed to Pond INFIL 1B1 : INFILTRATOR 1B1


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 5-yr Rainfall=4.67"

Area (ac)	CN	Description
1.758	98	Paved parking, HSG B
0.697	55	Woods, Good, HSG B
0.270	61	>75% Grass cover, Good, HSG B
2.725	83	Weighted Average
0.967		35.49% Pervious Area
1.758		64.51% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.2	150	0.2300	0.22		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
0.5	80	0.0200	2.87		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
11.7	230	Total			

Subcatchment PR-DA 1B1: PR-DA 1B1

Hydrograph



Summary for Subcatchment PR-DA 1B2: PR-DA 1B2

Runoff = 7.70 cfs @ 12.15 hrs, Volume= 0.615 af, Depth> 3.06"
 Routed to Pond INFIL 1B2 : INFILTRATOR 1B2


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 5-yr Rainfall=4.67"

Area (ac)	CN	Description
1.760	98	Paved parking, HSG B
0.310	55	Woods, Good, HSG B
0.340	61	>75% Grass cover, Good, HSG B
2.410	87	Weighted Average
0.650		26.97% Pervious Area
1.760		73.03% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.0	70	0.0850	0.13		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
1.7	300	0.0200	2.87		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
10.7	370	Total			

Subcatchment PR-DA 1B2: PR-DA 1B2

Hydrograph



Summary for Subcatchment PR-DA 1B3: PR-DA 1B3


Runoff = 7.78 cfs @ 12.23 hrs, Volume= 0.711 af, Depth> 1.57"
 Routed to Pond INFIL BASIN B3 : INFIL BASIN B3

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 5-yr Rainfall=4.67"

Area (ac)	CN	Description
1.340	98	Paved parking, HSG B
1.200	55	Woods, Good, HSG B
2.890	61	>75% Grass cover, Good, HSG B
5.430	69	Weighted Average
4.090		75.32% Pervious Area
1.340		24.68% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
13.6	150	0.0200	0.18		Sheet Flow, Sheet Flow Grass Grass: Short n= 0.150 P2= 3.20"
0.7	90	0.0200	2.28		Shallow Concentrated Flow, Shallow Concentrated Grass Unpaved Kv= 16.1 fps
1.4	1,170	0.0600	13.49	42.37	Pipe Channel, RCP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.017 Concrete sewer w/manholes & inlets
15.7	1,410	Total			

Subcatchment PR-DA 1B3: PR-DA 1B3



Summary for Subcatchment PR-DA 1BND: PR-DA 1BND

Runoff = 1.63 cfs @ 12.07 hrs, Volume= 0.110 af, Depth> 3.07"


Routed to Pond EXISTING POND : EXISTING POND

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 5-yr Rainfall=4.67"

Area (ac)	CN	Description
0.300	98	Paved parking, HSG B
0.130	61	>75% Grass cover, Good, HSG B
0.430	87	Weighted Average
0.130		30.23% Pervious Area
0.300		69.77% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Not Detained-Direct Entry

Subcatchment PR-DA 1BND: PR-DA 1BND



Summary for Subcatchment PR-DA 1C: PR-DA 1C


Runoff = 5.40 cfs @ 12.15 hrs, Volume= 0.428 af, Depth> 1.31"
 Routed to Pond EXISTING POND : EXISTING POND

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 5-yr Rainfall=4.67"

Area (ac)	CN	Description
* 0.900	98	Water Surface
2.680	55	Woods, Good, HSG B
0.350	61	>75% Grass cover, Good, HSG B
3.930	65	Weighted Average
3.030		77.10% Pervious Area
0.900		22.90% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
8.1	90	0.1833	0.18		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
1.3	140	0.1290	1.80		Shallow Concentrated Flow, Shallow Concentrated Woods Woodland Kv= 5.0 fps
0.3	210	0.0660	12.73	127.25	Channel Flow, Stream Channel Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.030 Stream, clean & straight
9.7	440	Total			

Subcatchment PR-DA 1C: PR-DA 1C



Summary for Subcatchment PR-DA-1B4: PR-DA 1B4

Runoff = 10.27 cfs @ 12.40 hrs, Volume= 1.159 af, Depth> 1.71"
 Routed to Pond INFIL BASIN B4 : INFIL BASIN B4


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 5-yr Rainfall=4.67"

Area (ac)	CN	Description
2.640	68	1 acre lots, 20% imp, HSG B
0.350	79	1 acre lots, 20% imp, HSG C
1.590	98	Paved parking, HSG B
1.010	55	Woods, Good, HSG B
2.560	61	>75% Grass cover, Good, HSG B
8.150	71	Weighted Average
5.962		73.15% Pervious Area
2.188		26.85% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
22.5	150	0.0400	0.11		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
3.8	950	0.0660	4.14		Shallow Concentrated Flow, Shallow Concentrated Woods Unpaved Kv= 16.1 fps
1.1	910	0.0660	14.15	44.44	Pipe Channel, RCP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.017 Concrete sewer w/manholes & inlets
27.4	2,010	Total			

Subcatchment PR-DA-1B4: PR-DA 1B4

Hydrograph



Summary for Pond EXISTING POND: EXISTING POND

Inflow Area = 106.945 ac, 22.75% Impervious, Inflow Depth > 1.57" for 5-yr event
 Inflow = 77.08 cfs @ 12.81 hrs, Volume= 14.002 af
 Outflow = 47.63 cfs @ 13.43 hrs, Volume= 13.347 af, Atten= 38%, Lag= 37.6 min
 Primary = 47.63 cfs @ 13.43 hrs, Volume= 13.347 af
 Routed to Link PR DP1 : PR DP1

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 75.28' @ 13.43 hrs Surf.Area= 1.207 ac Storage= 3.576 af

Plug-Flow detention time= 53.2 min calculated for 13.303 af (95% of inflow)
 Center-of-Mass det. time= 38.5 min (888.3 - 849.8)


Volume	Invert	Avail.Storage	Storage Description		
#1	71.80'	7.556 af	Existing Pond (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (acres)	Perim. (feet)	Inc.Store (acre-feet)	Cum.Store (acre-feet)	Wet.Area (acres)
71.80	0.938	1,000.1	0.000	0.000	0.938
74.00	1.020	1,016.0	2.153	2.153	1.016
76.00	1.320	1,692.0	2.334	4.487	4.360
78.00	1.760	1,652.0	3.069	7.556	4.617

Device	Routing	Invert	Outlet Devices
#1	Primary	71.80'	24.0" Round Culvert X 2.00 L= 100.0' Ke= 0.500 Inlet / Outlet Invert= 71.80' / 70.00' S= 0.0180 ' S= 0.0180 ' Cc= 0.900 n= 0.011 Concrete pipe, straight & clean, Flow Area= 3.14 sf
#2	Primary	75.75'	12.0' long + 3.0 ' SideZ x 12.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.57 2.62 2.70 2.67 2.66 2.67 2.66 2.64
#3	Primary	76.75'	30.0' long + 3.0 ' SideZ x 30.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63

Primary OutFlow Max=47.62 cfs @ 13.43 hrs HW=75.28' (Free Discharge)

- 1=Culvert (Inlet Controls 47.62 cfs @ 7.58 fps)
- 2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)
- 3=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Pond EXISTING POND: EXISTING POND



Summary for Pond INFIL 1B1: INFILTRATOR 1B1

Inflow Area = 2.725 ac, 64.51% Impervious, Inflow Depth > 2.69" for 5-yr event
 Inflow = 7.56 cfs @ 12.16 hrs, Volume= 0.611 af
 Outflow = 3.22 cfs @ 12.47 hrs, Volume= 0.412 af, Atten= 57%, Lag= 18.7 min
 Discarded = 0.08 cfs @ 12.47 hrs, Volume= 0.072 af
 Primary = 3.14 cfs @ 12.47 hrs, Volume= 0.340 af
 Routed to Pond INFIL 1B2 : INFILTRATOR 1B2

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 130.67' @ 12.47 hrs Surf.Area= 0.114 ac Storage= 0.267 af

Plug-Flow detention time= 126.4 min calculated for 0.410 af (67% of inflow)
 Center-of-Mass det. time= 58.7 min (845.7 - 787.0)

Volume	Invert	Avail.Storage	Storage Description
#1A	127.50'	0.170 af	23.00'W x 215.70'L x 6.00'H Field A 0.683 af Overall - 0.259 af Embedded = 0.424 af x 40.0% Voids
#2A	128.00'	0.259 af	Cultec R-902HD x 174 Inside #1 Effective Size= 69.8"W x 48.0"H => 17.65 sf x 3.67'L = 64.7 cf Overall Size= 78.0"W x 48.0"H x 4.10'L with 0.44' Overlap 174 Chambers in 3 Rows Cap Storage= 2.8 cf x 2 x 3 rows = 16.6 cf
		0.429 af	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	129.75'	15.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	127.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 120.00'

Discarded OutFlow Max=0.08 cfs @ 12.47 hrs HW=130.66' (Free Discharge)
 ↳ **2=Exfiltration** (Controls 0.08 cfs)

Primary OutFlow Max=3.12 cfs @ 12.47 hrs HW=130.66' (Free Discharge)
 ↳ **1=Orifice/Grate** (Orifice Controls 3.12 cfs @ 3.25 fps)

Pond INFIL 1B1: INFILTRATOR 1B1



Summary for Pond INFIL 1B2: INFILTRATOR 1B2

Inflow Area = 5.135 ac, 68.51% Impervious, Inflow Depth > 2.23" for 5-yr event
 Inflow = 7.70 cfs @ 12.15 hrs, Volume= 0.955 af
 Outflow = 5.05 cfs @ 12.57 hrs, Volume= 0.768 af, Atten= 34%, Lag= 24.8 min
 Discarded = 0.17 cfs @ 12.57 hrs, Volume= 0.131 af
 Primary = 4.88 cfs @ 12.57 hrs, Volume= 0.637 af
 Routed to Pond EXISTING POND : EXISTING POND

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 125.09' @ 12.57 hrs Surf.Area= 0.160 ac Storage= 0.308 af

Plug-Flow detention time= 95.8 min calculated for 0.765 af (80% of inflow)
 Center-of-Mass det. time= 45.4 min (844.3 - 798.9)

Volume	Invert	Avail.Storage	Storage Description
#1A	122.50'	0.236 af	30.25'W x 230.37'L x 6.00'H Field A 0.960 af Overall - 0.369 af Embedded = 0.591 af x 40.0% Voids
#2A	123.00'	0.369 af	Cultec R-902HD x 248 Inside #1 Effective Size= 69.8"W x 48.0"H => 17.65 sf x 3.67'L = 64.7 cf Overall Size= 78.0"W x 48.0"H x 4.10'L with 0.44' Overlap 248 Chambers in 4 Rows Cap Storage= 2.8 cf x 2 x 4 rows = 22.1 cf
		0.605 af	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	124.00'	18.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	122.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 120.00'

Discarded OutFlow Max=0.17 cfs @ 12.57 hrs HW=125.09' (Free Discharge)
 ↑**2=Exfiltration** (Controls 0.17 cfs)

Primary OutFlow Max=4.86 cfs @ 12.57 hrs HW=125.09' (Free Discharge)
 ↑**1=Orifice/Grate** (Orifice Controls 4.86 cfs @ 3.55 fps)

Pond INFIL 1B2: INFILTRATOR 1B2



Summary for Pond INFIL BASIN B3: INFIL BASIN B3

Inflow Area = 6.290 ac, 34.98% Impervious, Inflow Depth > 1.69" for 5-yr event
 Inflow = 10.25 cfs @ 12.19 hrs, Volume= 0.887 af
 Outflow = 6.87 cfs @ 12.42 hrs, Volume= 0.744 af, Atten= 33%, Lag= 13.6 min
 Discarded = 0.07 cfs @ 12.42 hrs, Volume= 0.045 af
 Primary = 6.80 cfs @ 12.42 hrs, Volume= 0.699 af
 Routed to Pond EXISTING POND : EXISTING POND

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 102.15' @ 12.42 hrs Surf.Area= 5,116 sf Storage= 10,742 cf

Plug-Flow detention time= 75.9 min calculated for 0.744 af (84% of inflow)
 Center-of-Mass det. time= 31.2 min (845.6 - 814.4)


Volume	Invert	Avail.Storage	Storage Description		
#1	99.50'	25,262 cf	Existing Pond (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
99.50	3,074	220.0	0	0	3,074
100.00	3,428	230.0	1,625	1,625	3,449
102.00	4,993	267.0	8,372	9,997	4,995
104.00	6,798	305.0	11,745	21,741	6,817
104.50	7,285	315.0	3,520	25,262	7,334

Device	Routing	Invert	Outlet Devices
#1	Primary	101.00'	24.0" Round Culvert L= 50.0' Ke= 0.500 Inlet / Outlet Invert= 101.00' / 100.00' S= 0.0200 ' n= 0.011 Concrete pipe, straight & clean, Flow Area= 3.14 sf
#2	Primary	103.50'	12.0' long + 3.0 ' SideZ x 6.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.37 2.51 2.70 2.68 2.68 2.67 2.65 2.65 2.65 2.65 2.66 2.66 2.67 2.69 2.72 2.76 2.83
#3	Discarded	99.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 89.00'

Discarded OutFlow Max=0.07 cfs @ 12.42 hrs HW=102.14' (Free Discharge)
 ↳ **3=Exfiltration** (Controls 0.07 cfs)

Primary OutFlow Max=6.76 cfs @ 12.42 hrs HW=102.14' (Free Discharge)
 ↳ **1=Culvert** (Inlet Controls 6.76 cfs @ 3.64 fps)
 ↳ **2=Broad-Crested Rectangular Weir** (Controls 0.00 cfs)

Pond INFIL BASIN B3: INFIL BASIN B3



Summary for Pond INFIL BASIN B4: INFIL BASIN B4

Inflow Area = 9.010 ac, 33.83% Impervious, Inflow Depth > 1.78" for 5-yr event
 Inflow = 11.60 cfs @ 12.38 hrs, Volume= 1.334 af
 Outflow = 11.48 cfs @ 12.42 hrs, Volume= 1.164 af, Atten= 1%, Lag= 2.6 min
 Discarded = 0.07 cfs @ 12.42 hrs, Volume= 0.047 af
 Primary = 11.41 cfs @ 12.42 hrs, Volume= 1.117 af
 Routed to Pond EXISTING POND : EXISTING POND

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 94.50' @ 12.42 hrs Surf.Area= 4,813 sf Storage= 9,484 cf

Plug-Flow detention time= 55.4 min calculated for 1.160 af (87% of inflow)
 Center-of-Mass det. time= 18.8 min (839.3 - 820.5)

Volume	Invert	Avail.Storage	Storage Description			
#1	92.00'	17,673 cf	Infil Basin B4 (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)	
92.00	2,832	377.0	0	0	2,832	
94.00	4,424	403.0	7,197	7,197	4,624	
96.00	6,097	428.0	10,476	17,673	6,475	


Device	Routing	Invert	Outlet Devices									
#1	Primary	94.00'	24.0" x 36.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads									
#2	Primary	95.50'	12.0' long + 3.0 ' SideZ x 6.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.37 2.51 2.70 2.68 2.68 2.67 2.65 2.65 2.65 2.65 2.66 2.66 2.67 2.69 2.72 2.76 2.83									
#3	Discarded	92.00'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 82.00'									

Discarded OutFlow Max=0.07 cfs @ 12.42 hrs HW=94.49' (Free Discharge)
 ↳3=Exfiltration (Controls 0.07 cfs)

Primary OutFlow Max=11.34 cfs @ 12.42 hrs HW=94.49' (Free Discharge)
 ↳1=Orifice/Grate (Weir Controls 11.34 cfs @ 2.30 fps)
 ↳2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Pond INFIL BASIN B4: INFIL BASIN B4

Hydrograph



Summary for Pond U.G. INFIL ROOF 1: U.G. INFIL ROOF 1

Inflow Area = 0.430 ac, 100.00% Impervious, Inflow Depth > 4.12" for 5-yr event
 Inflow = 1.98 cfs @ 12.07 hrs, Volume= 0.148 af
 Outflow = 1.79 cfs @ 12.11 hrs, Volume= 0.106 af, Atten= 9%, Lag= 2.5 min
 Discarded = 0.02 cfs @ 12.11 hrs, Volume= 0.018 af
 Primary = 1.78 cfs @ 12.11 hrs, Volume= 0.088 af
 Routed to Pond INFIL BASIN B3 : INFIL BASIN B3

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 151.73' @ 12.11 hrs Surf.Area= 1,033 sf Storage= 2,264 cf

Plug-Flow detention time= 121.3 min calculated for 0.105 af (71% of inflow)
 Center-of-Mass det. time= 54.5 min (789.3 - 734.8)

Volume	Invert	Avail.Storage	Storage Description
#1A	148.50'	1,228 cf	18.50'W x 55.83'L x 4.50'H Field A 4,648 cf Overall - 1,578 cf Embedded = 3,070 cf x 40.0% Voids
#2A	149.00'	1,578 cf	Cultec R-360HD x 42 Inside #1 Effective Size= 54.9"W x 36.0"H => 9.99 sf x 3.67'L = 36.6 cf Overall Size= 60.0"W x 36.0"H x 4.17'L with 0.50' Overlap 42 Chambers in 3 Rows Cap Storage= 6.5 cf x 2 x 3 rows = 38.8 cf
		2,806 cf	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	151.00'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	148.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 138.00'

Discarded OutFlow Max=0.02 cfs @ 12.11 hrs HW=151.72' (Free Discharge)
 ↑**2=Exfiltration** (Controls 0.02 cfs)

Primary OutFlow Max=1.73 cfs @ 12.11 hrs HW=151.72' (Free Discharge)
 ↑**1=Orifice/Grate** (Orifice Controls 1.73 cfs @ 2.88 fps)

Pond U.G. INFIL ROOF 1: U.G. INFIL ROOF 1



Summary for Pond U.G. INFIL ROOF 2: U.G. INFIL ROOF 2

Inflow Area = 0.430 ac, 100.00% Impervious, Inflow Depth > 4.12" for 5-yr event
 Inflow = 1.98 cfs @ 12.07 hrs, Volume= 0.148 af
 Outflow = 1.79 cfs @ 12.11 hrs, Volume= 0.106 af, Atten= 9%, Lag= 2.5 min
 Discarded = 0.02 cfs @ 12.11 hrs, Volume= 0.018 af
 Primary = 1.78 cfs @ 12.11 hrs, Volume= 0.088 af
 Routed to Pond INFIL BASIN B3 : INFIL BASIN B3

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 151.73' @ 12.11 hrs Surf.Area= 1,033 sf Storage= 2,264 cf

Plug-Flow detention time= 121.3 min calculated for 0.105 af (71% of inflow)
 Center-of-Mass det. time= 54.5 min (789.3 - 734.8)

Volume	Invert	Avail.Storage	Storage Description
#1A	148.50'	1,228 cf	18.50'W x 55.83'L x 4.50'H Field A 4,648 cf Overall - 1,578 cf Embedded = 3,070 cf x 40.0% Voids
#2A	149.00'	1,578 cf	Cultec R-360HD x 42 Inside #1 Effective Size= 54.9"W x 36.0"H => 9.99 sf x 3.67'L = 36.6 cf Overall Size= 60.0"W x 36.0"H x 4.17'L with 0.50' Overlap 42 Chambers in 3 Rows Cap Storage= 6.5 cf x 2 x 3 rows = 38.8 cf
		2,806 cf	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	151.00'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	148.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 138.00'

Discarded OutFlow Max=0.02 cfs @ 12.11 hrs HW=151.72' (Free Discharge)
 ↑**2=Exfiltration** (Controls 0.02 cfs)

Primary OutFlow Max=1.73 cfs @ 12.11 hrs HW=151.72' (Free Discharge)
 ↑**1=Orifice/Grate** (Orifice Controls 1.73 cfs @ 2.88 fps)

Pond U.G. INFIL ROOF 2: U.G. INFIL ROOF 2



Summary for Pond U.G. INFIL ROOF 3: U.G. INFIL ROOF 3

Inflow Area = 0.430 ac, 100.00% Impervious, Inflow Depth > 4.12" for 5-yr event
 Inflow = 1.98 cfs @ 12.07 hrs, Volume= 0.148 af
 Outflow = 1.79 cfs @ 12.11 hrs, Volume= 0.106 af, Atten= 9%, Lag= 2.5 min
 Discarded = 0.02 cfs @ 12.11 hrs, Volume= 0.018 af
 Primary = 1.78 cfs @ 12.11 hrs, Volume= 0.088 af
 Routed to Pond INFIL BASIN B4 : INFIL BASIN B4

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 151.73' @ 12.11 hrs Surf.Area= 1,033 sf Storage= 2,264 cf

Plug-Flow detention time= 121.3 min calculated for 0.105 af (71% of inflow)
 Center-of-Mass det. time= 54.5 min (789.3 - 734.8)

Volume	Invert	Avail.Storage	Storage Description
#1A	148.50'	1,228 cf	18.50'W x 55.83'L x 4.50'H Field A 4,648 cf Overall - 1,578 cf Embedded = 3,070 cf x 40.0% Voids
#2A	149.00'	1,578 cf	Cultec R-360HD x 42 Inside #1 Effective Size= 54.9"W x 36.0"H => 9.99 sf x 3.67'L = 36.6 cf Overall Size= 60.0"W x 36.0"H x 4.17'L with 0.50' Overlap 42 Chambers in 3 Rows Cap Storage= 6.5 cf x 2 x 3 rows = 38.8 cf
		2,806 cf	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	151.00'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	148.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 138.00'

Discarded OutFlow Max=0.02 cfs @ 12.11 hrs HW=151.72' (Free Discharge)
 ↑**2=Exfiltration** (Controls 0.02 cfs)

Primary OutFlow Max=1.73 cfs @ 12.11 hrs HW=151.72' (Free Discharge)
 ↑**1=Orifice/Grate** (Orifice Controls 1.73 cfs @ 2.88 fps)

Pond U.G. INFIL ROOF 3: U.G. INFIL ROOF 3



Summary for Pond U.G. INFIL ROOF 4: U.G. INFIL ROOF 4

Inflow Area = 0.430 ac, 100.00% Impervious, Inflow Depth > 4.12" for 5-yr event
 Inflow = 1.98 cfs @ 12.07 hrs, Volume= 0.148 af
 Outflow = 1.79 cfs @ 12.11 hrs, Volume= 0.106 af, Atten= 9%, Lag= 2.5 min
 Discarded = 0.02 cfs @ 12.11 hrs, Volume= 0.018 af
 Primary = 1.78 cfs @ 12.11 hrs, Volume= 0.088 af
 Routed to Pond INFIL BASIN B4 : INFIL BASIN B4

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 151.73' @ 12.11 hrs Surf.Area= 1,033 sf Storage= 2,264 cf

Plug-Flow detention time= 121.3 min calculated for 0.105 af (71% of inflow)
 Center-of-Mass det. time= 54.5 min (789.3 - 734.8)

Volume	Invert	Avail.Storage	Storage Description
#1A	148.50'	1,228 cf	18.50'W x 55.83'L x 4.50'H Field A 4,648 cf Overall - 1,578 cf Embedded = 3,070 cf x 40.0% Voids
#2A	149.00'	1,578 cf	Cultec R-360HD x 42 Inside #1 Effective Size= 54.9"W x 36.0"H => 9.99 sf x 3.67'L = 36.6 cf Overall Size= 60.0"W x 36.0"H x 4.17'L with 0.50' Overlap 42 Chambers in 3 Rows Cap Storage= 6.5 cf x 2 x 3 rows = 38.8 cf
		2,806 cf	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	151.00'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	148.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 138.00'

Discarded OutFlow Max=0.02 cfs @ 12.11 hrs HW=151.72' (Free Discharge)
 ↑**2=Exfiltration** (Controls 0.02 cfs)

Primary OutFlow Max=1.73 cfs @ 12.11 hrs HW=151.72' (Free Discharge)
 ↑**1=Orifice/Grate** (Orifice Controls 1.73 cfs @ 2.88 fps)

Pond U.G. INFIL ROOF 4: U.G. INFIL ROOF 4




Summary for Link PR DP1: PR DP1

Inflow Area = 106.945 ac, 22.75% Impervious, Inflow Depth > 1.50" for 5-yr event
Inflow = 47.63 cfs @ 13.43 hrs, Volume= 13.347 af
Primary = 47.63 cfs @ 13.43 hrs, Volume= 13.347 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link PR DP1: PR DP1

Hydrograph



Summary for Subcatchment NO ROOF 1: NO ROOF 1


Runoff = 2.34 cfs @ 12.07 hrs, Volume= 0.175 af, Depth> 4.88"
 Routed to Pond U.G. INFIL ROOF 1 : U.G. INFIL ROOF 1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-yr Rainfall=5.51"

Area (ac)	CN	Description
0.430	98	Paved parking, HSG B
0.430		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, ROOF 1

Subcatchment NO ROOF 1: NO ROOF 1



Summary for Subcatchment NO ROOF 2: NO ROOF 2

Runoff = 2.34 cfs @ 12.07 hrs, Volume= 0.175 af, Depth> 4.88"


Routed to Pond U.G. INFIL ROOF 2 : U.G. INFIL ROOF 2

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-yr Rainfall=5.51"

Area (ac)	CN	Description
0.430	98	Paved parking, HSG B
0.430		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, ROOF 1

Subcatchment NO ROOF 2: NO ROOF 2



Summary for Subcatchment NO ROOF 3: NO ROOF 3

Runoff = 2.34 cfs @ 12.07 hrs, Volume= 0.175 af, Depth> 4.88"


Routed to Pond U.G. INFIL ROOF 3 : U.G. INFIL ROOF 3

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-yr Rainfall=5.51"

Area (ac)	CN	Description
0.430	98	Paved parking, HSG B
0.430		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, ROOF 1

Subcatchment NO ROOF 3: NO ROOF 3



Summary for Subcatchment NO ROOF 4: NO ROOF 4

Runoff = 2.34 cfs @ 12.07 hrs, Volume= 0.175 af, Depth> 4.88"

Routed to Pond U.G. INFIL ROOF 4 : U.G. INFIL ROOF 4


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 10-yr Rainfall=5.51"

Area (ac)	CN	Description
0.430	98	Paved parking, HSG B
0.430		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, ROOF 1

Subcatchment NO ROOF 4: NO ROOF 4

Hydrograph



Summary for Subcatchment PR-DA 1A: PR-DA 1A

Runoff = 87.24 cfs @ 12.89 hrs, Volume= 14.963 af, Depth> 2.19"

Routed to Pond EXISTING POND : EXISTING POND


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-yr Rainfall=5.51"

Area (ac)	CN	Description
40.280	68	1 acre lots, 20% imp, HSG B
27.540	79	1 acre lots, 20% imp, HSG C
0.180	98	Paved parking, HSG B
11.690	55	Woods, Good, HSG B
0.120	61	>75% Grass cover, Good, HSG B
0.620	98	Paved parking, HSG C
1.450	70	Woods, Good, HSG C
0.270	74	>75% Grass cover, Good, HSG C
82.150	70	Weighted Average
67.786		82.51% Pervious Area
14.364		17.49% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
49.3	200	0.0100	0.07		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
0.8	130	0.0200	2.87		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
5.4	200	0.0150	0.61		Shallow Concentrated Flow, Shallow Concentrated Forest Woodland Kv= 5.0 fps
3.4	630	0.0230	3.08		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
4.6	2,300	0.0510	8.39	83.90	Channel Flow, Channel Flow Wooded Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.040 Winding stream, pools & shoals
63.5	3,460	Total			

Subcatchment PR-DA 1A: PR-DA 1A

Hydrograph



Summary for Subcatchment PR-DA 1B1: PR-DA 1B1

Runoff = 9.52 cfs @ 12.16 hrs, Volume= 0.775 af, Depth> 3.41"
 Routed to Pond INFIL 1B1 : INFILTRATOR 1B1


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-yr Rainfall=5.51"

Area (ac)	CN	Description
1.758	98	Paved parking, HSG B
0.697	55	Woods, Good, HSG B
0.270	61	>75% Grass cover, Good, HSG B
2.725	83	Weighted Average
0.967		35.49% Pervious Area
1.758		64.51% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.2	150	0.2300	0.22		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
0.5	80	0.0200	2.87		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
11.7	230	Total			

Subcatchment PR-DA 1B1: PR-DA 1B1

Hydrograph



Summary for Subcatchment PR-DA 1B2: PR-DA 1B2

Runoff = 9.49 cfs @ 12.15 hrs, Volume= 0.766 af, Depth> 3.82"
 Routed to Pond INFIL 1B2 : INFILTRATOR 1B2


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-yr Rainfall=5.51"

Area (ac)	CN	Description
1.760	98	Paved parking, HSG B
0.310	55	Woods, Good, HSG B
0.340	61	>75% Grass cover, Good, HSG B
2.410	87	Weighted Average
0.650		26.97% Pervious Area
1.760		73.03% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.0	70	0.0850	0.13		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
1.7	300	0.0200	2.87		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
10.7	370	Total			

Subcatchment PR-DA 1B2: PR-DA 1B2

Hydrograph



Summary for Subcatchment PR-DA 1B3: PR-DA 1B3


Runoff = 10.82 cfs @ 12.22 hrs, Volume= 0.971 af, Depth> 2.15"
 Routed to Pond INFIL BASIN B3 : INFIL BASIN B3

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-yr Rainfall=5.51"

Area (ac)	CN	Description
1.340	98	Paved parking, HSG B
1.200	55	Woods, Good, HSG B
2.890	61	>75% Grass cover, Good, HSG B
5.430	69	Weighted Average
4.090		75.32% Pervious Area
1.340		24.68% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
13.6	150	0.0200	0.18		Sheet Flow, Sheet Flow Grass Grass: Short n= 0.150 P2= 3.20"
0.7	90	0.0200	2.28		Shallow Concentrated Flow, Shallow Concentrated Grass Unpaved Kv= 16.1 fps
1.4	1,170	0.0600	13.49	42.37	Pipe Channel, RCP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.017 Concrete sewer w/manholes & inlets
15.7	1,410	Total			

Subcatchment PR-DA 1B3: PR-DA 1B3



Summary for Subcatchment PR-DA 1BND: PR-DA 1BND

Runoff = 2.01 cfs @ 12.07 hrs, Volume= 0.137 af, Depth> 3.82"


Routed to Pond EXISTING POND : EXISTING POND

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-yr Rainfall=5.51"

Area (ac)	CN	Description
0.300	98	Paved parking, HSG B
0.130	61	>75% Grass cover, Good, HSG B
0.430	87	Weighted Average
0.130		30.23% Pervious Area
0.300		69.77% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Not Detained-Direct Entry

Subcatchment PR-DA 1BND: PR-DA 1BND



Summary for Subcatchment PR-DA 1C: PR-DA 1C

Runoff = 7.75 cfs @ 12.15 hrs, Volume= 0.600 af, Depth> 1.83"
 Routed to Pond EXISTING POND : EXISTING POND


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-yr Rainfall=5.51"

Area (ac)	CN	Description
* 0.900	98	Water Surface
2.680	55	Woods, Good, HSG B
0.350	61	>75% Grass cover, Good, HSG B
3.930	65	Weighted Average
3.030		77.10% Pervious Area
0.900		22.90% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
8.1	90	0.1833	0.18		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
1.3	140	0.1290	1.80		Shallow Concentrated Flow, Shallow Concentrated Woods Woodland Kv= 5.0 fps
0.3	210	0.0660	12.73	127.25	Channel Flow, Stream Channel Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.030 Stream, clean & straight
9.7	440	Total			

Subcatchment PR-DA 1C: PR-DA 1C

Hydrograph



Summary for Subcatchment PR-DA-1B4: PR-DA 1B4

Runoff = 13.96 cfs @ 12.39 hrs, Volume= 1.564 af, Depth> 2.30"
 Routed to Pond INFIL BASIN B4 : INFIL BASIN B4


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-yr Rainfall=5.51"

Area (ac)	CN	Description
2.640	68	1 acre lots, 20% imp, HSG B
0.350	79	1 acre lots, 20% imp, HSG C
1.590	98	Paved parking, HSG B
1.010	55	Woods, Good, HSG B
2.560	61	>75% Grass cover, Good, HSG B
8.150	71	Weighted Average
5.962		73.15% Pervious Area
2.188		26.85% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
22.5	150	0.0400	0.11		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
3.8	950	0.0660	4.14		Shallow Concentrated Flow, Shallow Concentrated Woods Unpaved Kv= 16.1 fps
1.1	910	0.0660	14.15	44.44	Pipe Channel, RCP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.017 Concrete sewer w/manholes & inlets
27.4	2,010	Total			

Subcatchment PR-DA-1B4: PR-DA 1B4

Hydrograph



Summary for Pond EXISTING POND: EXISTING POND

Inflow Area = 106.945 ac, 22.75% Impervious, Inflow Depth > 2.16" for 10-yr event
 Inflow = 106.17 cfs @ 12.78 hrs, Volume= 19.213 af
 Outflow = 74.11 cfs @ 13.30 hrs, Volume= 18.469 af, Atten= 30%, Lag= 31.1 min
 Primary = 74.11 cfs @ 13.30 hrs, Volume= 18.469 af
 Routed to Link PR DP1 : PR DP1

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 76.36' @ 13.30 hrs Surf.Area= 1.393 ac Storage= 4.968 af

Plug-Flow detention time= 53.0 min calculated for 18.408 af (96% of inflow)
 Center-of-Mass det. time= 40.4 min (883.2 - 842.7)


Volume	Invert	Avail.Storage	Storage Description		
#1	71.80'	7.556 af	Existing Pond (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (acres)	Perim. (feet)	Inc.Store (acre-feet)	Cum.Store (acre-feet)	Wet.Area (acres)
71.80	0.938	1,000.1	0.000	0.000	0.938
74.00	1.020	1,016.0	2.153	2.153	1.016
76.00	1.320	1,692.0	2.334	4.487	4.360
78.00	1.760	1,652.0	3.069	7.556	4.617

Device	Routing	Invert	Outlet Devices
#1	Primary	71.80'	24.0" Round Culvert X 2.00 L= 100.0' Ke= 0.500 Inlet / Outlet Invert= 71.80' / 70.00' S= 0.0180 ' S Cc= 0.900 n= 0.011 Concrete pipe, straight & clean, Flow Area= 3.14 sf
#2	Primary	75.75'	12.0' long + 3.0 ' SideZ x 12.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.57 2.62 2.70 2.67 2.66 2.67 2.66 2.64
#3	Primary	76.75'	30.0' long + 3.0 ' SideZ x 30.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63

Primary OutFlow Max=74.12 cfs @ 13.30 hrs HW=76.35' (Free Discharge)

- 1=Culvert (Inlet Controls 57.04 cfs @ 9.08 fps)
- 2=Broad-Crested Rectangular Weir (Weir Controls 17.08 cfs @ 2.04 fps)
- 3=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Pond EXISTING POND: EXISTING POND



Summary for Pond INFIL 1B1: INFILTRATOR 1B1

Inflow Area = 2.725 ac, 64.51% Impervious, Inflow Depth > 3.41" for 10-yr event
 Inflow = 9.52 cfs @ 12.16 hrs, Volume= 0.775 af
 Outflow = 5.10 cfs @ 12.39 hrs, Volume= 0.574 af, Atten= 46%, Lag= 13.6 min
 Discarded = 0.09 cfs @ 12.39 hrs, Volume= 0.076 af
 Primary = 5.01 cfs @ 12.39 hrs, Volume= 0.498 af
 Routed to Pond INFIL 1B2 : INFILTRATOR 1B2

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 131.09' @ 12.39 hrs Surf.Area= 0.114 ac Storage= 0.302 af

Plug-Flow detention time= 109.4 min calculated for 0.572 af (74% of inflow)
 Center-of-Mass det. time= 49.1 min (830.5 - 781.4)

Volume	Invert	Avail.Storage	Storage Description
#1A	127.50'	0.170 af	23.00'W x 215.70'L x 6.00'H Field A 0.683 af Overall - 0.259 af Embedded = 0.424 af x 40.0% Voids
#2A	128.00'	0.259 af	Cultec R-902HD x 174 Inside #1 Effective Size= 69.8"W x 48.0"H => 17.65 sf x 3.67'L = 64.7 cf Overall Size= 78.0"W x 48.0"H x 4.10'L with 0.44' Overlap 174 Chambers in 3 Rows Cap Storage= 2.8 cf x 2 x 3 rows = 16.6 cf
		0.429 af	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	129.75'	15.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	127.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 120.00'

Discarded OutFlow Max=0.09 cfs @ 12.39 hrs HW=131.09' (Free Discharge)
 ↑**2=Exfiltration** (Controls 0.09 cfs)

Primary OutFlow Max=5.00 cfs @ 12.39 hrs HW=131.09' (Free Discharge)
 ↑**1=Orifice/Grate** (Orifice Controls 5.00 cfs @ 4.07 fps)

Pond INFIL 1B1: INFILTRATOR 1B1



Summary for Pond INFIL 1B2: INFILTRATOR 1B2

Inflow Area = 5.135 ac, 68.51% Impervious, Inflow Depth > 2.95" for 10-yr event
 Inflow = 11.72 cfs @ 12.21 hrs, Volume= 1.264 af
 Outflow = 7.92 cfs @ 12.51 hrs, Volume= 1.073 af, Atten= 32%, Lag= 17.7 min
 Discarded = 0.19 cfs @ 12.51 hrs, Volume= 0.139 af
 Primary = 7.74 cfs @ 12.51 hrs, Volume= 0.934 af
 Routed to Pond EXISTING POND : EXISTING POND

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 125.58' @ 12.51 hrs Surf.Area= 0.160 ac Storage= 0.368 af

Plug-Flow detention time= 80.0 min calculated for 1.069 af (85% of inflow)
 Center-of-Mass det. time= 38.1 min (831.0 - 792.9)

Volume	Invert	Avail.Storage	Storage Description
#1A	122.50'	0.236 af	30.25'W x 230.37'L x 6.00'H Field A 0.960 af Overall - 0.369 af Embedded = 0.591 af x 40.0% Voids
#2A	123.00'	0.369 af	Cultec R-902HD x 248 Inside #1 Effective Size= 69.8"W x 48.0"H => 17.65 sf x 3.67'L = 64.7 cf Overall Size= 78.0"W x 48.0"H x 4.10'L with 0.44' Overlap 248 Chambers in 4 Rows Cap Storage= 2.8 cf x 2 x 4 rows = 22.1 cf
		0.605 af	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	124.00'	18.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	122.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 120.00'

Discarded OutFlow Max=0.19 cfs @ 12.51 hrs HW=125.58' (Free Discharge)
 ↑**2=Exfiltration** (Controls 0.19 cfs)

Primary OutFlow Max=7.73 cfs @ 12.51 hrs HW=125.58' (Free Discharge)
 ↑**1=Orifice/Grate** (Orifice Controls 7.73 cfs @ 4.37 fps)

Pond INFIL 1B2: INFILTRATOR 1B2



Summary for Pond INFIL BASIN B3: INFIL BASIN B3

Inflow Area = 6.290 ac, 34.98% Impervious, Inflow Depth > 2.29" for 10-yr event
 Inflow = 13.68 cfs @ 12.19 hrs, Volume= 1.201 af
 Outflow = 10.59 cfs @ 12.35 hrs, Volume= 1.055 af, Atten= 23%, Lag= 9.6 min
 Discarded = 0.08 cfs @ 12.35 hrs, Volume= 0.048 af
 Primary = 10.51 cfs @ 12.35 hrs, Volume= 1.007 af
 Routed to Pond EXISTING POND : EXISTING POND

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 102.50' @ 12.35 hrs Surf.Area= 5,416 sf Storage= 12,583 cf

Plug-Flow detention time= 61.2 min calculated for 1.052 af (88% of inflow)
 Center-of-Mass det. time= 25.4 min (833.6 - 808.1)


Volume	Invert	Avail.Storage	Storage Description		
#1	99.50'	25,262 cf	Existing Pond (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
99.50	3,074	220.0	0	0	3,074
100.00	3,428	230.0	1,625	1,625	3,449
102.00	4,993	267.0	8,372	9,997	4,995
104.00	6,798	305.0	11,745	21,741	6,817
104.50	7,285	315.0	3,520	25,262	7,334

Device	Routing	Invert	Outlet Devices
#1	Primary	101.00'	24.0" Round Culvert L= 50.0' Ke= 0.500 Inlet / Outlet Invert= 101.00' / 100.00' S= 0.0200 '/' Cc= 0.900 n= 0.011 Concrete pipe, straight & clean, Flow Area= 3.14 sf
#2	Primary	103.50'	12.0' long + 3.0 ' SideZ x 6.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.37 2.51 2.70 2.68 2.68 2.67 2.65 2.65 2.65 2.65 2.66 2.66 2.67 2.69 2.72 2.76 2.83
#3	Discarded	99.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 89.00'

Discarded OutFlow Max=0.08 cfs @ 12.35 hrs HW=102.50' (Free Discharge)
 ↳3=Exfiltration (Controls 0.08 cfs)

Primary OutFlow Max=10.49 cfs @ 12.35 hrs HW=102.50' (Free Discharge)
 ↳1=Culvert (Inlet Controls 10.49 cfs @ 4.16 fps)
 ↳2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Pond INFIL BASIN B3: INFIL BASIN B3



Summary for Pond INFIL BASIN B4: INFIL BASIN B4

Inflow Area = 9.010 ac, 33.83% Impervious, Inflow Depth > 2.39" for 10-yr event
 Inflow = 15.55 cfs @ 12.37 hrs, Volume= 1.793 af
 Outflow = 15.41 cfs @ 12.41 hrs, Volume= 1.622 af, Atten= 1%, Lag= 2.2 min
 Discarded = 0.07 cfs @ 12.41 hrs, Volume= 0.049 af
 Primary = 15.34 cfs @ 12.41 hrs, Volume= 1.573 af
 Routed to Pond EXISTING POND : EXISTING POND

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 94.60' @ 12.41 hrs Surf.Area= 4,901 sf Storage= 10,010 cf

Plug-Flow detention time= 44.6 min calculated for 1.617 af (90% of inflow)
 Center-of-Mass det. time= 15.3 min (829.7 - 814.3)

Volume	Invert	Avail.Storage	Storage Description			
#1	92.00'	17,673 cf	Infil Basin B4 (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)	
92.00	2,832	377.0	0	0	2,832	
94.00	4,424	403.0	7,197	7,197	4,624	
96.00	6,097	428.0	10,476	17,673	6,475	

Device	Routing	Invert	Outlet Devices									
#1	Primary	94.00'	24.0" x 36.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads									
#2	Primary	95.50'	12.0' long + 3.0 ' SideZ x 6.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.37 2.51 2.70 2.68 2.68 2.67 2.65 2.65 2.65									
#3	Discarded	92.00'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 82.00'									

Discarded OutFlow Max=0.07 cfs @ 12.41 hrs HW=94.60' (Free Discharge)

↳ **3=Exfiltration** (Controls 0.07 cfs)


Primary OutFlow Max=15.29 cfs @ 12.41 hrs HW=94.60' (Free Discharge)

↳ **1=Orifice/Grate** (Weir Controls 15.29 cfs @ 2.54 fps)

↳ **2=Broad-Crested Rectangular Weir** (Controls 0.00 cfs)

Pond INFIL BASIN B4: INFIL BASIN B4

Hydrograph



Summary for Pond U.G. INFIL ROOF 1: U.G. INFIL ROOF 1

Inflow Area = 0.430 ac, 100.00% Impervious, Inflow Depth > 4.88" for 10-yr event
 Inflow = 2.34 cfs @ 12.07 hrs, Volume= 0.175 af
 Outflow = 2.16 cfs @ 12.11 hrs, Volume= 0.133 af, Atten= 8%, Lag= 2.3 min
 Discarded = 0.02 cfs @ 12.11 hrs, Volume= 0.018 af
 Primary = 2.14 cfs @ 12.11 hrs, Volume= 0.115 af
 Routed to Pond INFIL BASIN B3 : INFIL BASIN B3

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 151.82' @ 12.11 hrs Surf.Area= 1,033 sf Storage= 2,313 cf

Plug-Flow detention time= 112.0 min calculated for 0.132 af (76% of inflow)
 Center-of-Mass det. time= 51.7 min (785.6 - 733.8)

Volume	Invert	Avail.Storage	Storage Description
#1A	148.50'	1,228 cf	18.50'W x 55.83'L x 4.50'H Field A 4,648 cf Overall - 1,578 cf Embedded = 3,070 cf x 40.0% Voids
#2A	149.00'	1,578 cf	Cultec R-360HD x 42 Inside #1 Effective Size= 54.9"W x 36.0"H => 9.99 sf x 3.67'L = 36.6 cf Overall Size= 60.0"W x 36.0"H x 4.17'L with 0.50' Overlap 42 Chambers in 3 Rows Cap Storage= 6.5 cf x 2 x 3 rows = 38.8 cf
		2,806 cf	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	151.00'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	148.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 138.00'

Discarded OutFlow Max=0.02 cfs @ 12.11 hrs HW=151.81' (Free Discharge)
 ↳ **2=Exfiltration** (Controls 0.02 cfs)

Primary OutFlow Max=2.10 cfs @ 12.11 hrs HW=151.81' (Free Discharge)
 ↳ **1=Orifice/Grate** (Orifice Controls 2.10 cfs @ 3.07 fps)

Pond U.G. INFIL ROOF 1: U.G. INFIL ROOF 1



Summary for Pond U.G. INFIL ROOF 2: U.G. INFIL ROOF 2

Inflow Area = 0.430 ac, 100.00% Impervious, Inflow Depth > 4.88" for 10-yr event
 Inflow = 2.34 cfs @ 12.07 hrs, Volume= 0.175 af
 Outflow = 2.16 cfs @ 12.11 hrs, Volume= 0.133 af, Atten= 8%, Lag= 2.3 min
 Discarded = 0.02 cfs @ 12.11 hrs, Volume= 0.018 af
 Primary = 2.14 cfs @ 12.11 hrs, Volume= 0.115 af
 Routed to Pond INFIL BASIN B3 : INFIL BASIN B3

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 151.82' @ 12.11 hrs Surf.Area= 1,033 sf Storage= 2,313 cf

Plug-Flow detention time= 112.0 min calculated for 0.132 af (76% of inflow)
 Center-of-Mass det. time= 51.7 min (785.6 - 733.8)

Volume	Invert	Avail.Storage	Storage Description
#1A	148.50'	1,228 cf	18.50'W x 55.83'L x 4.50'H Field A 4,648 cf Overall - 1,578 cf Embedded = 3,070 cf x 40.0% Voids
#2A	149.00'	1,578 cf	Cultec R-360HD x 42 Inside #1 Effective Size= 54.9"W x 36.0"H => 9.99 sf x 3.67'L = 36.6 cf Overall Size= 60.0"W x 36.0"H x 4.17'L with 0.50' Overlap 42 Chambers in 3 Rows Cap Storage= 6.5 cf x 2 x 3 rows = 38.8 cf
		2,806 cf	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	151.00'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	148.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 138.00'

Discarded OutFlow Max=0.02 cfs @ 12.11 hrs HW=151.81' (Free Discharge)
 ↳ **2=Exfiltration** (Controls 0.02 cfs)

Primary OutFlow Max=2.10 cfs @ 12.11 hrs HW=151.81' (Free Discharge)
 ↳ **1=Orifice/Grate** (Orifice Controls 2.10 cfs @ 3.07 fps)

Pond U.G. INFIL ROOF 2: U.G. INFIL ROOF 2



Summary for Pond U.G. INFIL ROOF 3: U.G. INFIL ROOF 3

Inflow Area = 0.430 ac, 100.00% Impervious, Inflow Depth > 4.88" for 10-yr event
 Inflow = 2.34 cfs @ 12.07 hrs, Volume= 0.175 af
 Outflow = 2.16 cfs @ 12.11 hrs, Volume= 0.133 af, Atten= 8%, Lag= 2.3 min
 Discarded = 0.02 cfs @ 12.11 hrs, Volume= 0.018 af
 Primary = 2.14 cfs @ 12.11 hrs, Volume= 0.115 af
 Routed to Pond INFIL BASIN B4 : INFIL BASIN B4

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 151.82' @ 12.11 hrs Surf.Area= 1,033 sf Storage= 2,313 cf

Plug-Flow detention time= 112.0 min calculated for 0.132 af (76% of inflow)
 Center-of-Mass det. time= 51.7 min (785.6 - 733.8)

Volume	Invert	Avail.Storage	Storage Description
#1A	148.50'	1,228 cf	18.50'W x 55.83'L x 4.50'H Field A 4,648 cf Overall - 1,578 cf Embedded = 3,070 cf x 40.0% Voids
#2A	149.00'	1,578 cf	Cultec R-360HD x 42 Inside #1 Effective Size= 54.9"W x 36.0"H => 9.99 sf x 3.67'L = 36.6 cf Overall Size= 60.0"W x 36.0"H x 4.17'L with 0.50' Overlap 42 Chambers in 3 Rows Cap Storage= 6.5 cf x 2 x 3 rows = 38.8 cf
		2,806 cf	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	151.00'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	148.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 138.00'

Discarded OutFlow Max=0.02 cfs @ 12.11 hrs HW=151.81' (Free Discharge)
 ↳ **2=Exfiltration** (Controls 0.02 cfs)

Primary OutFlow Max=2.10 cfs @ 12.11 hrs HW=151.81' (Free Discharge)
 ↳ **1=Orifice/Grate** (Orifice Controls 2.10 cfs @ 3.07 fps)

Pond U.G. INFIL ROOF 3: U.G. INFIL ROOF 3



Summary for Pond U.G. INFIL ROOF 4: U.G. INFIL ROOF 4

Inflow Area = 0.430 ac, 100.00% Impervious, Inflow Depth > 4.88" for 10-yr event
 Inflow = 2.34 cfs @ 12.07 hrs, Volume= 0.175 af
 Outflow = 2.16 cfs @ 12.11 hrs, Volume= 0.133 af, Atten= 8%, Lag= 2.3 min
 Discarded = 0.02 cfs @ 12.11 hrs, Volume= 0.018 af
 Primary = 2.14 cfs @ 12.11 hrs, Volume= 0.115 af
 Routed to Pond INFIL BASIN B4 : INFIL BASIN B4

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 151.82' @ 12.11 hrs Surf.Area= 1,033 sf Storage= 2,313 cf

Plug-Flow detention time= 112.0 min calculated for 0.132 af (76% of inflow)
 Center-of-Mass det. time= 51.7 min (785.6 - 733.8)

Volume	Invert	Avail.Storage	Storage Description
#1A	148.50'	1,228 cf	18.50'W x 55.83'L x 4.50'H Field A 4,648 cf Overall - 1,578 cf Embedded = 3,070 cf x 40.0% Voids
#2A	149.00'	1,578 cf	Cultec R-360HD x 42 Inside #1 Effective Size= 54.9"W x 36.0"H => 9.99 sf x 3.67'L = 36.6 cf Overall Size= 60.0"W x 36.0"H x 4.17'L with 0.50' Overlap 42 Chambers in 3 Rows Cap Storage= 6.5 cf x 2 x 3 rows = 38.8 cf
		2,806 cf	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	151.00'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	148.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 138.00'

Discarded OutFlow Max=0.02 cfs @ 12.11 hrs HW=151.81' (Free Discharge)
 ↳ **2=Exfiltration** (Controls 0.02 cfs)

Primary OutFlow Max=2.10 cfs @ 12.11 hrs HW=151.81' (Free Discharge)
 ↳ **1=Orifice/Grate** (Orifice Controls 2.10 cfs @ 3.07 fps)

Pond U.G. INFIL ROOF 4: U.G. INFIL ROOF 4




Summary for Link PR DP1: PR DP1

Inflow Area = 106.945 ac, 22.75% Impervious, Inflow Depth > 2.07" for 10-yr event
Inflow = 74.11 cfs @ 13.30 hrs, Volume= 18.469 af
Primary = 74.11 cfs @ 13.30 hrs, Volume= 18.469 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link PR DP1: PR DP1

Hydrograph



Summary for Subcatchment NO ROOF 1: NO ROOF 1

Runoff = 2.83 cfs @ 12.07 hrs, Volume= 0.213 af, Depth> 5.94"


Routed to Pond U.G. INFIL ROOF 1 : U.G. INFIL ROOF 1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 25-yr Rainfall=6.67"

Area (ac)	CN	Description
0.430	98	Paved parking, HSG B
0.430		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, ROOF 1

Subcatchment NO ROOF 1: NO ROOF 1



Summary for Subcatchment NO ROOF 2: NO ROOF 2

Runoff = 2.83 cfs @ 12.07 hrs, Volume= 0.213 af, Depth> 5.94"

Routed to Pond U.G. INFIL ROOF 2 : U.G. INFIL ROOF 2


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 25-yr Rainfall=6.67"

Area (ac)	CN	Description
0.430	98	Paved parking, HSG B
0.430		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, ROOF 1

Subcatchment NO ROOF 2: NO ROOF 2

Hydrograph



Summary for Subcatchment NO ROOF 3: NO ROOF 3

Runoff = 2.83 cfs @ 12.07 hrs, Volume= 0.213 af, Depth> 5.94"

Routed to Pond U.G. INFIL ROOF 3 : U.G. INFIL ROOF 3


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 25-yr Rainfall=6.67"

Area (ac)	CN	Description
0.430	98	Paved parking, HSG B
0.430		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, ROOF 1

Subcatchment NO ROOF 3: NO ROOF 3

Hydrograph



Summary for Subcatchment NO ROOF 4: NO ROOF 4

Runoff = 2.83 cfs @ 12.07 hrs, Volume= 0.213 af, Depth> 5.94"


Routed to Pond U.G. INFIL ROOF 4 : U.G. INFIL ROOF 4

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 25-yr Rainfall=6.67"

Area (ac)	CN	Description
0.430	98	Paved parking, HSG B
0.430		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, ROOF 1

Subcatchment NO ROOF 4: NO ROOF 4



Summary for Subcatchment PR-DA 1A: PR-DA 1A

Runoff = 121.83 cfs @ 12.88 hrs, Volume= 20.816 af, Depth> 3.04"

Routed to Pond EXISTING POND : EXISTING POND


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 25-yr Rainfall=6.67"

Area (ac)	CN	Description
40.280	68	1 acre lots, 20% imp, HSG B
27.540	79	1 acre lots, 20% imp, HSG C
0.180	98	Paved parking, HSG B
11.690	55	Woods, Good, HSG B
0.120	61	>75% Grass cover, Good, HSG B
0.620	98	Paved parking, HSG C
1.450	70	Woods, Good, HSG C
0.270	74	>75% Grass cover, Good, HSG C
82.150	70	Weighted Average
67.786		82.51% Pervious Area
14.364		17.49% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
49.3	200	0.0100	0.07		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
0.8	130	0.0200	2.87		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
5.4	200	0.0150	0.61		Shallow Concentrated Flow, Shallow Concentrated Forest Woodland Kv= 5.0 fps
3.4	630	0.0230	3.08		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
4.6	2,300	0.0510	8.39	83.90	Channel Flow, Channel Flow Wooded Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.040 Winding stream, pools & shoals
63.5	3,460	Total			

Subcatchment PR-DA 1A: PR-DA 1A

Hydrograph



Summary for Subcatchment PR-DA 1B1: PR-DA 1B1

Runoff = 12.24 cfs @ 12.16 hrs, Volume= 1.007 af, Depth> 4.44"
 Routed to Pond INFIL 1B1 : INFILTRATOR 1B1


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 25-yr Rainfall=6.67"

Area (ac)	CN	Description
1.758	98	Paved parking, HSG B
0.697	55	Woods, Good, HSG B
0.270	61	>75% Grass cover, Good, HSG B
2.725	83	Weighted Average
0.967		35.49% Pervious Area
1.758		64.51% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.2	150	0.2300	0.22		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
0.5	80	0.0200	2.87		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
11.7	230	Total			

Subcatchment PR-DA 1B1: PR-DA 1B1

Hydrograph



Summary for Subcatchment PR-DA 1B2: PR-DA 1B2

Runoff = 11.95 cfs @ 12.15 hrs, Volume= 0.978 af, Depth> 4.87"
 Routed to Pond INFIL 1B2 : INFILTRATOR 1B2


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 25-yr Rainfall=6.67"

Area (ac)	CN	Description
1.760	98	Paved parking, HSG B
0.310	55	Woods, Good, HSG B
0.340	61	>75% Grass cover, Good, HSG B
2.410	87	Weighted Average
0.650		26.97% Pervious Area
1.760		73.03% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.0	70	0.0850	0.13		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
1.7	300	0.0200	2.87		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
10.7	370	Total			

Subcatchment PR-DA 1B2: PR-DA 1B2

Hydrograph



Summary for Subcatchment PR-DA 1B3: PR-DA 1B3


Runoff = 15.22 cfs @ 12.22 hrs, Volume= 1.357 af, Depth> 3.00"
 Routed to Pond INFIL BASIN B3 : INFIL BASIN B3

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 25-yr Rainfall=6.67"

Area (ac)	CN	Description
1.340	98	Paved parking, HSG B
1.200	55	Woods, Good, HSG B
2.890	61	>75% Grass cover, Good, HSG B
5.430	69	Weighted Average
4.090		75.32% Pervious Area
1.340		24.68% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
13.6	150	0.0200	0.18		Sheet Flow, Sheet Flow Grass Grass: Short n= 0.150 P2= 3.20"
0.7	90	0.0200	2.28		Shallow Concentrated Flow, Shallow Concentrated Grass Unpaved Kv= 16.1 fps
1.4	1,170	0.0600	13.49	42.37	Pipe Channel, RCP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.017 Concrete sewer w/manholes & inlets
15.7	1,410	Total			

Subcatchment PR-DA 1B3: PR-DA 1B3



Summary for Subcatchment PR-DA 1BND: PR-DA 1BND

Runoff = 2.53 cfs @ 12.07 hrs, Volume= 0.175 af, Depth> 4.88"


Routed to Pond EXISTING POND : EXISTING POND

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 25-yr Rainfall=6.67"

Area (ac)	CN	Description
0.300	98	Paved parking, HSG B
0.130	61	>75% Grass cover, Good, HSG B
0.430	87	Weighted Average
0.130		30.23% Pervious Area
0.300		69.77% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Not Detained-Direct Entry

Subcatchment PR-DA 1BND: PR-DA 1BND



Summary for Subcatchment PR-DA 1C: PR-DA 1C

Runoff = 11.27 cfs @ 12.15 hrs, Volume= 0.860 af, Depth> 2.63"


Routed to Pond EXISTING POND : EXISTING POND

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 25-yr Rainfall=6.67"

Area (ac)	CN	Description
* 0.900	98	Water Surface
2.680	55	Woods, Good, HSG B
0.350	61	>75% Grass cover, Good, HSG B
3.930	65	Weighted Average
3.030		77.10% Pervious Area
0.900		22.90% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
8.1	90	0.1833	0.18		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
1.3	140	0.1290	1.80		Shallow Concentrated Flow, Shallow Concentrated Woods Woodland Kv= 5.0 fps
0.3	210	0.0660	12.73	127.25	Channel Flow, Stream Channel Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.030 Stream, clean & straight
9.7	440	Total			

Subcatchment PR-DA 1C: PR-DA 1C



Summary for Subcatchment PR-DA-1B4: PR-DA 1B4

Runoff = 19.33 cfs @ 12.39 hrs, Volume= 2.161 af, Depth> 3.18"
 Routed to Pond INFIL BASIN B4 : INFIL BASIN B4


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 25-yr Rainfall=6.67"

Area (ac)	CN	Description
2.640	68	1 acre lots, 20% imp, HSG B
0.350	79	1 acre lots, 20% imp, HSG C
1.590	98	Paved parking, HSG B
1.010	55	Woods, Good, HSG B
2.560	61	>75% Grass cover, Good, HSG B
8.150	71	Weighted Average
5.962		73.15% Pervious Area
2.188		26.85% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
22.5	150	0.0400	0.11		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
3.8	950	0.0660	4.14		Shallow Concentrated Flow, Shallow Concentrated Woods Unpaved Kv= 16.1 fps
1.1	910	0.0660	14.15	44.44	Pipe Channel, RCP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.017 Concrete sewer w/manholes & inlets
27.4	2,010	Total			

Subcatchment PR-DA-1B4: PR-DA 1B4

Hydrograph



Summary for Pond EXISTING POND: EXISTING POND

Inflow Area = 106.945 ac, 22.75% Impervious, Inflow Depth > 3.02" for 25-yr event
 Inflow = 148.63 cfs @ 12.77 hrs, Volume= 26.905 af
 Outflow = 130.53 cfs @ 13.07 hrs, Volume= 26.048 af, Atten= 12%, Lag= 17.7 min
 Primary = 130.53 cfs @ 13.07 hrs, Volume= 26.048 af
 Routed to Link PR DP1 : PR DP1

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 77.02' @ 13.07 hrs Surf.Area= 1.536 ac Storage= 5.936 af

Plug-Flow detention time= 47.7 min calculated for 26.048 af (97% of inflow)
 Center-of-Mass det. time= 36.9 min (872.4 - 835.5)

Volume	Invert	Avail.Storage	Storage Description		
#1	71.80'	7.556 af	Existing Pond (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (acres)	Perim. (feet)	Inc.Store (acre-feet)	Cum.Store (acre-feet)	Wet.Area (acres)
71.80	0.938	1,000.1	0.000	0.000	0.938
74.00	1.020	1,016.0	2.153	2.153	1.016
76.00	1.320	1,692.0	2.334	4.487	4.360
78.00	1.760	1,652.0	3.069	7.556	4.617


Device	Routing	Invert	Outlet Devices
#1	Primary	71.80'	24.0" Round Culvert X 2.00 L= 100.0' Ke= 0.500 Inlet / Outlet Invert= 71.80' / 70.00' S= 0.0180 ' S Cc= 0.900 n= 0.011 Concrete pipe, straight & clean, Flow Area= 3.14 sf
#2	Primary	75.75'	12.0' long + 3.0 ' SideZ x 12.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.57 2.62 2.70 2.67 2.66 2.67 2.66 2.64
#3	Primary	76.75'	30.0' long + 3.0 ' SideZ x 30.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63

Primary OutFlow Max=130.23 cfs @ 13.07 hrs HW=77.01' (Free Discharge)

- 1=Culvert (Inlet Controls 62.10 cfs @ 9.88 fps)
- 2=Broad-Crested Rectangular Weir (Weir Controls 56.97 cfs @ 2.85 fps)
- 3=Broad-Crested Rectangular Weir (Weir Controls 11.16 cfs @ 1.37 fps)

Pond EXISTING POND: EXISTING POND

Hydrograph



Summary for Pond INFIL 1B1: INFILTRATOR 1B1

Inflow Area = 2.725 ac, 64.51% Impervious, Inflow Depth > 4.44" for 25-yr event
 Inflow = 12.24 cfs @ 12.16 hrs, Volume= 1.007 af
 Outflow = 7.38 cfs @ 12.34 hrs, Volume= 0.804 af, Atten= 40%, Lag= 11.0 min
 Discarded = 0.09 cfs @ 12.34 hrs, Volume= 0.081 af
 Primary = 7.28 cfs @ 12.34 hrs, Volume= 0.722 af
 Routed to Pond INFIL 1B2 : INFILTRATOR 1B2

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 131.89' @ 12.34 hrs Surf.Area= 0.114 ac Storage= 0.355 af

Plug-Flow detention time= 95.7 min calculated for 0.801 af (80% of inflow)
 Center-of-Mass det. time= 43.5 min (818.7 - 775.2)

Volume	Invert	Avail.Storage	Storage Description
#1A	127.50'	0.170 af	23.00'W x 215.70'L x 6.00'H Field A 0.683 af Overall - 0.259 af Embedded = 0.424 af x 40.0% Voids
#2A	128.00'	0.259 af	Cultec R-902HD x 174 Inside #1 Effective Size= 69.8"W x 48.0"H => 17.65 sf x 3.67'L = 64.7 cf Overall Size= 78.0"W x 48.0"H x 4.10'L with 0.44' Overlap 174 Chambers in 3 Rows Cap Storage= 2.8 cf x 2 x 3 rows = 16.6 cf
		0.429 af	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	129.75'	15.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	127.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 120.00'

Discarded OutFlow Max=0.09 cfs @ 12.34 hrs HW=131.89' (Free Discharge)
 ↑**2=Exfiltration** (Controls 0.09 cfs)

Primary OutFlow Max=7.27 cfs @ 12.34 hrs HW=131.89' (Free Discharge)
 ↑**1=Orifice/Grate** (Orifice Controls 7.27 cfs @ 5.93 fps)

Pond INFIL 1B1: INFILTRATOR 1B1



Summary for Pond INFIL 1B2: INFILTRATOR 1B2

Inflow Area = 5.135 ac, 68.51% Impervious, Inflow Depth > 3.97" for 25-yr event
 Inflow = 17.26 cfs @ 12.17 hrs, Volume= 1.700 af
 Outflow = 11.16 cfs @ 12.47 hrs, Volume= 1.504 af, Atten= 35%, Lag= 18.1 min
 Discarded = 0.21 cfs @ 12.47 hrs, Volume= 0.150 af
 Primary = 10.94 cfs @ 12.47 hrs, Volume= 1.354 af
 Routed to Pond EXISTING POND : EXISTING POND

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 126.40' @ 12.47 hrs Surf.Area= 0.160 ac Storage= 0.460 af

Plug-Flow detention time= 68.9 min calculated for 1.504 af (88% of inflow)
 Center-of-Mass det. time= 33.9 min (821.2 - 787.3)

Volume	Invert	Avail.Storage	Storage Description
#1A	122.50'	0.236 af	30.25'W x 230.37'L x 6.00'H Field A 0.960 af Overall - 0.369 af Embedded = 0.591 af x 40.0% Voids
#2A	123.00'	0.369 af	Cultec R-902HD x 248 Inside #1 Effective Size= 69.8"W x 48.0"H => 17.65 sf x 3.67'L = 64.7 cf Overall Size= 78.0"W x 48.0"H x 4.10'L with 0.44' Overlap 248 Chambers in 4 Rows Cap Storage= 2.8 cf x 2 x 4 rows = 22.1 cf
		0.605 af	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	124.00'	18.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	122.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 120.00'

Discarded OutFlow Max=0.21 cfs @ 12.47 hrs HW=126.40' (Free Discharge)
 ↳ **2=Exfiltration** (Controls 0.21 cfs)

Primary OutFlow Max=10.92 cfs @ 12.47 hrs HW=126.40' (Free Discharge)
 ↳ **1=Orifice/Grate** (Orifice Controls 10.92 cfs @ 6.18 fps)

Pond INFIL 1B2: INFILTRATOR 1B2



Summary for Pond INFIL BASIN B3: INFIL BASIN B3

Inflow Area = 6.290 ac, 34.98% Impervious, Inflow Depth > 3.17" for 25-yr event
 Inflow = 18.70 cfs @ 12.19 hrs, Volume= 1.662 af
 Outflow = 14.97 cfs @ 12.33 hrs, Volume= 1.512 af, Atten= 20%, Lag= 8.3 min
 Discarded = 0.09 cfs @ 12.33 hrs, Volume= 0.052 af
 Primary = 14.88 cfs @ 12.33 hrs, Volume= 1.461 af
 Routed to Pond EXISTING POND : EXISTING POND

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 102.96' @ 12.33 hrs Surf.Area= 5,822 sf Storage= 15,167 cf

Plug-Flow detention time= 50.7 min calculated for 1.512 af (91% of inflow)
 Center-of-Mass det. time= 21.8 min (823.3 - 801.4)


Volume	Invert	Avail.Storage	Storage Description		
#1	99.50'	25,262 cf	Existing Pond (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
99.50	3,074	220.0	0	0	3,074
100.00	3,428	230.0	1,625	1,625	3,449
102.00	4,993	267.0	8,372	9,997	4,995
104.00	6,798	305.0	11,745	21,741	6,817
104.50	7,285	315.0	3,520	25,262	7,334

Device	Routing	Invert	Outlet Devices
#1	Primary	101.00'	24.0" Round Culvert L= 50.0' Ke= 0.500 Inlet / Outlet Invert= 101.00' / 100.00' S= 0.0200 ' S= 0.0200 ' Cc= 0.900 n= 0.011 Concrete pipe, straight & clean, Flow Area= 3.14 sf
#2	Primary	103.50'	12.0' long + 3.0 ' SideZ x 6.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.37 2.51 2.70 2.68 2.68 2.67 2.65 2.65 2.65 2.65 2.66 2.66 2.67 2.69 2.72 2.76 2.83
#3	Discarded	99.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 89.00'

Discarded OutFlow Max=0.09 cfs @ 12.33 hrs HW=102.95' (Free Discharge)
 ↳3=Exfiltration (Controls 0.09 cfs)

Primary OutFlow Max=14.85 cfs @ 12.33 hrs HW=102.95' (Free Discharge)
 ↳1=Culvert (Inlet Controls 14.85 cfs @ 4.76 fps)
 ↳2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Pond INFIL BASIN B3: INFIL BASIN B3



Summary for Pond INFIL BASIN B4: INFIL BASIN B4

Inflow Area = 9.010 ac, 33.83% Impervious, Inflow Depth > 3.28" for 25-yr event
 Inflow = 21.27 cfs @ 12.37 hrs, Volume= 2.465 af
 Outflow = 21.10 cfs @ 12.40 hrs, Volume= 2.293 af, Atten= 1%, Lag= 2.1 min
 Discarded = 0.07 cfs @ 12.40 hrs, Volume= 0.053 af
 Primary = 21.03 cfs @ 12.40 hrs, Volume= 2.239 af
 Routed to Pond EXISTING POND : EXISTING POND

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 94.74' @ 12.40 hrs Surf.Area= 5,016 sf Storage= 10,710 cf

Plug-Flow detention time= 36.4 min calculated for 2.293 af (93% of inflow)
 Center-of-Mass det. time= 13.3 min (820.9 - 807.7)

Volume	Invert	Avail.Storage	Storage Description			
#1	92.00'	17,673 cf	Infil Basin B4 (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)	
92.00	2,832	377.0	0	0	2,832	
94.00	4,424	403.0	7,197	7,197	4,624	
96.00	6,097	428.0	10,476	17,673	6,475	


Device	Routing	Invert	Outlet Devices									
#1	Primary	94.00'	24.0" x 36.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads									
#2	Primary	95.50'	12.0' long + 3.0 ' SideZ x 6.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.37 2.51 2.70 2.68 2.68 2.67 2.65 2.65 2.65									
#3	Discarded	92.00'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 82.00'									

Discarded OutFlow Max=0.07 cfs @ 12.40 hrs HW=94.74' (Free Discharge)
 ↳3=Exfiltration (Controls 0.07 cfs)

Primary OutFlow Max=20.99 cfs @ 12.40 hrs HW=94.74' (Free Discharge)
 ↳1=Orifice/Grate (Weir Controls 20.99 cfs @ 2.82 fps)
 ↳2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

Pond INFIL BASIN B4: INFIL BASIN B4

Hydrograph



Summary for Pond U.G. INFIL ROOF 1: U.G. INFIL ROOF 1

Inflow Area = 0.430 ac, 100.00% Impervious, Inflow Depth > 5.94" for 25-yr event
 Inflow = 2.83 cfs @ 12.07 hrs, Volume= 0.213 af
 Outflow = 2.61 cfs @ 12.11 hrs, Volume= 0.170 af, Atten= 8%, Lag= 2.2 min
 Discarded = 0.02 cfs @ 12.11 hrs, Volume= 0.018 af
 Primary = 2.59 cfs @ 12.11 hrs, Volume= 0.152 af
 Routed to Pond INFIL BASIN B3 : INFIL BASIN B3

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 151.96' @ 12.11 hrs Surf.Area= 1,033 sf Storage= 2,377 cf

Plug-Flow detention time= 102.8 min calculated for 0.170 af (80% of inflow)
 Center-of-Mass det. time= 48.7 min (781.7 - 733.0)

Volume	Invert	Avail.Storage	Storage Description
#1A	148.50'	1,228 cf	18.50'W x 55.83'L x 4.50'H Field A 4,648 cf Overall - 1,578 cf Embedded = 3,070 cf x 40.0% Voids
#2A	149.00'	1,578 cf	Cultec R-360HD x 42 Inside #1 Effective Size= 54.9"W x 36.0"H => 9.99 sf x 3.67'L = 36.6 cf Overall Size= 60.0"W x 36.0"H x 4.17'L with 0.50' Overlap 42 Chambers in 3 Rows Cap Storage= 6.5 cf x 2 x 3 rows = 38.8 cf
		2,806 cf	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	151.00'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	148.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 138.00'

Discarded OutFlow Max=0.02 cfs @ 12.11 hrs HW=151.95' (Free Discharge)
 ↑**2=Exfiltration** (Controls 0.02 cfs)

Primary OutFlow Max=2.56 cfs @ 12.11 hrs HW=151.95' (Free Discharge)
 ↑**1=Orifice/Grate** (Orifice Controls 2.56 cfs @ 3.32 fps)

Pond U.G. INFIL ROOF 1: U.G. INFIL ROOF 1



Summary for Pond U.G. INFIL ROOF 2: U.G. INFIL ROOF 2

Inflow Area = 0.430 ac, 100.00% Impervious, Inflow Depth > 5.94" for 25-yr event
 Inflow = 2.83 cfs @ 12.07 hrs, Volume= 0.213 af
 Outflow = 2.61 cfs @ 12.11 hrs, Volume= 0.170 af, Atten= 8%, Lag= 2.2 min
 Discarded = 0.02 cfs @ 12.11 hrs, Volume= 0.018 af
 Primary = 2.59 cfs @ 12.11 hrs, Volume= 0.152 af
 Routed to Pond INFIL BASIN B3 : INFIL BASIN B3

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 151.96' @ 12.11 hrs Surf.Area= 1,033 sf Storage= 2,377 cf

Plug-Flow detention time= 102.8 min calculated for 0.170 af (80% of inflow)
 Center-of-Mass det. time= 48.7 min (781.7 - 733.0)

Volume	Invert	Avail.Storage	Storage Description
#1A	148.50'	1,228 cf	18.50'W x 55.83'L x 4.50'H Field A 4,648 cf Overall - 1,578 cf Embedded = 3,070 cf x 40.0% Voids
#2A	149.00'	1,578 cf	Cultec R-360HD x 42 Inside #1 Effective Size= 54.9"W x 36.0"H => 9.99 sf x 3.67'L = 36.6 cf Overall Size= 60.0"W x 36.0"H x 4.17'L with 0.50' Overlap 42 Chambers in 3 Rows Cap Storage= 6.5 cf x 2 x 3 rows = 38.8 cf
		2,806 cf	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	151.00'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	148.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 138.00'

Discarded OutFlow Max=0.02 cfs @ 12.11 hrs HW=151.95' (Free Discharge)
 ↑**2=Exfiltration** (Controls 0.02 cfs)

Primary OutFlow Max=2.56 cfs @ 12.11 hrs HW=151.95' (Free Discharge)
 ↑**1=Orifice/Grate** (Orifice Controls 2.56 cfs @ 3.32 fps)

Pond U.G. INFIL ROOF 2: U.G. INFIL ROOF 2



Summary for Pond U.G. INFIL ROOF 3: U.G. INFIL ROOF 3

Inflow Area = 0.430 ac, 100.00% Impervious, Inflow Depth > 5.94" for 25-yr event
 Inflow = 2.83 cfs @ 12.07 hrs, Volume= 0.213 af
 Outflow = 2.61 cfs @ 12.11 hrs, Volume= 0.170 af, Atten= 8%, Lag= 2.2 min
 Discarded = 0.02 cfs @ 12.11 hrs, Volume= 0.018 af
 Primary = 2.59 cfs @ 12.11 hrs, Volume= 0.152 af
 Routed to Pond INFIL BASIN B4 : INFIL BASIN B4

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 151.96' @ 12.11 hrs Surf.Area= 1,033 sf Storage= 2,377 cf

Plug-Flow detention time= 102.8 min calculated for 0.170 af (80% of inflow)
 Center-of-Mass det. time= 48.7 min (781.7 - 733.0)

Volume	Invert	Avail.Storage	Storage Description
#1A	148.50'	1,228 cf	18.50'W x 55.83'L x 4.50'H Field A 4,648 cf Overall - 1,578 cf Embedded = 3,070 cf x 40.0% Voids
#2A	149.00'	1,578 cf	Cultec R-360HD x 42 Inside #1 Effective Size= 54.9"W x 36.0"H => 9.99 sf x 3.67'L = 36.6 cf Overall Size= 60.0"W x 36.0"H x 4.17'L with 0.50' Overlap 42 Chambers in 3 Rows Cap Storage= 6.5 cf x 2 x 3 rows = 38.8 cf
		2,806 cf	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	151.00'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	148.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 138.00'

Discarded OutFlow Max=0.02 cfs @ 12.11 hrs HW=151.95' (Free Discharge)
 ↑**2=Exfiltration** (Controls 0.02 cfs)

Primary OutFlow Max=2.56 cfs @ 12.11 hrs HW=151.95' (Free Discharge)
 ↑**1=Orifice/Grate** (Orifice Controls 2.56 cfs @ 3.32 fps)

Pond U.G. INFIL ROOF 3: U.G. INFIL ROOF 3



Summary for Pond U.G. INFIL ROOF 4: U.G. INFIL ROOF 4

Inflow Area = 0.430 ac, 100.00% Impervious, Inflow Depth > 5.94" for 25-yr event
 Inflow = 2.83 cfs @ 12.07 hrs, Volume= 0.213 af
 Outflow = 2.61 cfs @ 12.11 hrs, Volume= 0.170 af, Atten= 8%, Lag= 2.2 min
 Discarded = 0.02 cfs @ 12.11 hrs, Volume= 0.018 af
 Primary = 2.59 cfs @ 12.11 hrs, Volume= 0.152 af
 Routed to Pond INFIL BASIN B4 : INFIL BASIN B4

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 151.96' @ 12.11 hrs Surf.Area= 1,033 sf Storage= 2,377 cf

Plug-Flow detention time= 102.8 min calculated for 0.170 af (80% of inflow)
 Center-of-Mass det. time= 48.7 min (781.7 - 733.0)

Volume	Invert	Avail.Storage	Storage Description
#1A	148.50'	1,228 cf	18.50'W x 55.83'L x 4.50'H Field A 4,648 cf Overall - 1,578 cf Embedded = 3,070 cf x 40.0% Voids
#2A	149.00'	1,578 cf	Cultec R-360HD x 42 Inside #1 Effective Size= 54.9"W x 36.0"H => 9.99 sf x 3.67'L = 36.6 cf Overall Size= 60.0"W x 36.0"H x 4.17'L with 0.50' Overlap 42 Chambers in 3 Rows Cap Storage= 6.5 cf x 2 x 3 rows = 38.8 cf
		2,806 cf	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	151.00'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	148.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 138.00'

Discarded OutFlow Max=0.02 cfs @ 12.11 hrs HW=151.95' (Free Discharge)
 ↑**2=Exfiltration** (Controls 0.02 cfs)

Primary OutFlow Max=2.56 cfs @ 12.11 hrs HW=151.95' (Free Discharge)
 ↑**1=Orifice/Grate** (Orifice Controls 2.56 cfs @ 3.32 fps)

Pond U.G. INFIL ROOF 4: U.G. INFIL ROOF 4




Summary for Link PR DP1: PR DP1

Inflow Area = 106.945 ac, 22.75% Impervious, Inflow Depth > 2.92" for 25-yr event
Inflow = 130.53 cfs @ 13.07 hrs, Volume= 26.048 af
Primary = 130.53 cfs @ 13.07 hrs, Volume= 26.048 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link PR DP1: PR DP1

Hydrograph



Summary for Subcatchment NO ROOF 1: NO ROOF 1

Runoff = 3.20 cfs @ 12.07 hrs, Volume= 0.241 af, Depth> 6.73"

Routed to Pond U.G. INFIL ROOF 1 : U.G. INFIL ROOF 1


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 50-yr Rainfall=7.54"

Area (ac)	CN	Description
0.430	98	Paved parking, HSG B
0.430		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, ROOF 1

Subcatchment NO ROOF 1: NO ROOF 1

Hydrograph



Summary for Subcatchment NO ROOF 2: NO ROOF 2

Runoff = 3.20 cfs @ 12.07 hrs, Volume= 0.241 af, Depth> 6.73"

Routed to Pond U.G. INFIL ROOF 2 : U.G. INFIL ROOF 2


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 50-yr Rainfall=7.54"

Area (ac)	CN	Description
0.430	98	Paved parking, HSG B
0.430		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, ROOF 1

Subcatchment NO ROOF 2: NO ROOF 2

Hydrograph



Summary for Subcatchment NO ROOF 3: NO ROOF 3

Runoff = 3.20 cfs @ 12.07 hrs, Volume= 0.241 af, Depth> 6.73"

Routed to Pond U.G. INFIL ROOF 3 : U.G. INFIL ROOF 3


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 50-yr Rainfall=7.54"

Area (ac)	CN	Description
0.430	98	Paved parking, HSG B
0.430		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, ROOF 1

Subcatchment NO ROOF 3: NO ROOF 3

Hydrograph



Summary for Subcatchment NO ROOF 4: NO ROOF 4


Runoff = 3.20 cfs @ 12.07 hrs, Volume= 0.241 af, Depth> 6.73"
 Routed to Pond U.G. INFIL ROOF 4 : U.G. INFIL ROOF 4

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 50-yr Rainfall=7.54"

Area (ac)	CN	Description
0.430	98	Paved parking, HSG B
0.430		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, ROOF 1

Subcatchment NO ROOF 4: NO ROOF 4



Summary for Subcatchment PR-DA 1A: PR-DA 1A

Runoff = 148.67 cfs @ 12.87 hrs, Volume= 25.430 af, Depth> 3.71"

Routed to Pond EXISTING POND : EXISTING POND


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 50-yr Rainfall=7.54"

Area (ac)	CN	Description
40.280	68	1 acre lots, 20% imp, HSG B
27.540	79	1 acre lots, 20% imp, HSG C
0.180	98	Paved parking, HSG B
11.690	55	Woods, Good, HSG B
0.120	61	>75% Grass cover, Good, HSG B
0.620	98	Paved parking, HSG C
1.450	70	Woods, Good, HSG C
0.270	74	>75% Grass cover, Good, HSG C
82.150	70	Weighted Average
67.786		82.51% Pervious Area
14.364		17.49% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
49.3	200	0.0100	0.07		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
0.8	130	0.0200	2.87		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
5.4	200	0.0150	0.61		Shallow Concentrated Flow, Shallow Concentrated Forest Woodland Kv= 5.0 fps
3.4	630	0.0230	3.08		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
4.6	2,300	0.0510	8.39	83.90	Channel Flow, Channel Flow Wooded Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.040 Winding stream, pools & shoals
63.5	3,460	Total			

Subcatchment PR-DA 1A: PR-DA 1A

Hydrograph



Summary for Subcatchment PR-DA 1B1: PR-DA 1B1

Runoff = 14.28 cfs @ 12.16 hrs, Volume= 1.185 af, Depth> 5.22"
 Routed to Pond INFIL 1B1 : INFILTRATOR 1B1


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 50-yr Rainfall=7.54"

Area (ac)	CN	Description
1.758	98	Paved parking, HSG B
0.697	55	Woods, Good, HSG B
0.270	61	>75% Grass cover, Good, HSG B
2.725	83	Weighted Average
0.967		35.49% Pervious Area
1.758		64.51% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.2	150	0.2300	0.22		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
0.5	80	0.0200	2.87		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
11.7	230	Total			

Subcatchment PR-DA 1B1: PR-DA 1B1

Hydrograph



Summary for Subcatchment PR-DA 1B2: PR-DA 1B2

Runoff = 13.80 cfs @ 12.15 hrs, Volume= 1.138 af, Depth> 5.67"
 Routed to Pond INFIL 1B2 : INFILTRATOR 1B2


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 50-yr Rainfall=7.54"

Area (ac)	CN	Description
1.760	98	Paved parking, HSG B
0.310	55	Woods, Good, HSG B
0.340	61	>75% Grass cover, Good, HSG B
2.410	87	Weighted Average
0.650		26.97% Pervious Area
1.760		73.03% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.0	70	0.0850	0.13		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
1.7	300	0.0200	2.87		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
10.7	370	Total			

Subcatchment PR-DA 1B2: PR-DA 1B2

Hydrograph



Summary for Subcatchment PR-DA 1B3: PR-DA 1B3


Runoff = 18.66 cfs @ 12.22 hrs, Volume= 1.662 af, Depth> 3.67"
 Routed to Pond INFIL BASIN B3 : INFIL BASIN B3

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 50-yr Rainfall=7.54"

Area (ac)	CN	Description
1.340	98	Paved parking, HSG B
1.200	55	Woods, Good, HSG B
2.890	61	>75% Grass cover, Good, HSG B
5.430	69	Weighted Average
4.090		75.32% Pervious Area
1.340		24.68% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
13.6	150	0.0200	0.18		Sheet Flow, Sheet Flow Grass Grass: Short n= 0.150 P2= 3.20"
0.7	90	0.0200	2.28		Shallow Concentrated Flow, Shallow Concentrated Grass Unpaved Kv= 16.1 fps
1.4	1,170	0.0600	13.49	42.37	Pipe Channel, RCP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.017 Concrete sewer w/manholes & inlets
15.7	1,410	Total			

Subcatchment PR-DA 1B3: PR-DA 1B3



Summary for Subcatchment PR-DA 1BND: PR-DA 1BND


Runoff = 2.91 cfs @ 12.07 hrs, Volume= 0.203 af, Depth> 5.67"
 Routed to Pond EXISTING POND : EXISTING POND

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 50-yr Rainfall=7.54"

Area (ac)	CN	Description
0.300	98	Paved parking, HSG B
0.130	61	>75% Grass cover, Good, HSG B
0.430	87	Weighted Average
0.130		30.23% Pervious Area
0.300		69.77% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Not Detained-Direct Entry

Subcatchment PR-DA 1BND: PR-DA 1BND



Summary for Subcatchment PR-DA 1C: PR-DA 1C

Runoff = 14.05 cfs @ 12.14 hrs, Volume= 1.068 af, Depth> 3.26"

Routed to Pond EXISTING POND : EXISTING POND


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 50-yr Rainfall=7.54"

Area (ac)	CN	Description
* 0.900	98	Water Surface
2.680	55	Woods, Good, HSG B
0.350	61	>75% Grass cover, Good, HSG B
3.930	65	Weighted Average
3.030		77.10% Pervious Area
0.900		22.90% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
8.1	90	0.1833	0.18		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
1.3	140	0.1290	1.80		Shallow Concentrated Flow, Shallow Concentrated Woods Woodland Kv= 5.0 fps
0.3	210	0.0660	12.73	127.25	Channel Flow, Stream Channel Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.030 Stream, clean & straight
9.7	440	Total			

Subcatchment PR-DA 1C: PR-DA 1C

Hydrograph



Summary for Subcatchment PR-DA-1B4: PR-DA 1B4

Runoff = 23.49 cfs @ 12.38 hrs, Volume= 2.630 af, Depth> 3.87"
 Routed to Pond INFIL BASIN B4 : INFIL BASIN B4


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 50-yr Rainfall=7.54"

Area (ac)	CN	Description
2.640	68	1 acre lots, 20% imp, HSG B
0.350	79	1 acre lots, 20% imp, HSG C
1.590	98	Paved parking, HSG B
1.010	55	Woods, Good, HSG B
2.560	61	>75% Grass cover, Good, HSG B
8.150	71	Weighted Average
5.962		73.15% Pervious Area
2.188		26.85% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
22.5	150	0.0400	0.11		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
3.8	950	0.0660	4.14		Shallow Concentrated Flow, Shallow Concentrated Woods Unpaved Kv= 16.1 fps
1.1	910	0.0660	14.15	44.44	Pipe Channel, RCP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.017 Concrete sewer w/manholes & inlets
27.4	2,010	Total			

Subcatchment PR-DA-1B4: PR-DA 1B4

Hydrograph



Summary for Pond EXISTING POND: EXISTING POND

Inflow Area = 106.945 ac, 22.75% Impervious, Inflow Depth > 3.70" for 50-yr event
 Inflow = 181.45 cfs @ 12.76 hrs, Volume= 32.955 af
 Outflow = 171.39 cfs @ 12.96 hrs, Volume= 32.017 af, Atten= 6%, Lag= 11.8 min
 Primary = 171.39 cfs @ 12.96 hrs, Volume= 32.017 af
 Routed to Link PR DP1 : PR DP1

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 77.26' @ 12.96 hrs Surf.Area= 1.590 ac Storage= 6.317 af

Plug-Flow detention time= 44.0 min calculated for 32.017 af (97% of inflow)
 Center-of-Mass det. time= 34.2 min (865.4 - 831.1)

Volume	Invert	Avail.Storage	Storage Description		
#1	71.80'	7.556 af	Existing Pond (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (acres)	Perim. (feet)	Inc.Store (acre-feet)	Cum.Store (acre-feet)	Wet.Area (acres)
71.80	0.938	1,000.1	0.000	0.000	0.938
74.00	1.020	1,016.0	2.153	2.153	1.016
76.00	1.320	1,692.0	2.334	4.487	4.360
78.00	1.760	1,652.0	3.069	7.556	4.617


Device	Routing	Invert	Outlet Devices
#1	Primary	71.80'	24.0" Round Culvert X 2.00 L= 100.0' Ke= 0.500 Inlet / Outlet Invert= 71.80' / 70.00' S= 0.0180 ' S= 0.0180 ' Cc= 0.900 n= 0.011 Concrete pipe, straight & clean, Flow Area= 3.14 sf
#2	Primary	75.75'	12.0' long + 3.0 ' SideZ x 12.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.57 2.62 2.70 2.67 2.66 2.67 2.66 2.64
#3	Primary	76.75'	30.0' long + 3.0 ' SideZ x 30.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63

Primary OutFlow Max=171.20 cfs @ 12.96 hrs HW=77.26' (Free Discharge)

- 1=Culvert (Inlet Controls 63.88 cfs @ 10.17 fps)
- 2=Broad-Crested Rectangular Weir (Weir Controls 76.71 cfs @ 3.08 fps)
- 3=Broad-Crested Rectangular Weir (Weir Controls 30.61 cfs @ 1.91 fps)

Pond EXISTING POND: EXISTING POND

Hydrograph



Summary for Pond INFIL 1B1: INFILTRATOR 1B1

Inflow Area = 2.725 ac, 64.51% Impervious, Inflow Depth > 5.22" for 50-yr event
 Inflow = 14.28 cfs @ 12.16 hrs, Volume= 1.185 af
 Outflow = 9.04 cfs @ 12.32 hrs, Volume= 0.979 af, Atten= 37%, Lag= 9.8 min
 Discarded = 0.10 cfs @ 12.32 hrs, Volume= 0.085 af
 Primary = 8.94 cfs @ 12.32 hrs, Volume= 0.894 af
 Routed to Pond INFIL 1B2 : INFILTRATOR 1B2

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 132.66' @ 12.32 hrs Surf.Area= 0.114 ac Storage= 0.391 af

Plug-Flow detention time= 88.8 min calculated for 0.976 af (82% of inflow)
 Center-of-Mass det. time= 41.4 min (812.7 - 771.3)

Volume	Invert	Avail.Storage	Storage Description
#1A	127.50'	0.170 af	23.00'W x 215.70'L x 6.00'H Field A 0.683 af Overall - 0.259 af Embedded = 0.424 af x 40.0% Voids
#2A	128.00'	0.259 af	Cultec R-902HD x 174 Inside #1 Effective Size= 69.8"W x 48.0"H => 17.65 sf x 3.67'L = 64.7 cf Overall Size= 78.0"W x 48.0"H x 4.10'L with 0.44' Overlap 174 Chambers in 3 Rows Cap Storage= 2.8 cf x 2 x 3 rows = 16.6 cf
		0.429 af	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	129.75'	15.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	127.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 120.00'

Discarded OutFlow Max=0.10 cfs @ 12.32 hrs HW=132.64' (Free Discharge)
 ↑**2=Exfiltration** (Controls 0.10 cfs)

Primary OutFlow Max=8.90 cfs @ 12.32 hrs HW=132.64' (Free Discharge)
 ↑**1=Orifice/Grate** (Orifice Controls 8.90 cfs @ 7.25 fps)

Pond INFIL 1B1: INFILTRATOR 1B1



Summary for Pond INFIL 1B2: INFILTRATOR 1B2

Inflow Area = 5.135 ac, 68.51% Impervious, Inflow Depth > 4.75" for 50-yr event
 Inflow = 20.56 cfs @ 12.17 hrs, Volume= 2.033 af
 Outflow = 13.76 cfs @ 12.45 hrs, Volume= 1.833 af, Atten= 33%, Lag= 16.8 min
 Discarded = 0.24 cfs @ 12.45 hrs, Volume= 0.157 af
 Primary = 13.51 cfs @ 12.45 hrs, Volume= 1.676 af
 Routed to Pond EXISTING POND : EXISTING POND

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 127.27' @ 12.45 hrs Surf.Area= 0.160 ac Storage= 0.527 af

Plug-Flow detention time= 63.5 min calculated for 1.833 af (90% of inflow)
 Center-of-Mass det. time= 32.4 min (816.5 - 784.1)

Volume	Invert	Avail.Storage	Storage Description
#1A	122.50'	0.236 af	30.25'W x 230.37'L x 6.00'H Field A 0.960 af Overall - 0.369 af Embedded = 0.591 af x 40.0% Voids
#2A	123.00'	0.369 af	Cultec R-902HD x 248 Inside #1 Effective Size= 69.8"W x 48.0"H => 17.65 sf x 3.67'L = 64.7 cf Overall Size= 78.0"W x 48.0"H x 4.10'L with 0.44' Overlap 248 Chambers in 4 Rows Cap Storage= 2.8 cf x 2 x 4 rows = 22.1 cf
		0.605 af	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	124.00'	18.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	122.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 120.00'

Discarded OutFlow Max=0.24 cfs @ 12.45 hrs HW=127.27' (Free Discharge)
 ↳ **2=Exfiltration** (Controls 0.24 cfs)

Primary OutFlow Max=13.51 cfs @ 12.45 hrs HW=127.27' (Free Discharge)
 ↳ **1=Orifice/Grate** (Orifice Controls 13.51 cfs @ 7.64 fps)

Pond INFIL 1B2: INFILTRATOR 1B2



Summary for Pond INFIL BASIN B3: INFIL BASIN B3

Inflow Area = 6.290 ac, 34.98% Impervious, Inflow Depth > 3.86" for 50-yr event
 Inflow = 22.68 cfs @ 12.19 hrs, Volume= 2.023 af
 Outflow = 17.57 cfs @ 12.34 hrs, Volume= 1.871 af, Atten= 23%, Lag= 8.9 min
 Discarded = 0.09 cfs @ 12.34 hrs, Volume= 0.055 af
 Primary = 17.48 cfs @ 12.34 hrs, Volume= 1.816 af
 Routed to Pond EXISTING POND : EXISTING POND

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 103.34' @ 12.34 hrs Surf.Area= 6,167 sf Storage= 17,432 cf

Plug-Flow detention time= 45.8 min calculated for 1.871 af (93% of inflow)
 Center-of-Mass det. time= 20.7 min (818.0 - 797.2)

Volume	Invert	Avail.Storage	Storage Description		
#1	99.50'	25,262 cf	Existing Pond (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
99.50	3,074	220.0	0	0	3,074
100.00	3,428	230.0	1,625	1,625	3,449
102.00	4,993	267.0	8,372	9,997	4,995
104.00	6,798	305.0	11,745	21,741	6,817
104.50	7,285	315.0	3,520	25,262	7,334


Device	Routing	Invert	Outlet Devices
#1	Primary	101.00'	24.0" Round Culvert L= 50.0' Ke= 0.500 Inlet / Outlet Invert= 101.00' / 100.00' S= 0.0200 ' S= 0.0200 ' Cc= 0.900 n= 0.011 Concrete pipe, straight & clean, Flow Area= 3.14 sf
#2	Primary	103.50'	12.0' long + 3.0 ' SideZ x 6.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.37 2.51 2.70 2.68 2.68 2.67 2.65 2.65 2.65 2.65 2.66 2.66 2.67 2.69 2.72 2.76 2.83
#3	Discarded	99.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 89.00'

Discarded OutFlow Max=0.09 cfs @ 12.34 hrs HW=103.33' (Free Discharge)
 ↳ **3=Exfiltration** (Controls 0.09 cfs)

Primary OutFlow Max=17.45 cfs @ 12.34 hrs HW=103.33' (Free Discharge)
 ↳ **1=Culvert** (Inlet Controls 17.45 cfs @ 5.56 fps)
 ↳ **2=Broad-Crested Rectangular Weir** (Controls 0.00 cfs)

Pond INFIL BASIN B3: INFIL BASIN B3

Hydrograph



Summary for Pond INFIL BASIN B4: INFIL BASIN B4

Inflow Area = 9.010 ac, 33.83% Impervious, Inflow Depth > 3.98" for 50-yr event
 Inflow = 25.69 cfs @ 12.37 hrs, Volume= 2.990 af
 Outflow = 25.50 cfs @ 12.40 hrs, Volume= 2.817 af, Atten= 1%, Lag= 2.0 min
 Discarded = 0.07 cfs @ 12.40 hrs, Volume= 0.056 af
 Primary = 25.43 cfs @ 12.40 hrs, Volume= 2.761 af
 Routed to Pond EXISTING POND : EXISTING POND

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 94.85' @ 12.40 hrs Surf.Area= 5,099 sf Storage= 11,220 cf

Plug-Flow detention time= 32.3 min calculated for 2.817 af (94% of inflow)
 Center-of-Mass det. time= 12.4 min (816.0 - 803.5)

Volume	Invert	Avail.Storage	Storage Description			
#1	92.00'	17,673 cf	Infil Basin B4 (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)	
92.00	2,832	377.0	0	0	2,832	
94.00	4,424	403.0	7,197	7,197	4,624	
96.00	6,097	428.0	10,476	17,673	6,475	


Device	Routing	Invert	Outlet Devices									
#1	Primary	94.00'	24.0" x 36.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads									
#2	Primary	95.50'	12.0' long + 3.0 ' SideZ x 6.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.37 2.51 2.70 2.68 2.68 2.67 2.65 2.65 2.65									
#3	Discarded	92.00'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 82.00'									

Discarded OutFlow Max=0.07 cfs @ 12.40 hrs HW=94.85' (Free Discharge)
 ↳ **3=Exfiltration** (Controls 0.07 cfs)

Primary OutFlow Max=25.43 cfs @ 12.40 hrs HW=94.85' (Free Discharge)
 ↳ **1=Orifice/Grate** (Weir Controls 25.43 cfs @ 3.01 fps)
 ↳ **2=Broad-Crested Rectangular Weir** (Controls 0.00 cfs)

Pond INFIL BASIN B4: INFIL BASIN B4

Hydrograph



Summary for Pond U.G. INFIL ROOF 1: U.G. INFIL ROOF 1

Inflow Area = 0.430 ac, 100.00% Impervious, Inflow Depth > 6.73" for 50-yr event
 Inflow = 3.20 cfs @ 12.07 hrs, Volume= 0.241 af
 Outflow = 2.91 cfs @ 12.11 hrs, Volume= 0.199 af, Atten= 9%, Lag= 2.3 min
 Discarded = 0.02 cfs @ 12.11 hrs, Volume= 0.018 af
 Primary = 2.90 cfs @ 12.11 hrs, Volume= 0.180 af
 Routed to Pond INFIL BASIN B3 : INFIL BASIN B3

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 152.09' @ 12.11 hrs Surf.Area= 1,033 sf Storage= 2,429 cf

Plug-Flow detention time= 97.6 min calculated for 0.198 af (82% of inflow)
 Center-of-Mass det. time= 46.5 min (779.0 - 732.5)

Volume	Invert	Avail.Storage	Storage Description
#1A	148.50'	1,228 cf	18.50'W x 55.83'L x 4.50'H Field A 4,648 cf Overall - 1,578 cf Embedded = 3,070 cf x 40.0% Voids
#2A	149.00'	1,578 cf	Cultec R-360HD x 42 Inside #1 Effective Size= 54.9"W x 36.0"H => 9.99 sf x 3.67'L = 36.6 cf Overall Size= 60.0"W x 36.0"H x 4.17'L with 0.50' Overlap 42 Chambers in 3 Rows Cap Storage= 6.5 cf x 2 x 3 rows = 38.8 cf
		2,806 cf	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	151.00'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	148.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 138.00'

Discarded OutFlow Max=0.02 cfs @ 12.11 hrs HW=152.07' (Free Discharge)
 ↑**2=Exfiltration** (Controls 0.02 cfs)

Primary OutFlow Max=2.86 cfs @ 12.11 hrs HW=152.07' (Free Discharge)
 ↑**1=Orifice/Grate** (Orifice Controls 2.86 cfs @ 3.64 fps)

Pond U.G. INFIL ROOF 1: U.G. INFIL ROOF 1



Summary for Pond U.G. INFIL ROOF 2: U.G. INFIL ROOF 2

Inflow Area = 0.430 ac, 100.00% Impervious, Inflow Depth > 6.73" for 50-yr event
 Inflow = 3.20 cfs @ 12.07 hrs, Volume= 0.241 af
 Outflow = 2.91 cfs @ 12.11 hrs, Volume= 0.199 af, Atten= 9%, Lag= 2.3 min
 Discarded = 0.02 cfs @ 12.11 hrs, Volume= 0.018 af
 Primary = 2.90 cfs @ 12.11 hrs, Volume= 0.180 af
 Routed to Pond INFIL BASIN B3 : INFIL BASIN B3

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 152.09' @ 12.11 hrs Surf.Area= 1,033 sf Storage= 2,429 cf

Plug-Flow detention time= 97.6 min calculated for 0.198 af (82% of inflow)
 Center-of-Mass det. time= 46.5 min (779.0 - 732.5)

Volume	Invert	Avail.Storage	Storage Description
#1A	148.50'	1,228 cf	18.50'W x 55.83'L x 4.50'H Field A 4,648 cf Overall - 1,578 cf Embedded = 3,070 cf x 40.0% Voids
#2A	149.00'	1,578 cf	Cultec R-360HD x 42 Inside #1 Effective Size= 54.9"W x 36.0"H => 9.99 sf x 3.67'L = 36.6 cf Overall Size= 60.0"W x 36.0"H x 4.17'L with 0.50' Overlap 42 Chambers in 3 Rows Cap Storage= 6.5 cf x 2 x 3 rows = 38.8 cf
		2,806 cf	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	151.00'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	148.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 138.00'

Discarded OutFlow Max=0.02 cfs @ 12.11 hrs HW=152.07' (Free Discharge)
 ↑**2=Exfiltration** (Controls 0.02 cfs)

Primary OutFlow Max=2.86 cfs @ 12.11 hrs HW=152.07' (Free Discharge)
 ↑**1=Orifice/Grate** (Orifice Controls 2.86 cfs @ 3.64 fps)

Pond U.G. INFIL ROOF 2: U.G. INFIL ROOF 2



Summary for Pond U.G. INFIL ROOF 3: U.G. INFIL ROOF 3

Inflow Area = 0.430 ac, 100.00% Impervious, Inflow Depth > 6.73" for 50-yr event
 Inflow = 3.20 cfs @ 12.07 hrs, Volume= 0.241 af
 Outflow = 2.91 cfs @ 12.11 hrs, Volume= 0.199 af, Atten= 9%, Lag= 2.3 min
 Discarded = 0.02 cfs @ 12.11 hrs, Volume= 0.018 af
 Primary = 2.90 cfs @ 12.11 hrs, Volume= 0.180 af
 Routed to Pond INFIL BASIN B4 : INFIL BASIN B4

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 152.09' @ 12.11 hrs Surf.Area= 1,033 sf Storage= 2,429 cf

Plug-Flow detention time= 97.6 min calculated for 0.198 af (82% of inflow)
 Center-of-Mass det. time= 46.5 min (779.0 - 732.5)

Volume	Invert	Avail.Storage	Storage Description
#1A	148.50'	1,228 cf	18.50'W x 55.83'L x 4.50'H Field A 4,648 cf Overall - 1,578 cf Embedded = 3,070 cf x 40.0% Voids
#2A	149.00'	1,578 cf	Cultec R-360HD x 42 Inside #1 Effective Size= 54.9"W x 36.0"H => 9.99 sf x 3.67'L = 36.6 cf Overall Size= 60.0"W x 36.0"H x 4.17'L with 0.50' Overlap 42 Chambers in 3 Rows Cap Storage= 6.5 cf x 2 x 3 rows = 38.8 cf
		2,806 cf	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	151.00'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	148.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 138.00'

Discarded OutFlow Max=0.02 cfs @ 12.11 hrs HW=152.07' (Free Discharge)
 ↳ **2=Exfiltration** (Controls 0.02 cfs)

Primary OutFlow Max=2.86 cfs @ 12.11 hrs HW=152.07' (Free Discharge)
 ↳ **1=Orifice/Grate** (Orifice Controls 2.86 cfs @ 3.64 fps)

Pond U.G. INFIL ROOF 3: U.G. INFIL ROOF 3



Summary for Pond U.G. INFIL ROOF 4: U.G. INFIL ROOF 4

Inflow Area = 0.430 ac, 100.00% Impervious, Inflow Depth > 6.73" for 50-yr event
 Inflow = 3.20 cfs @ 12.07 hrs, Volume= 0.241 af
 Outflow = 2.91 cfs @ 12.11 hrs, Volume= 0.199 af, Atten= 9%, Lag= 2.3 min
 Discarded = 0.02 cfs @ 12.11 hrs, Volume= 0.018 af
 Primary = 2.90 cfs @ 12.11 hrs, Volume= 0.180 af
 Routed to Pond INFIL BASIN B4 : INFIL BASIN B4

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 152.09' @ 12.11 hrs Surf.Area= 1,033 sf Storage= 2,429 cf

Plug-Flow detention time= 97.6 min calculated for 0.198 af (82% of inflow)
 Center-of-Mass det. time= 46.5 min (779.0 - 732.5)

Volume	Invert	Avail.Storage	Storage Description
#1A	148.50'	1,228 cf	18.50'W x 55.83'L x 4.50'H Field A 4,648 cf Overall - 1,578 cf Embedded = 3,070 cf x 40.0% Voids
#2A	149.00'	1,578 cf	Cultec R-360HD x 42 Inside #1 Effective Size= 54.9"W x 36.0"H => 9.99 sf x 3.67'L = 36.6 cf Overall Size= 60.0"W x 36.0"H x 4.17'L with 0.50' Overlap 42 Chambers in 3 Rows Cap Storage= 6.5 cf x 2 x 3 rows = 38.8 cf
		2,806 cf	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	151.00'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	148.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 138.00'

Discarded OutFlow Max=0.02 cfs @ 12.11 hrs HW=152.07' (Free Discharge)
 ↑**2=Exfiltration** (Controls 0.02 cfs)

Primary OutFlow Max=2.86 cfs @ 12.11 hrs HW=152.07' (Free Discharge)
 ↑**1=Orifice/Grate** (Orifice Controls 2.86 cfs @ 3.64 fps)

Pond U.G. INFIL ROOF 4: U.G. INFIL ROOF 4




Summary for Link PR DP1: PR DP1

Inflow Area = 106.945 ac, 22.75% Impervious, Inflow Depth > 3.59" for 50-yr event
Inflow = 171.39 cfs @ 12.96 hrs, Volume= 32.017 af
Primary = 171.39 cfs @ 12.96 hrs, Volume= 32.017 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link PR DP1: PR DP1



Summary for Subcatchment NO ROOF 1: NO ROOF 1

Runoff = 3.60 cfs @ 12.07 hrs, Volume= 0.271 af, Depth> 7.56"


Routed to Pond U.G. INFIL ROOF 1 : U.G. INFIL ROOF 1

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 100-yr Rainfall=8.46"

Area (ac)	CN	Description
0.430	98	Paved parking, HSG B
0.430		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, ROOF 1

Subcatchment NO ROOF 1: NO ROOF 1



Summary for Subcatchment NO ROOF 2: NO ROOF 2

Runoff = 3.60 cfs @ 12.07 hrs, Volume= 0.271 af, Depth> 7.56"


Routed to Pond U.G. INFIL ROOF 2 : U.G. INFIL ROOF 2

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 100-yr Rainfall=8.46"

Area (ac)	CN	Description
0.430	98	Paved parking, HSG B
0.430		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, ROOF 1

Subcatchment NO ROOF 2: NO ROOF 2



Summary for Subcatchment NO ROOF 3: NO ROOF 3

Runoff = 3.60 cfs @ 12.07 hrs, Volume= 0.271 af, Depth> 7.56"


Routed to Pond U.G. INFIL ROOF 3 : U.G. INFIL ROOF 3

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 100-yr Rainfall=8.46"

Area (ac)	CN	Description
0.430	98	Paved parking, HSG B
0.430		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, ROOF 1

Subcatchment NO ROOF 3: NO ROOF 3



Summary for Subcatchment NO ROOF 4: NO ROOF 4

Runoff = 3.60 cfs @ 12.07 hrs, Volume= 0.271 af, Depth> 7.56"


Routed to Pond U.G. INFIL ROOF 4 : U.G. INFIL ROOF 4

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 100-yr Rainfall=8.46"

Area (ac)	CN	Description
0.430	98	Paved parking, HSG B
0.430		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, ROOF 1

Subcatchment NO ROOF 4: NO ROOF 4



Summary for Subcatchment PR-DA 1A: PR-DA 1A

Runoff = 177.76 cfs @ 12.87 hrs, Volume= 30.466 af, Depth> 4.45"

Routed to Pond EXISTING POND : EXISTING POND


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 100-yr Rainfall=8.46"

Area (ac)	CN	Description
40.280	68	1 acre lots, 20% imp, HSG B
27.540	79	1 acre lots, 20% imp, HSG C
0.180	98	Paved parking, HSG B
11.690	55	Woods, Good, HSG B
0.120	61	>75% Grass cover, Good, HSG B
0.620	98	Paved parking, HSG C
1.450	70	Woods, Good, HSG C
0.270	74	>75% Grass cover, Good, HSG C
82.150	70	Weighted Average
67.786		82.51% Pervious Area
14.364		17.49% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
49.3	200	0.0100	0.07		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
0.8	130	0.0200	2.87		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
5.4	200	0.0150	0.61		Shallow Concentrated Flow, Shallow Concentrated Forest Woodland Kv= 5.0 fps
3.4	630	0.0230	3.08		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
4.6	2,300	0.0510	8.39	83.90	Channel Flow, Channel Flow Wooded Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.040 Winding stream, pools & shoals
63.5	3,460	Total			

Subcatchment PR-DA 1A: PR-DA 1A

Hydrograph



Summary for Subcatchment PR-DA 1B1: PR-DA 1B1

Runoff = 16.44 cfs @ 12.16 hrs, Volume= 1.374 af, Depth> 6.05"
 Routed to Pond INFIL 1B1 : INFILTRATOR 1B1


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 100-yr Rainfall=8.46"

Area (ac)	CN	Description
1.758	98	Paved parking, HSG B
0.697	55	Woods, Good, HSG B
0.270	61	>75% Grass cover, Good, HSG B
2.725	83	Weighted Average
0.967		35.49% Pervious Area
1.758		64.51% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.2	150	0.2300	0.22		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
0.5	80	0.0200	2.87		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
11.7	230	Total			

Subcatchment PR-DA 1B1: PR-DA 1B1

Hydrograph



Summary for Subcatchment PR-DA 1B2: PR-DA 1B2

Runoff = 15.74 cfs @ 12.15 hrs, Volume= 1.308 af, Depth> 6.51"
 Routed to Pond INFIL 1B2 : INFILTRATOR 1B2


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 100-yr Rainfall=8.46"

Area (ac)	CN	Description
1.760	98	Paved parking, HSG B
0.310	55	Woods, Good, HSG B
0.340	61	>75% Grass cover, Good, HSG B
2.410	87	Weighted Average
0.650		26.97% Pervious Area
1.760		73.03% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.0	70	0.0850	0.13		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
1.7	300	0.0200	2.87		Shallow Concentrated Flow, Shallow Concentrated Paved Paved Kv= 20.3 fps
10.7	370	Total			

Subcatchment PR-DA 1B2: PR-DA 1B2

Hydrograph



Summary for Subcatchment PR-DA 1B3: PR-DA 1B3


Runoff = 22.37 cfs @ 12.22 hrs, Volume= 1.996 af, Depth> 4.41"
 Routed to Pond INFIL BASIN B3 : INFIL BASIN B3

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 100-yr Rainfall=8.46"

Area (ac)	CN	Description
1.340	98	Paved parking, HSG B
1.200	55	Woods, Good, HSG B
2.890	61	>75% Grass cover, Good, HSG B
5.430	69	Weighted Average
4.090		75.32% Pervious Area
1.340		24.68% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
13.6	150	0.0200	0.18		Sheet Flow, Sheet Flow Grass Grass: Short n= 0.150 P2= 3.20"
0.7	90	0.0200	2.28		Shallow Concentrated Flow, Shallow Concentrated Grass Unpaved Kv= 16.1 fps
1.4	1,170	0.0600	13.49	42.37	Pipe Channel, RCP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.017 Concrete sewer w/manholes & inlets
15.7	1,410	Total			

Subcatchment PR-DA 1B3: PR-DA 1B3



Summary for Subcatchment PR-DA 1BND: PR-DA 1BND

Runoff = 3.32 cfs @ 12.07 hrs, Volume= 0.234 af, Depth> 6.52"

Routed to Pond EXISTING POND : EXISTING POND


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
Type III 24-hr 100-yr Rainfall=8.46"

Area (ac)	CN	Description
0.300	98	Paved parking, HSG B
0.130	61	>75% Grass cover, Good, HSG B
0.430	87	Weighted Average
0.130		30.23% Pervious Area
0.300		69.77% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Not Detained-Direct Entry

Subcatchment PR-DA 1BND: PR-DA 1BND

Hydrograph



Summary for Subcatchment PR-DA 1C: PR-DA 1C


Runoff = 17.08 cfs @ 12.14 hrs, Volume= 1.297 af, Depth> 3.96"
 Routed to Pond EXISTING POND : EXISTING POND

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 100-yr Rainfall=8.46"

Area (ac)	CN	Description
* 0.900	98	Water Surface
2.680	55	Woods, Good, HSG B
0.350	61	>75% Grass cover, Good, HSG B
3.930	65	Weighted Average
3.030		77.10% Pervious Area
0.900		22.90% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
8.1	90	0.1833	0.18		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
1.3	140	0.1290	1.80		Shallow Concentrated Flow, Shallow Concentrated Woods Woodland Kv= 5.0 fps
0.3	210	0.0660	12.73	127.25	Channel Flow, Stream Channel Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.030 Stream, clean & straight
9.7	440	Total			

Subcatchment PR-DA 1C: PR-DA 1C



Summary for Subcatchment PR-DA-1B4: PR-DA 1B4

Runoff = 27.97 cfs @ 12.38 hrs, Volume= 3.140 af, Depth> 4.62"
 Routed to Pond INFIL BASIN B4 : INFIL BASIN B4


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 100-yr Rainfall=8.46"

Area (ac)	CN	Description
2.640	68	1 acre lots, 20% imp, HSG B
0.350	79	1 acre lots, 20% imp, HSG C
1.590	98	Paved parking, HSG B
1.010	55	Woods, Good, HSG B
2.560	61	>75% Grass cover, Good, HSG B
8.150	71	Weighted Average
5.962		73.15% Pervious Area
2.188		26.85% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
22.5	150	0.0400	0.11		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
3.8	950	0.0660	4.14		Shallow Concentrated Flow, Shallow Concentrated Woods Unpaved Kv= 16.1 fps
1.1	910	0.0660	14.15	44.44	Pipe Channel, RCP_Round 24" 24.0" Round Area= 3.1 sf Perim= 6.3' r= 0.50' n= 0.017 Concrete sewer w/manholes & inlets
27.4	2,010	Total			

Subcatchment PR-DA-1B4: PR-DA 1B4

Hydrograph



Summary for Pond EXISTING POND: EXISTING POND

Inflow Area = 106.945 ac, 22.75% Impervious, Inflow Depth > 4.44" for 100-yr event
 Inflow = 217.00 cfs @ 12.75 hrs, Volume= 39.549 af
 Outflow = 210.51 cfs @ 12.89 hrs, Volume= 38.530 af, Atten= 3%, Lag= 8.6 min
 Primary = 210.51 cfs @ 12.89 hrs, Volume= 38.530 af
 Routed to Link PR DP1 : PR DP1

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 77.46' @ 12.89 hrs Surf.Area= 1.634 ac Storage= 6.636 af

Plug-Flow detention time= 40.9 min calculated for 38.530 af (97% of inflow)
 Center-of-Mass det. time= 31.9 min (859.1 - 827.2)

Volume	Invert	Avail.Storage	Storage Description		
#1	71.80'	7.556 af	Existing Pond (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (acres)	Perim. (feet)	Inc.Store (acre-feet)	Cum.Store (acre-feet)	Wet.Area (acres)
71.80	0.938	1,000.1	0.000	0.000	0.938
74.00	1.020	1,016.0	2.153	2.153	1.016
76.00	1.320	1,692.0	2.334	4.487	4.360
78.00	1.760	1,652.0	3.069	7.556	4.617


Device	Routing	Invert	Outlet Devices
#1	Primary	71.80'	24.0" Round Culvert X 2.00 L= 100.0' Ke= 0.500 Inlet / Outlet Invert= 71.80' / 70.00' S= 0.0180 ' S Cc= 0.900 n= 0.011 Concrete pipe, straight & clean, Flow Area= 3.14 sf
#2	Primary	75.75'	12.0' long + 3.0 ' SideZ x 12.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.57 2.62 2.70 2.67 2.66 2.67 2.66 2.64
#3	Primary	76.75'	30.0' long + 3.0 ' SideZ x 30.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.68 2.70 2.70 2.64 2.63 2.64 2.64 2.63

Primary OutFlow Max=210.35 cfs @ 12.89 hrs HW=77.46' (Free Discharge)

- 1=Culvert (Inlet Controls 65.29 cfs @ 10.39 fps)
- 2=Broad-Crested Rectangular Weir (Weir Controls 94.78 cfs @ 3.24 fps)
- 3=Broad-Crested Rectangular Weir (Weir Controls 50.28 cfs @ 2.21 fps)

Pond EXISTING POND: EXISTING POND

Hydrograph



Summary for Pond INFIL 1B1: INFILTRATOR 1B1

Inflow Area = 2.725 ac, 64.51% Impervious, Inflow Depth > 6.05" for 100-yr event
 Inflow = 16.44 cfs @ 12.16 hrs, Volume= 1.374 af
 Outflow = 10.45 cfs @ 12.32 hrs, Volume= 1.167 af, Atten= 36%, Lag= 9.7 min
 Discarded = 0.11 cfs @ 12.32 hrs, Volume= 0.088 af
 Primary = 10.34 cfs @ 12.32 hrs, Volume= 1.079 af
 Routed to Pond INFIL 1B2 : INFILTRATOR 1B2

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 133.44' @ 12.32 hrs Surf.Area= 0.114 ac Storage= 0.426 af

Plug-Flow detention time= 84.2 min calculated for 1.167 af (85% of inflow)
 Center-of-Mass det. time= 40.1 min (807.9 - 767.8)

Volume	Invert	Avail.Storage	Storage Description
#1A	127.50'	0.170 af	23.00'W x 215.70'L x 6.00'H Field A 0.683 af Overall - 0.259 af Embedded = 0.424 af x 40.0% Voids
#2A	128.00'	0.259 af	Cultec R-902HD x 174 Inside #1 Effective Size= 69.8"W x 48.0"H => 17.65 sf x 3.67'L = 64.7 cf Overall Size= 78.0"W x 48.0"H x 4.10'L with 0.44' Overlap 174 Chambers in 3 Rows Cap Storage= 2.8 cf x 2 x 3 rows = 16.6 cf
		0.429 af	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	129.75'	15.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	127.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 120.00'

Discarded OutFlow Max=0.11 cfs @ 12.32 hrs HW=133.42' (Free Discharge)
 ↳ **2=Exfiltration** (Controls 0.11 cfs)

Primary OutFlow Max=10.31 cfs @ 12.32 hrs HW=133.42' (Free Discharge)
 ↳ **1=Orifice/Grate** (Orifice Controls 10.31 cfs @ 8.40 fps)

Pond INFIL 1B1: INFILTRATOR 1B1



Summary for Pond INFIL 1B2: INFILTRATOR 1B2

Inflow Area = 5.135 ac, 68.51% Impervious, Inflow Depth > 5.58" for 100-yr event
 Inflow = 23.93 cfs @ 12.17 hrs, Volume= 2.387 af
 Outflow = 16.16 cfs @ 12.44 hrs, Volume= 2.184 af, Atten= 32%, Lag= 16.2 min
 Discarded = 0.28 cfs @ 12.44 hrs, Volume= 0.164 af
 Primary = 15.89 cfs @ 12.44 hrs, Volume= 2.021 af
 Routed to Pond EXISTING POND : EXISTING POND

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 128.24' @ 12.44 hrs Surf.Area= 0.160 ac Storage= 0.589 af

Plug-Flow detention time= 58.6 min calculated for 2.177 af (91% of inflow)
 Center-of-Mass det. time= 31.3 min (812.6 - 781.3)

Volume	Invert	Avail.Storage	Storage Description
#1A	122.50'	0.236 af	30.25'W x 230.37'L x 6.00'H Field A 0.960 af Overall - 0.369 af Embedded = 0.591 af x 40.0% Voids
#2A	123.00'	0.369 af	Cultec R-902HD x 248 Inside #1 Effective Size= 69.8"W x 48.0"H => 17.65 sf x 3.67'L = 64.7 cf Overall Size= 78.0"W x 48.0"H x 4.10'L with 0.44' Overlap 248 Chambers in 4 Rows Cap Storage= 2.8 cf x 2 x 4 rows = 22.1 cf
		0.605 af	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	124.00'	18.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	122.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 120.00'

Discarded OutFlow Max=0.28 cfs @ 12.44 hrs HW=128.23' (Free Discharge)
 ↳ **2=Exfiltration** (Controls 0.28 cfs)

Primary OutFlow Max=15.87 cfs @ 12.44 hrs HW=128.23' (Free Discharge)
 ↳ **1=Orifice/Grate** (Orifice Controls 15.87 cfs @ 8.98 fps)

Pond INFIL 1B2: INFILTRATOR 1B2



Summary for Pond INFIL BASIN B3: INFIL BASIN B3

Inflow Area = 6.290 ac, 34.98% Impervious, Inflow Depth > 4.61" for 100-yr event
 Inflow = 27.00 cfs @ 12.19 hrs, Volume= 2.416 af
 Outflow = 21.89 cfs @ 12.32 hrs, Volume= 2.262 af, Atten= 19%, Lag= 7.8 min
 Discarded = 0.10 cfs @ 12.32 hrs, Volume= 0.058 af
 Primary = 21.79 cfs @ 12.32 hrs, Volume= 2.204 af
 Routed to Pond EXISTING POND : EXISTING POND

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 103.68' @ 12.32 hrs Surf.Area= 6,489 sf Storage= 19,606 cf

Plug-Flow detention time= 41.5 min calculated for 2.254 af (93% of inflow)
 Center-of-Mass det. time= 19.9 min (813.3 - 793.4)


Volume	Invert	Avail.Storage	Storage Description		
#1	99.50'	25,262 cf	Existing Pond (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
99.50	3,074	220.0	0	0	3,074
100.00	3,428	230.0	1,625	1,625	3,449
102.00	4,993	267.0	8,372	9,997	4,995
104.00	6,798	305.0	11,745	21,741	6,817
104.50	7,285	315.0	3,520	25,262	7,334

Device	Routing	Invert	Outlet Devices
#1	Primary	101.00'	24.0" Round Culvert L= 50.0' Ke= 0.500 Inlet / Outlet Invert= 101.00' / 100.00' S= 0.0200 ' S= 0.0200 ' Cc= 0.900 n= 0.011 Concrete pipe, straight & clean, Flow Area= 3.14 sf
#2	Primary	103.50'	12.0' long + 3.0 ' SideZ x 6.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.37 2.51 2.70 2.68 2.68 2.67 2.65 2.65 2.65 2.65 2.66 2.66 2.67 2.69 2.72 2.76 2.83
#3	Discarded	99.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 89.00'

Discarded OutFlow Max=0.10 cfs @ 12.32 hrs HW=103.67' (Free Discharge)
 ↳3=Exfiltration (Controls 0.10 cfs)

Primary OutFlow Max=21.51 cfs @ 12.32 hrs HW=103.67' (Free Discharge)
 ↳1=Culvert (Inlet Controls 19.52 cfs @ 6.21 fps)
 ↳2=Broad-Crested Rectangular Weir (Weir Controls 1.98 cfs @ 0.96 fps)

Pond INFIL BASIN B3: INFIL BASIN B3



Summary for Pond INFIL BASIN B4: INFIL BASIN B4

Inflow Area = 9.010 ac, 33.83% Impervious, Inflow Depth > 4.74" for 100-yr event
 Inflow = 30.46 cfs @ 12.37 hrs, Volume= 3.560 af
 Outflow = 29.44 cfs @ 12.43 hrs, Volume= 3.386 af, Atten= 3%, Lag= 4.1 min
 Discarded = 0.08 cfs @ 12.43 hrs, Volume= 0.058 af
 Primary = 29.36 cfs @ 12.43 hrs, Volume= 3.327 af
 Routed to Pond EXISTING POND : EXISTING POND

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 95.03' @ 12.43 hrs Surf.Area= 5,255 sf Storage= 12,190 cf

Plug-Flow detention time= 28.7 min calculated for 3.375 af (95% of inflow)
 Center-of-Mass det. time= 11.8 min (811.5 - 799.7)

Volume	Invert	Avail.Storage	Storage Description			
#1	92.00'	17,673 cf	Infil Basin B4 (Irregular) Listed below (Recalc)			
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)	
92.00	2,832	377.0	0	0	2,832	
94.00	4,424	403.0	7,197	7,197	4,624	
96.00	6,097	428.0	10,476	17,673	6,475	

Device	Routing	Invert	Outlet Devices									
#1	Primary	94.00'	24.0" x 36.0" Horiz. Orifice/Grate C= 0.600 Limited to weir flow at low heads									
#2	Primary	95.50'	12.0' long + 3.0 ' SideZ x 6.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 5.00 5.50 Coef. (English) 2.37 2.51 2.70 2.68 2.68 2.67 2.65 2.65 2.65									
#3	Discarded	92.00'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 82.00'									

Discarded OutFlow Max=0.08 cfs @ 12.43 hrs HW=95.03' (Free Discharge)


↳ **3=Exfiltration** (Controls 0.08 cfs)

Primary OutFlow Max=29.29 cfs @ 12.43 hrs HW=95.03' (Free Discharge)

↳ **1=Orifice/Grate** (Orifice Controls 29.29 cfs @ 4.88 fps)

↳ **2=Broad-Crested Rectangular Weir** (Controls 0.00 cfs)

Pond INFIL BASIN B4: INFIL BASIN B4



Summary for Pond U.G. INFIL ROOF 1: U.G. INFIL ROOF 1

Inflow Area = 0.430 ac, 100.00% Impervious, Inflow Depth > 7.56" for 100-yr event
 Inflow = 3.60 cfs @ 12.07 hrs, Volume= 0.271 af
 Outflow = 3.25 cfs @ 12.11 hrs, Volume= 0.228 af, Atten= 10%, Lag= 2.4 min
 Discarded = 0.02 cfs @ 12.11 hrs, Volume= 0.018 af
 Primary = 3.24 cfs @ 12.11 hrs, Volume= 0.210 af
 Routed to Pond INFIL BASIN B3 : INFIL BASIN B3

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 152.23' @ 12.11 hrs Surf.Area= 1,033 sf Storage= 2,488 cf

Plug-Flow detention time= 90.9 min calculated for 0.227 af (84% of inflow)
 Center-of-Mass det. time= 44.2 min (776.4 - 732.2)

Volume	Invert	Avail.Storage	Storage Description
#1A	148.50'	1,228 cf	18.50'W x 55.83'L x 4.50'H Field A 4,648 cf Overall - 1,578 cf Embedded = 3,070 cf x 40.0% Voids
#2A	149.00'	1,578 cf	Cultec R-360HD x 42 Inside #1 Effective Size= 54.9"W x 36.0"H => 9.99 sf x 3.67'L = 36.6 cf Overall Size= 60.0"W x 36.0"H x 4.17'L with 0.50' Overlap 42 Chambers in 3 Rows Cap Storage= 6.5 cf x 2 x 3 rows = 38.8 cf
		2,806 cf	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	151.00'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	148.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 138.00'

Discarded OutFlow Max=0.02 cfs @ 12.11 hrs HW=152.21' (Free Discharge)
 ↑**2=Exfiltration** (Controls 0.02 cfs)

Primary OutFlow Max=3.18 cfs @ 12.11 hrs HW=152.21' (Free Discharge)
 ↑**1=Orifice/Grate** (Orifice Controls 3.18 cfs @ 4.05 fps)

Pond U.G. INFIL ROOF 1: U.G. INFIL ROOF 1



Summary for Pond U.G. INFIL ROOF 2: U.G. INFIL ROOF 2

Inflow Area = 0.430 ac, 100.00% Impervious, Inflow Depth > 7.56" for 100-yr event
 Inflow = 3.60 cfs @ 12.07 hrs, Volume= 0.271 af
 Outflow = 3.25 cfs @ 12.11 hrs, Volume= 0.228 af, Atten= 10%, Lag= 2.4 min
 Discarded = 0.02 cfs @ 12.11 hrs, Volume= 0.018 af
 Primary = 3.24 cfs @ 12.11 hrs, Volume= 0.210 af
 Routed to Pond INFIL BASIN B3 : INFIL BASIN B3

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 152.23' @ 12.11 hrs Surf.Area= 1,033 sf Storage= 2,488 cf

Plug-Flow detention time= 90.9 min calculated for 0.227 af (84% of inflow)
 Center-of-Mass det. time= 44.2 min (776.4 - 732.2)

Volume	Invert	Avail.Storage	Storage Description
#1A	148.50'	1,228 cf	18.50'W x 55.83'L x 4.50'H Field A 4,648 cf Overall - 1,578 cf Embedded = 3,070 cf x 40.0% Voids
#2A	149.00'	1,578 cf	Cultec R-360HD x 42 Inside #1 Effective Size= 54.9"W x 36.0"H => 9.99 sf x 3.67'L = 36.6 cf Overall Size= 60.0"W x 36.0"H x 4.17'L with 0.50' Overlap 42 Chambers in 3 Rows Cap Storage= 6.5 cf x 2 x 3 rows = 38.8 cf
		2,806 cf	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	151.00'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	148.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 138.00'

Discarded OutFlow Max=0.02 cfs @ 12.11 hrs HW=152.21' (Free Discharge)
 ↑**2=Exfiltration** (Controls 0.02 cfs)

Primary OutFlow Max=3.18 cfs @ 12.11 hrs HW=152.21' (Free Discharge)
 ↑**1=Orifice/Grate** (Orifice Controls 3.18 cfs @ 4.05 fps)

Pond U.G. INFIL ROOF 2: U.G. INFIL ROOF 2



Summary for Pond U.G. INFIL ROOF 3: U.G. INFIL ROOF 3

Inflow Area = 0.430 ac, 100.00% Impervious, Inflow Depth > 7.56" for 100-yr event
 Inflow = 3.60 cfs @ 12.07 hrs, Volume= 0.271 af
 Outflow = 3.25 cfs @ 12.11 hrs, Volume= 0.228 af, Atten= 10%, Lag= 2.4 min
 Discarded = 0.02 cfs @ 12.11 hrs, Volume= 0.018 af
 Primary = 3.24 cfs @ 12.11 hrs, Volume= 0.210 af
 Routed to Pond INFIL BASIN B4 : INFIL BASIN B4

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 152.23' @ 12.11 hrs Surf.Area= 1,033 sf Storage= 2,488 cf

Plug-Flow detention time= 90.9 min calculated for 0.227 af (84% of inflow)
 Center-of-Mass det. time= 44.2 min (776.4 - 732.2)

Volume	Invert	Avail.Storage	Storage Description
#1A	148.50'	1,228 cf	18.50'W x 55.83'L x 4.50'H Field A 4,648 cf Overall - 1,578 cf Embedded = 3,070 cf x 40.0% Voids
#2A	149.00'	1,578 cf	Cultec R-360HD x 42 Inside #1 Effective Size= 54.9"W x 36.0"H => 9.99 sf x 3.67'L = 36.6 cf Overall Size= 60.0"W x 36.0"H x 4.17'L with 0.50' Overlap 42 Chambers in 3 Rows Cap Storage= 6.5 cf x 2 x 3 rows = 38.8 cf
		2,806 cf	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	151.00'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	148.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 138.00'

Discarded OutFlow Max=0.02 cfs @ 12.11 hrs HW=152.21' (Free Discharge)
 ↑**2=Exfiltration** (Controls 0.02 cfs)

Primary OutFlow Max=3.18 cfs @ 12.11 hrs HW=152.21' (Free Discharge)
 ↑**1=Orifice/Grate** (Orifice Controls 3.18 cfs @ 4.05 fps)

Pond U.G. INFIL ROOF 3: U.G. INFIL ROOF 3



Summary for Pond U.G. INFIL ROOF 4: U.G. INFIL ROOF 4

Inflow Area = 0.430 ac, 100.00% Impervious, Inflow Depth > 7.56" for 100-yr event
 Inflow = 3.60 cfs @ 12.07 hrs, Volume= 0.271 af
 Outflow = 3.25 cfs @ 12.11 hrs, Volume= 0.228 af, Atten= 10%, Lag= 2.4 min
 Discarded = 0.02 cfs @ 12.11 hrs, Volume= 0.018 af
 Primary = 3.24 cfs @ 12.11 hrs, Volume= 0.210 af
 Routed to Pond INFIL BASIN B4 : INFIL BASIN B4

Routing by Stor-Ind method, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Peak Elev= 152.23' @ 12.11 hrs Surf.Area= 1,033 sf Storage= 2,488 cf

Plug-Flow detention time= 90.9 min calculated for 0.227 af (84% of inflow)
 Center-of-Mass det. time= 44.2 min (776.4 - 732.2)

Volume	Invert	Avail.Storage	Storage Description
#1A	148.50'	1,228 cf	18.50'W x 55.83'L x 4.50'H Field A 4,648 cf Overall - 1,578 cf Embedded = 3,070 cf x 40.0% Voids
#2A	149.00'	1,578 cf	Cultec R-360HD x 42 Inside #1 Effective Size= 54.9"W x 36.0"H => 9.99 sf x 3.67'L = 36.6 cf Overall Size= 60.0"W x 36.0"H x 4.17'L with 0.50' Overlap 42 Chambers in 3 Rows Cap Storage= 6.5 cf x 2 x 3 rows = 38.8 cf
		2,806 cf	Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	151.00'	12.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Discarded	148.50'	0.520 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 138.00'

Discarded OutFlow Max=0.02 cfs @ 12.11 hrs HW=152.21' (Free Discharge)
 ↳ **2=Exfiltration** (Controls 0.02 cfs)

Primary OutFlow Max=3.18 cfs @ 12.11 hrs HW=152.21' (Free Discharge)
 ↳ **1=Orifice/Grate** (Orifice Controls 3.18 cfs @ 4.05 fps)

Pond U.G. INFIL ROOF 4: U.G. INFIL ROOF 4




Summary for Link PR DP1: PR DP1

Inflow Area = 106.945 ac, 22.75% Impervious, Inflow Depth > 4.32" for 100-yr event
Inflow = 210.51 cfs @ 12.89 hrs, Volume= 38.530 af
Primary = 210.51 cfs @ 12.89 hrs, Volume= 38.530 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link PR DP1: PR DP1

Hydrograph







PR-DA2



PR-DP2



Area Listing (selected nodes)

Area (acres)	CN	Description (subcatchment-numbers)
0.660	61	>75% Grass cover, Good, HSG B (PR-DA2)
0.350	98	Paved parking, HSG B (PR-DA2)
1.690	55	Woods, Good, HSG B (PR-DA2)
2.700	62	TOTAL AREA

Soil Listing (selected nodes)

Area (acres)	Soil Group	Subcatchment Numbers
0.000	HSG A	
2.700	HSG B	PR-DA2
0.000	HSG C	
0.000	HSG D	
0.000	Other	
2.700		TOTAL AREA

Ground Covers (selected nodes)

HSG-A (acres)	HSG-B (acres)	HSG-C (acres)	HSG-D (acres)	Other (acres)	Total (acres)	Ground Cover	Subcatchment Numbers
0.000	0.660	0.000	0.000	0.000	0.660	>75% Grass cover, Good	PR-DA2
0.000	0.350	0.000	0.000	0.000	0.350	Paved parking	PR-DA2
0.000	1.690	0.000	0.000	0.000	1.690	Woods, Good	PR-DA2
0.000	2.700	0.000	0.000	0.000	2.700	TOTAL AREA	

Summary for Subcatchment PR-DA2: PR-DA2

Runoff = 0.64 cfs @ 12.27 hrs, Volume= 0.081 af, Depth> 0.36"
 Routed to Link PR-DP2 : PR-DP2


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 1-yr Rainfall=3.04"

Area (ac)	CN	Description
0.350	98	Paved parking, HSG B
1.690	55	Woods, Good, HSG B
0.660	61	>75% Grass cover, Good, HSG B
2.700	62	Weighted Average
2.350		87.04% Pervious Area
0.350		12.96% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.7	100	0.2600	0.22		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
5.7	620	0.1300	1.80		Shallow Concentrated Flow, Shallow Concentrated Woods Woodland Kv= 5.0 fps
0.1	45	0.0100	6.75	67.55	Channel Flow, Stream Channel Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.022 Earth, clean & straight
13.5	765	Total			

Subcatchment PR-DA2: PR-DA2

Hydrograph




Summary for Link PR-DP2: PR-DP2

Inflow Area = 2.700 ac, 12.96% Impervious, Inflow Depth > 0.36" for 1-yr event
Inflow = 0.64 cfs @ 12.27 hrs, Volume= 0.081 af
Primary = 0.64 cfs @ 12.27 hrs, Volume= 0.081 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link PR-DP2: PR-DP2

Hydrograph



Summary for Subcatchment PR-DA2: PR-DA2


Runoff = 1.32 cfs @ 12.23 hrs, Volume= 0.138 af, Depth> 0.61"
 Routed to Link PR-DP2 : PR-DP2

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 2-yr Rainfall=3.66"

Area (ac)	CN	Description
0.350	98	Paved parking, HSG B
1.690	55	Woods, Good, HSG B
0.660	61	>75% Grass cover, Good, HSG B
2.700	62	Weighted Average
2.350		87.04% Pervious Area
0.350		12.96% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.7	100	0.2600	0.22		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
5.7	620	0.1300	1.80		Shallow Concentrated Flow, Shallow Concentrated Woods Woodland Kv= 5.0 fps
0.1	45	0.0100	6.75	67.55	Channel Flow, Stream Channel Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.022 Earth, clean & straight
13.5	765	Total			

Subcatchment PR-DA2: PR-DA2




Summary for Link PR-DP2: PR-DP2

Inflow Area = 2.700 ac, 12.96% Impervious, Inflow Depth > 0.61" for 2-yr event
Inflow = 1.32 cfs @ 12.23 hrs, Volume= 0.138 af
Primary = 1.32 cfs @ 12.23 hrs, Volume= 0.138 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link PR-DP2: PR-DP2

Hydrograph



Summary for Subcatchment PR-DA2: PR-DA2


Runoff = 2.74 cfs @ 12.21 hrs, Volume= 0.251 af, Depth> 1.12"
 Routed to Link PR-DP2 : PR-DP2

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 5-yr Rainfall=4.67"

Area (ac)	CN	Description
0.350	98	Paved parking, HSG B
1.690	55	Woods, Good, HSG B
0.660	61	>75% Grass cover, Good, HSG B
2.700	62	Weighted Average
2.350		87.04% Pervious Area
0.350		12.96% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.7	100	0.2600	0.22		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
5.7	620	0.1300	1.80		Shallow Concentrated Flow, Shallow Concentrated Woods Woodland Kv= 5.0 fps
0.1	45	0.0100	6.75	67.55	Channel Flow, Stream Channel Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.022 Earth, clean & straight
13.5	765	Total			

Subcatchment PR-DA2: PR-DA2




Summary for Link PR-DP2: PR-DP2

Inflow Area = 2.700 ac, 12.96% Impervious, Inflow Depth > 1.12" for 5-yr event
Inflow = 2.74 cfs @ 12.21 hrs, Volume= 0.251 af
Primary = 2.74 cfs @ 12.21 hrs, Volume= 0.251 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link PR-DP2: PR-DP2



Summary for Subcatchment PR-DA2: PR-DA2


Runoff = 4.10 cfs @ 12.20 hrs, Volume= 0.360 af, Depth> 1.60"
 Routed to Link PR-DP2 : PR-DP2

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 10-yr Rainfall=5.51"

Area (ac)	CN	Description
0.350	98	Paved parking, HSG B
1.690	55	Woods, Good, HSG B
0.660	61	>75% Grass cover, Good, HSG B
2.700	62	Weighted Average
2.350		87.04% Pervious Area
0.350		12.96% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.7	100	0.2600	0.22		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
5.7	620	0.1300	1.80		Shallow Concentrated Flow, Shallow Concentrated Woods Woodland Kv= 5.0 fps
0.1	45	0.0100	6.75	67.55	Channel Flow, Stream Channel Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.022 Earth, clean & straight
13.5	765	Total			

Subcatchment PR-DA2: PR-DA2




Summary for Link PR-DP2: PR-DP2

Inflow Area = 2.700 ac, 12.96% Impervious, Inflow Depth > 1.60" for 10-yr event
Inflow = 4.10 cfs @ 12.20 hrs, Volume= 0.360 af
Primary = 4.10 cfs @ 12.20 hrs, Volume= 0.360 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link PR-DP2: PR-DP2

Hydrograph



Summary for Subcatchment PR-DA2: PR-DA2


Runoff = 6.15 cfs @ 12.20 hrs, Volume= 0.528 af, Depth> 2.35"
 Routed to Link PR-DP2 : PR-DP2

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 25-yr Rainfall=6.67"

Area (ac)	CN	Description
0.350	98	Paved parking, HSG B
1.690	55	Woods, Good, HSG B
0.660	61	>75% Grass cover, Good, HSG B
2.700	62	Weighted Average
2.350		87.04% Pervious Area
0.350		12.96% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.7	100	0.2600	0.22		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
5.7	620	0.1300	1.80		Shallow Concentrated Flow, Shallow Concentrated Woods Woodland Kv= 5.0 fps
0.1	45	0.0100	6.75	67.55	Channel Flow, Stream Channel Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.022 Earth, clean & straight
13.5	765	Total			

Subcatchment PR-DA2: PR-DA2




Summary for Link PR-DP2: PR-DP2

Inflow Area = 2.700 ac, 12.96% Impervious, Inflow Depth > 2.35" for 25-yr event
Inflow = 6.15 cfs @ 12.20 hrs, Volume= 0.528 af
Primary = 6.15 cfs @ 12.20 hrs, Volume= 0.528 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link PR-DP2: PR-DP2

Hydrograph



Summary for Subcatchment PR-DA2: PR-DA2

Runoff = 7.79 cfs @ 12.20 hrs, Volume= 0.663 af, Depth> 2.95"
 Routed to Link PR-DP2 : PR-DP2


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 50-yr Rainfall=7.54"

Area (ac)	CN	Description
0.350	98	Paved parking, HSG B
1.690	55	Woods, Good, HSG B
0.660	61	>75% Grass cover, Good, HSG B
2.700	62	Weighted Average
2.350		87.04% Pervious Area
0.350		12.96% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.7	100	0.2600	0.22		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
5.7	620	0.1300	1.80		Shallow Concentrated Flow, Shallow Concentrated Woods Woodland Kv= 5.0 fps
0.1	45	0.0100	6.75	67.55	Channel Flow, Stream Channel Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.022 Earth, clean & straight
13.5	765	Total			

Subcatchment PR-DA2: PR-DA2

Hydrograph




Summary for Link PR-DP2: PR-DP2

Inflow Area = 2.700 ac, 12.96% Impervious, Inflow Depth > 2.95" for 50-yr event
Inflow = 7.79 cfs @ 12.20 hrs, Volume= 0.663 af
Primary = 7.79 cfs @ 12.20 hrs, Volume= 0.663 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link PR-DP2: PR-DP2

Hydrograph



Summary for Subcatchment PR-DA2: PR-DA2


Runoff = 9.60 cfs @ 12.19 hrs, Volume= 0.813 af, Depth> 3.62"
 Routed to Link PR-DP2 : PR-DP2

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs
 Type III 24-hr 100-yr Rainfall=8.46"

Area (ac)	CN	Description
0.350	98	Paved parking, HSG B
1.690	55	Woods, Good, HSG B
0.660	61	>75% Grass cover, Good, HSG B
2.700	62	Weighted Average
2.350		87.04% Pervious Area
0.350		12.96% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.7	100	0.2600	0.22		Sheet Flow, Sheet Flow Woods Woods: Light underbrush n= 0.400 P2= 3.20"
5.7	620	0.1300	1.80		Shallow Concentrated Flow, Shallow Concentrated Woods Woodland Kv= 5.0 fps
0.1	45	0.0100	6.75	67.55	Channel Flow, Stream Channel Area= 10.0 sf Perim= 10.0' r= 1.00' n= 0.022 Earth, clean & straight
13.5	765	Total			

Subcatchment PR-DA2: PR-DA2




Summary for Link PR-DP2: PR-DP2

Inflow Area = 2.700 ac, 12.96% Impervious, Inflow Depth > 3.62" for 100-yr event
Inflow = 9.60 cfs @ 12.19 hrs, Volume= 0.813 af
Primary = 9.60 cfs @ 12.19 hrs, Volume= 0.813 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 5.00-20.00 hrs, dt= 0.05 hrs

Link PR-DP2: PR-DP2



Appendix E – Water Quality Calculations

WATER QUALITY CALCULATIONS
800 Long Ridge Road
Stamford, CT

BLT Apartment Buildings
 Storm Drainage - PRDA-1B1

Job No 4084
 Designed by SQ
 Sheet No. 1 of 1
 Date 9/27/2023

Storm Water Quality Calculations - WQV - Water Quality Volume
 As defined in Chapter 7 of the "2004 CT Stormwater Quality Manual"

WQV= Water Quality Volume

WQV= $\frac{(1")(R)(A)}{12 \text{ IN/FT.}}$

Area= Total inflowing drainage area on and off site entering stormwater quality system as Acres
 Note: See drainage area map(s)

Drainage Area in Acres Entering System: Rational Method Coefficient:
 A= 2.660 Acres C = 0.98

Percent of Impervious Cover Inflowing Drainage Area:
 I= $\frac{1.800}{2.660} \times 100 = 67.67 \%$ of Impervious Area

Volumetric Runoff Coefficient:
 R= $0.05 + 0.009(I) = 0.6590$ Coefficient

Water Quality Volume:
 Required WQV= $\frac{1xRxA}{12} = \frac{0.1461 \text{ Acre Feet}}{6,363 \text{ cubic feet}}$

Provided WQV= $\frac{0.1560 \text{ Acre Feet}}{6,795 \text{ cubic feet}}$

Storm Water Quality Calculations - WQF - Water Quality Flow
 As defined in Connecticut Stormwater Design Manual

Q = $\frac{WQV(\text{acre-feet})x12}{\text{Drainage Area}}$

Q = Runoff Depth (Inches)

WQV (ACRE FEET) = 0.1461 Acre Feet

Drainage Area = Total inflowing drainage area on and off site entering stormwater quality system (Acres)

Drainage Area = 2.6600 Acres

Q = 0.6590 Inches

NRCS Runoff Curve Number:
 $CN = \frac{1000}{10+5P+10Q-10(Q^2+1.25QP)^{1/2}}$

CN = 96.40

la = $200/CN-2$

la = 0.0748

P = 1 Inch

$\frac{la}{P} = 0.0748$

Time of Concentration = 11.7 minutes = 0.195 hours

Therefore, $q_u = 550$ cfs/sq mi/inch runoff (From Exhibit 4-III in TR-55)

Compute Water Quality Flow:

A = Drain Area Miles² = 0.00416 sq mi

WQF=(q_u)(A)(Q) = 1.51 cfs

WATER QUALITY CALCULATIONS
800 Long Ridge Road
Stamford, CT

BLT Apartment Buildings
 Storm Drainage - PRDA-1B2

Job No 4084
 Designed by SQ
 Sheet No. 1 of 1
 Date 9/27/2023

Storm Water Quality Calculations - WQV - Water Quality Volume
 As defined in Chapter 7 of the "2004 CT Stormwater Quality Manual"

WQV= $\frac{\text{Water Quality Volume}}{12 \text{ IN/FT.}}$

WQV= $\frac{(1 \text{ "})(R)(A)}{12 \text{ IN/FT.}}$

Area= Total inflowing drainage area on and off site entering stormwater quality system as Acres
 Note: See drainage area map(s)

Drainage Area in Acres Entering System: Rational Method Coefficient:
 A= 2.350 Acres C = 0.98

Percent of Impervious Cover Inflowing Drainage Area:
 I= $\frac{1.760}{2.350} \times 100 = 74.89 \%$ of Impervious Area

Volumetric Runoff Coefficient:
 R= $0.05 + 0.009(I) = 0.7240$ Coefficient

Water Quality Volume:
 Required WQV= $\frac{1 \times R \times A}{12} = \frac{0.1418 \text{ Acre Feet}}{6,176 \text{ cubic feet}}$

Provided WQV= $\frac{0.1620 \text{ Acre Feet}}{7,035 \text{ cubic feet}}$

Storm Water Quality Calculations - WQF - Water Quality Flow
 As defined in Connecticut Stormwater Design Manual

Q = $\frac{\text{WQV(acre-feet)} \times 12}{\text{Drainage Area}}$

Q = Runoff Depth (Inches)

WQV (ACRE FEET) = 0.1418 Acre Feet

Drainage Area = Total inflowing drainage area on and off site entering stormwater quality system (Acres)

Drainage Area = 2.3500 Acres

Q = 0.7240 Inches

NRCS Runoff Curve Number:
 $CN = \frac{1000}{10 + 5P + 10Q - 10(Q^2 + 1.25QP)^{1/2}}$

CN = 97.23

la = $200 / CN - 2$

la = 0.0570

P = 1 Inch

$\frac{la}{P} = 0.0570$

Time of Concentration = 10.7 minutes = 0.1 hours

Therefore, $q_u = 650$ cfs/sq mi/inch runoff (From Exhibit 4-III in TR-55)

Compute Water Quality Flow:

A = Drain Area Miles² = 0.00367 sq mi

WQF=(q_u)(A)(Q) = 1.73 cfs

WATER QUALITY CALCULATIONS
800 Long Ridge Road
Stamford, CT

BLT Apartment Buildings
 Storm Drainage - PRDA-1B3

Job No 4084
 Designed by SQ
 Sheet No. 1 of 1
 Date 9/27/2023

Storm Water Quality Calculations - WQV - Water Quality Volume
 As defined in Chapter 7 of the "2004 CT Stormwater Quality Manual"

WQV= Water Quality Volume

WQV= $\frac{(1")(R)(A)}{12 \text{ IN/FT.}}$

Area= Total inflowing drainage area on and off site entering stormwater quality system as Acres
 Note: See drainage area map(s)

Drainage Area in Acres Entering System: Rational Method Coefficient:
 A= 5.430 Acres C = 0.98

Percent of Impervious Cover Inflowing Drainage Area:
 I= $\frac{1.340}{5.430} \times 100 = 24.68 \%$ of Impervious Area

Volumetric Runoff Coefficient:
 R= $0.05 + 0.009(I) = 0.2721$ Coefficient

Water Quality Volume:
 Required WQV= $\frac{1xRxA}{12} = \frac{0.1231 \text{ Acre Feet}}{5,363 \text{ cubic feet}}$

Provided WQV= $\frac{0.1240 \text{ Acre Feet}}{5,419 \text{ cubic feet}}$

Storm Water Quality Calculations - WQF - Water Quality Flow
 As defined in Connecticut Stormwater Design Manual

Q = $\frac{WQV(\text{acre-feet})x12}{\text{Drainage Area}}$

Q = Runoff Depth (Inches)

WQV (ACRE FEET) = 0.1231 Acre Feet

Drainage Area = Total inflowing drainage area on and off site entering stormwater quality system (Acres)

Drainage Area = 5.4300 Acres

Q = 0.2721 Inches

NRCS Runoff Curve Number:
 $CN = \frac{1000}{10+5P+10Q-10(Q^2+1.25QP)^{1/2}}$

CN = 88.61

la = $200/CN-2$

la = 0.2571

P = 1 Inch

$\frac{la}{P} = 0.2571$

Time of Concentration = 15.7 minutes = 0.262 hours

Therefore, $q_u = 450$ cfs/sq mi/inch runoff (From Exhibit 4-III in TR-55)

Compute Water Quality Flow:

A = Drain Area Miles² = 0.00848 sq mi

WQF=(q_u)(A)(Q) = 1.04 cfs

WATER QUALITY CALCULATIONS
800 Long Ridge Road
Stamford, CT

BLT Apartment Buildings
 Storm Drainage - PRDA-1B4

Job No 4084
 Designed by SQ
 Sheet No. 1 of 1
 Date 9/27/2023

Storm Water Quality Calculations - WQV - Water Quality Volume
 As defined in Chapter 7 of the "2004 CT Stormwater Quality Manual"

WQV= $\frac{\text{Water Quality Volume}}{12 \text{ IN/FT.}}$

Area= Total inflowing drainage area on and off site entering stormwater quality system as Acres
 Note: See drainage area map(s)

Drainage Area in Acres Entering System: Rational Method Coefficient:
 A= 8.150 Acres C = 0.98

Percent of Impervious Cover Inflowing Drainage Area:
 $I = \frac{1.640}{8.150} \times 100 = 20.12 \%$ of Impervious Area

Volumetric Runoff Coefficient:
 $R = 0.05 + 0.009(I) = 0.2311$ Coefficient

Water Quality Volume:
 Required WQV= $\frac{1 \times R \times A}{12} = \frac{0.1570 \text{ Acre Feet}}{6,837 \text{ cubic feet}}$

Provided WQV= $\frac{0.1650 \text{ Acre Feet}}{7,197 \text{ cubic feet}}$

Storm Water Quality Calculations - WQF - Water Quality Flow
 As defined in Connecticut Stormwater Design Manual

$Q = \frac{WQV(\text{acre-feet}) \times 12}{\text{Drainage Area}}$

Q = Runoff Depth (Inches)

WQV (ACRE FEET) = 0.1570 Acre Feet

Drainage Area = Total inflowing drainage area on and off site entering stormwater quality system (Acres)

Drainage Area = 8.1500 Acres

Q = 0.2311 Inches

NRCS Runoff Curve Number:
 $CN = \frac{1000}{10 + 5P + 10Q - 10(Q^2 + 1.25QP)^{1/2}}$

CN = 87.26

$I_a = 200 / CN - 2$

$I_a = 0.2921$

P = 1 Inch

$\frac{I_a}{P} = 0.2921$

Time of Concentration = 27.4 minutes = 0.46 hours

Therefore, $q_u = 375$ cfs/sq mi/inch runoff (From Exhibit 4-III in TR-55)

Compute Water Quality Flow:

A = Drain Area Miles² = 0.01273 sq mi

WQF=(q_u)(A)(Q) = 1.10 cfs

WATER QUALITY CALCULATIONS
800 Long Ridge Road
Stamford, CT

BLT Apartment Buildings
 Storm Drainage - North Building Roof Quadrant (Typ.)

Job No 4084
 Designed by SQ
 Sheet No. 1 of 1
 Date 9/28/2023

Storm Water Quality Calculations - WQV - Water Quality Volume
 As defined in Chapter 7 of the "2004 CT Stormwater Quality Manual"

WQV= Water Quality Volume

$$WQV = \frac{(1")(R)(A)}{12 \text{ IN/FT.}}$$

Area= Total inflowing drainage area on and off site entering stormwater quality system as Acres
 Note: See drainage area map(s)

Drainage Area in Acres Entering System: Rational Method Coefficient:
 A= 0.430 Acres C = 0.98

Percent of Impervious Cover Inflowing Drainage Area:

$$I = \frac{0.430}{0.430} \times 100 = 100.00 \text{ \% of Impervious Area}$$

Volumetric Runoff Coefficient:

$$R = 0.05 + 0.009(I) = 0.9500 \text{ Coefficient}$$

Water Quality Volume:
 Required WQV=
$$\frac{1xRxA}{12} = \frac{0.0340 \text{ Acre Feet}}{1,483 \text{ cubic feet}}$$

Provided WQV=
$$= \frac{0.0410 \text{ Acre Feet}}{1,795 \text{ cubic feet}}$$

Storm Water Quality Calculations - WQF - Water Quality Flow
 As defined in Connecticut Stormwater Design Manual

$$Q = \frac{WQV(\text{acre-feet}) \times 12}{\text{Drainage Area}}$$

Q = Runoff Depth (Inches)

WQV (ACRE FEET) = 0.0340 Acre Feet

Drainage Area = Total inflowing drainage area on and off site entering stormwater quality system (Acres)

Drainage Area = 0.4300 Acres

Q = 0.9500 Inches

NRCS Runoff Curve Number:

$$CN = \frac{1000}{10 + 5P + 10Q - 10(Q^2 + 1.25QP)^{1/2}}$$

CN = 99.57

la = 200/CN-2

la = 0.0086

P = 1 Inch

$$\frac{la}{P} = 0.0086$$

Time of Concentration = 5 minutes = 0.083 hours

Therefore, $q_u = 650$ cfs/sq mi/inch runoff (From Exhibit 4-III in TR-55)

Compute Water Quality Flow:

A = Drain Area Miles² = 0.00067 sq mi

WQF=(q_u)(A)(Q) = 0.41 cfs

Appendix F – Hydrodynamic Separator Sizing Calculations

Hydrodynamic Separation Product Calculator

800 Long Ridge Road

CB3 TO INFIL BED 1B1

CDS 2015-4

Project Information					
Project Name	800 Long Ridge Road			Option #	A
Country	UNITED_STATES	State	Connecticut	City	Stamford

Contact Information			
First Name	Emily	Last Name	Jones
Company	Civil 1	Phone #	203-266-0778
Email	emily@civil1.com		

Design Criteria					
Site Designation	CB3 TO INFIL BED 1B1			Sizing Method	Net Annual
Screening Required?	No	Drainage Area (ac)	2.66	Peak Flow (cfs)	5.54
Groundwater Depth (ft)	10 - 15	Pipe Invert Depth (ft)	5 - 10	Bedrock Depth (ft)	10 - 15
Multiple Inlets?	No	Grate Inlet Required?	Yes	Pipe Size (in)	15.00
Required Particle Size Distribution?	No	90° between two inlets?	N/A	180° between inlet and outlet?	No
Runoff Coefficient	0.66	Rainfall Station	34 - Birdgeport Airport, CT	TC (Min)	12

Treatment Selection					
Treatment Unit	CDS	System Model	2015-4		
Target Removal	80%	Particle Size Distribution (PSD)	125	Predicted Net Annual Removal	81.20%

Hydrodynamic Separation Product Calculator

800 Long Ridge Road

CB3 TO INFIL BED 1B1

CDS 2015-4

CDS ESTIMATED NET ANNUAL SOLIDS LOAD REDUCTION BASED ON THE RATIONAL RAINFALL METHOD

Rainfall Intensity ¹ (in/hr)	% Rainfall Volume ¹	Cumulative Rainfall Volume	Rainfall Volume Treated	Total Flowrate (cfs)	Treated Flowrate (cfs)	Operating Rate (%)	Removal Efficiency (%)	Incremental Removal (%)
0.0200	9.71%	9.71%	9.71%	0.0351	0.0351	5.01%	100.00%	9.71%
0.0400	9.68%	19.39%	9.68%	0.0702	0.0702	10.03%	99.40%	9.62%
0.0600	9.81%	29.20%	9.81%	0.1053	0.1053	15.04%	98.40%	9.65%
0.0800	7.67%	36.87%	7.67%	0.1404	0.1404	20.06%	97.40%	7.47%
0.1000	8.04%	44.91%	8.04%	0.1756	0.1756	25.09%	96.39%	7.75%
0.1200	5.44%	50.35%	5.44%	0.2107	0.2107	30.10%	95.39%	5.19%
0.1400	4.65%	55.00%	4.65%	0.2458	0.2458	35.11%	94.38%	4.39%
0.1600	5.49%	60.49%	5.49%	0.2809	0.2809	40.13%	93.38%	5.13%
0.1800	3.45%	63.94%	3.45%	0.3160	0.3160	45.14%	92.38%	3.19%
0.2000	4.08%	68.02%	4.08%	0.3511	0.3511	50.16%	91.37%	3.73%
0.2500	6.51%	74.53%	6.51%	0.4389	0.4389	62.70%	88.86%	5.78%
0.3000	5.47%	80.00%	5.47%	0.5267	0.5267	75.24%	86.35%	4.72%
0.3500	4.02%	84.02%	4.02%	0.6145	0.6145	87.79%	83.84%	3.37%
0.4000	1.98%	86.00%	1.97%	0.7022	0.7000	100.00%	81.14%	1.61%
0.4500	2.13%	88.13%	1.89%	0.7900	0.7000	100.00%	72.13%	1.54%
0.5000	2.03%	90.16%	1.62%	0.8778	0.7000	100.00%	64.91%	1.32%
0.7500	5.11%	95.27%	2.72%	1.3167	0.7000	100.00%	43.27%	2.21%
1.0000	2.48%	97.75%	0.99%	1.7556	0.7000	100.00%	32.46%	0.81%
1.5000	1.76%	99.51%	0.47%	2.6334	0.7000	100.00%	21.64%	0.38%
2.0000	0.48%	99.99%	0.10%	3.5112	0.7000	100.00%	16.23%	0.08%
								87.65%
Removal Efficiency Adjustment ² =								6.45%
Predicted % Annual Rainfall Treated =								87.33%
Predicted Net Annual Load Removal Efficiency =								81.20%

1 - Based on 10 years of hourly precipitation data from NCDC station 806, Bridgeport WSO ARPT, Fairfield County, CT

2 - Reduction due to use of 60-minute data for a site that has a time of concentration less than 30-minutes.

Hydrodynamic Separation Product Calculator

800 Long Ridge Road
 CB 5 TO INFILTRATION BED 1B2
 CDS 2015-4

Project Information					
Project Name	800 Long Ridge Road			Option #	A
Country	UNITED_STATES	State	Connecticut	City	Stamford

Contact Information			
First Name	Emily	Last Name	Jones
Company	Civil 1	Phone #	203-266-0778
Email	emily@civil1.com		

Design Criteria					
Site Designation	CB 5 TO INFILTRATION BED 1B2			Sizing Method	Net Annual
Screening Required?	No	Drainage Area (ac)	2.35	Peak Flow (cfs)	5.28
Groundwater Depth (ft)	10 - 15	Pipe Invert Depth (ft)	0 - 5	Bedrock Depth (ft)	10 - 15
Multiple Inlets?	No	Grate Inlet Required?	Yes	Pipe Size (in)	15.00
Required Particle Size Distribution?	No	90° between two inlets?	N/A	180° between inlet and outlet?	No
Runoff Coefficient	0.72	Rainfall Station	34 - Birdgeport Airport, CT	TC (Min)	11

Treatment Selection					
Treatment Unit	CDS	System Model	2015-4		
Target Removal	80%	Particle Size Distribution (PSD)	125	Predicted Net Annual Removal	81.62%

Hydrodynamic Separation Product Calculator

800 Long Ridge Road

CB 5 TO INFILTRATION BED 1B2

CDS 2015-4

CDS ESTIMATED NET ANNUAL SOLIDS LOAD REDUCTION BASED ON THE RATIONAL RAINFALL METHOD

Rainfall Intensity ¹ (in/hr)	% Rainfall Volume ¹	Cumulative Rainfall Volume	Rainfall Volume Treated	Total Flowrate (cfs)	Treated Flowrate (cfs)	Operating Rate (%)	Removal Efficiency (%)	Incremental Removal (%)
0.0200	9.71%	9.71%	9.71%	0.0338	0.0338	4.83%	100.00%	9.71%
0.0400	9.68%	19.39%	9.68%	0.0677	0.0677	9.67%	99.48%	9.63%
0.0600	9.81%	29.20%	9.81%	0.1015	0.1015	14.50%	98.51%	9.66%
0.0800	7.67%	36.87%	7.67%	0.1354	0.1354	19.34%	97.54%	7.48%
0.1000	8.04%	44.91%	8.04%	0.1692	0.1692	24.17%	96.57%	7.76%
0.1200	5.44%	50.35%	5.44%	0.2030	0.2030	29.00%	95.61%	5.20%
0.1400	4.65%	55.00%	4.65%	0.2369	0.2369	33.84%	94.64%	4.40%
0.1600	5.49%	60.49%	5.49%	0.2707	0.2707	38.67%	93.67%	5.14%
0.1800	3.45%	63.94%	3.45%	0.3046	0.3046	43.51%	92.70%	3.20%
0.2000	4.08%	68.02%	4.08%	0.3384	0.3384	48.34%	91.74%	3.74%
0.2500	6.51%	74.53%	6.51%	0.4230	0.4230	60.43%	89.32%	5.81%
0.3000	5.47%	80.00%	5.47%	0.5076	0.5076	72.51%	86.90%	4.75%
0.3500	4.02%	84.02%	4.02%	0.5922	0.5922	84.60%	84.48%	3.40%
0.4000	1.98%	86.00%	1.98%	0.6768	0.6768	96.69%	82.06%	1.62%
0.4500	2.13%	88.13%	1.96%	0.7614	0.7000	100.00%	74.84%	1.59%
0.5000	2.03%	90.16%	1.68%	0.8460	0.7000	100.00%	67.35%	1.37%
0.7500	5.11%	95.27%	2.82%	1.2690	0.7000	100.00%	44.90%	2.29%
1.0000	2.48%	97.75%	1.03%	1.6920	0.7000	100.00%	33.68%	0.84%
1.5000	1.76%	99.51%	0.49%	2.5380	0.7000	100.00%	22.45%	0.40%
2.0000	0.48%	99.99%	0.10%	3.3840	0.7000	100.00%	16.84%	0.08%
								88.07%
Removal Efficiency Adjustment ² =								6.45%
Predicted % Annual Rainfall Treated =								87.63%
Predicted Net Annual Load Removal Efficiency =								81.62%

1 - Based on 10 years of hourly precipitation data from NCDC station 806, Bridgeport WSO ARPT, Fairfield County, CT

2 - Reduction due to use of 60-minute data for a site that has a time of concentration less than 30-minutes.

Hydrodynamic Separation Product Calculator

800 Long Ridge Road
 CB17 TO INFIL BASIN B3
 CDS 2015-4

Project Information					
Project Name	800 Long Ridge Road			Option #	A
Country	UNITED_STATES	State	Connecticut	City	Stamford

Contact Information			
First Name	Emily	Last Name	Jones
Company	Civil 1	Phone #	203-266-0778
Email	emily@civil1.com		

Design Criteria					
Site Designation	CB17 TO INFIL BASIN B3			Sizing Method	Net Annual
Screening Required?	No	Drainage Area (ac)	5.43	Peak Flow (cfs)	15.86
Groundwater Depth (ft)	10 - 15	Pipe Invert Depth (ft)	5 - 10	Bedrock Depth (ft)	10 - 15
Multiple Inlets?	No	Grate Inlet Required?	No	Pipe Size (in)	24.00
Required Particle Size Distribution?	No	90° between two inlets?	N/A	180° between inlet and outlet?	No
Runoff Coefficient	0.27	Rainfall Station	34 - Birdgeport Airport, CT	TC (Min)	16

Treatment Selection					
Treatment Unit	CDS	System Model	2015-4		
Target Removal	80%	Particle Size Distribution (PSD)	125	Predicted Net Annual Removal	83.32%

Hydrodynamic Separation Product Calculator

800 Long Ridge Road
 CB17 TO INFIL BASIN B3
 CDS 2015-4

CDS ESTIMATED NET ANNUAL SOLIDS LOAD REDUCTION BASED ON THE RATIONAL RAINFALL METHOD

Rainfall Intensity ¹ (in/hr)	% Rainfall Volume ¹	Cumulative Rainfall Volume	Rainfall Volume Treated	Total Flowrate (cfs)	Treated Flowrate (cfs)	Operating Rate (%)	Removal Efficiency (%)	Incremental Removal (%)	
0.0200	9.71%	9.71%	9.71%	0.0293	0.0293	4.19%	100.00%	9.71%	
0.0400	9.68%	19.39%	9.68%	0.0586	0.0586	8.37%	99.74%	9.65%	
0.0600	9.81%	29.20%	9.81%	0.0880	0.0880	12.57%	98.89%	9.70%	
0.0800	7.67%	36.87%	7.67%	0.1173	0.1173	16.76%	98.06%	7.52%	
0.1000	8.04%	44.91%	8.04%	0.1466	0.1466	20.94%	97.22%	7.82%	
0.1200	5.44%	50.35%	5.44%	0.1759	0.1759	25.13%	96.38%	5.24%	
0.1400	4.65%	55.00%	4.65%	0.2053	0.2053	29.33%	95.54%	4.44%	
0.1600	5.49%	60.49%	5.49%	0.2346	0.2346	33.51%	94.70%	5.20%	
0.1800	3.45%	63.94%	3.45%	0.2639	0.2639	37.70%	93.87%	3.24%	
0.2000	4.08%	68.02%	4.08%	0.2932	0.2932	41.89%	93.03%	3.80%	
0.2500	6.51%	74.53%	6.51%	0.3665	0.3665	52.36%	90.93%	5.92%	
0.3000	5.47%	80.00%	5.47%	0.4398	0.4398	62.83%	88.84%	4.86%	
0.3500	4.02%	84.02%	4.02%	0.5131	0.5131	73.30%	86.74%	3.49%	
0.4000	1.98%	86.00%	1.98%	0.5864	0.5864	83.77%	84.65%	1.68%	
0.4500	2.13%	88.13%	2.13%	0.6597	0.6597	94.24%	82.55%	1.76%	
0.5000	2.03%	90.16%	1.94%	0.7331	0.7000	100.00%	77.72%	1.58%	
0.7500	5.11%	95.27%	3.25%	1.0996	0.7000	100.00%	51.82%	2.65%	
1.0000	2.48%	97.75%	1.18%	1.4661	0.7000	100.00%	38.87%	0.96%	
1.5000	1.76%	99.51%	0.56%	2.1992	0.7000	100.00%	25.91%	0.46%	
2.0000	0.48%	99.99%	0.11%	2.9322	0.7000	100.00%	19.43%	0.09%	
								89.77%	
								Removal Efficiency Adjustment ² =	6.45%
								Predicted % Annual Rainfall Treated =	88.72%
								Predicted Net Annual Load Removal Efficiency =	83.32%

1 - Based on 10 years of hourly precipitation data from NCDC station 806, Bridgeport WSO ARPT, Fairfield County, CT

2 - Reduction due to use of 60-minute data for a site that has a time of concentration less than 30-minutes.

Hydrodynamic Separation Product Calculator

800 Long Ridge Road
 CB26 TO INFILTRATION BASIN B4
 CDS 2015-4

Project Information					
Project Name	800 Long Ridge Road			Option #	A
Country	UNITED_STATES	State	Connecticut	City	Stamford

Contact Information			
First Name	Emily	Last Name	Jones
Company	Civil 1	Phone #	203-266-0778
Email	emily@civil1.com		

Design Criteria					
Site Designation	CB26 TO INFILTRATION BASIN B4			Sizing Method	Net Annual
Screening Required?	No	Drainage Area (ac)	8.15	Peak Flow (cfs)	15.40
Groundwater Depth (ft)	10 - 15	Pipe Invert Depth (ft)	5 - 10	Bedrock Depth (ft)	10 - 15
Multiple Inlets?	No	Grate Inlet Required?	No	Pipe Size (in)	24.00
Required Particle Size Distribution?	No	90° between two inlets?	N/A	180° between inlet and outlet?	No
Runoff Coefficient	0.23	Rainfall Station	34 - Birdgeport Airport, CT	TC (Min)	27

Treatment Selection					
Treatment Unit	CDS	System Model	2015-4		
Target Removal	80%	Particle Size Distribution (PSD)	125	Predicted Net Annual Removal	80.32%

Hydrodynamic Separation Product Calculator

800 Long Ridge Road

CB26 TO INFILTRATION BASIN B4

CDS 2015-4

CDS ESTIMATED NET ANNUAL SOLIDS LOAD REDUCTION BASED ON THE RATIONAL RAINFALL METHOD

Rainfall Intensity ¹ (in/hr)	% Rainfall Volume ¹	Cumulative Rainfall Volume	Rainfall Volume Treated	Total Flowrate (cfs)	Treated Flowrate (cfs)	Operating Rate (%)	Removal Efficiency (%)	Incremental Removal (%)
0.0200	9.71%	9.71%	9.71%	0.0375	0.0375	5.36%	100.00%	9.71%
0.0400	9.68%	19.39%	9.68%	0.0750	0.0750	10.71%	99.27%	9.61%
0.0600	9.81%	29.20%	9.81%	0.1125	0.1125	16.07%	98.19%	9.63%
0.0800	7.67%	36.87%	7.67%	0.1500	0.1500	21.43%	97.12%	7.45%
0.1000	8.04%	44.91%	8.04%	0.1875	0.1875	26.79%	96.05%	7.72%
0.1200	5.44%	50.35%	5.44%	0.2249	0.2249	32.13%	94.98%	5.17%
0.1400	4.65%	55.00%	4.65%	0.2624	0.2624	37.49%	93.91%	4.37%
0.1600	5.49%	60.49%	5.49%	0.2999	0.2999	42.84%	92.84%	5.10%
0.1800	3.45%	63.94%	3.45%	0.3374	0.3374	48.20%	91.77%	3.17%
0.2000	4.08%	68.02%	4.08%	0.3749	0.3749	53.56%	90.69%	3.70%
0.2500	6.51%	74.53%	6.51%	0.4686	0.4686	66.94%	88.02%	5.73%
0.3000	5.47%	80.00%	5.47%	0.5624	0.5624	80.34%	85.33%	4.67%
0.3500	4.02%	84.02%	4.02%	0.6561	0.6561	93.73%	82.65%	3.32%
0.4000	1.98%	86.00%	1.85%	0.7498	0.7000	100.00%	75.99%	1.50%
0.4500	2.13%	88.13%	1.77%	0.8435	0.7000	100.00%	67.55%	1.44%
0.5000	2.03%	90.16%	1.52%	0.9373	0.7000	100.00%	60.79%	1.23%
0.7500	5.11%	95.27%	2.54%	1.4059	0.7000	100.00%	40.53%	2.07%
1.0000	2.48%	97.75%	0.93%	1.8745	0.7000	100.00%	30.40%	0.75%
1.5000	1.76%	99.51%	0.44%	2.8118	0.7000	100.00%	20.26%	0.36%
2.0000	0.48%	99.99%	0.09%	3.7490	0.7000	100.00%	15.20%	0.07%
								86.77%
Removal Efficiency Adjustment ² =								6.45%
Predicted % Annual Rainfall Treated =								86.71%
Predicted Net Annual Load Removal Efficiency =								80.32%

1 - Based on 10 years of hourly precipitation data from NCDC station 806, Bridgeport WSO ARPT, Fairfield County, CT

2 - Reduction due to use of 60-minute data for a site that has a time of concentration less than 30-minutes.

SECTION (____)
STORM WATER TREATMENT DEVICE

1.0 GENERAL

- 1.1 This item shall govern the furnishing and installation of the CDS® by Contech Engineered Solutions LLC, complete and operable as shown and as specified herein, in accordance with the requirements of the plans and contract documents.
- 1.2 The Contractor shall furnish all labor, equipment and materials necessary to install the storm water treatment device(s) (SWTD) and appurtenances specified in the Drawings and these specifications.
- 1.3 The manufacturer of the SWTD shall be one that is regularly engaged in the engineering design and production of systems deployed for the treatment of storm water runoff for at least five (5) years and which have a history of successful production, acceptable to the Engineer. In accordance with the Drawings, the SWTD(s) shall be a CDS® device manufactured by:

Contech Engineered Solutions LLC
9025 Centre Pointe Drive
West Chester, OH, 45069
Tel: 1 800 338 1122

1.4 Related Sections

- 1.4.1 Section 02240: Dewatering
- 1.4.2 Section 02260: Excavation Support and Protection
- 1.4.3 Section 02315: Excavation and Fill
- 1.4.4 Section 02340: Soil Stabilization

- 1.5 All components shall be subject to inspection by the engineer at the place of manufacture and/or installation. All components are subject to being rejected or identified for repair if the quality of materials and manufacturing do not comply with the requirements of this specification. Components which have been identified as defective may be subject for repair where final acceptance of the component is contingent on the discretion of the Engineer.
- 1.6 The manufacturer shall guarantee the SWTD components against all manufacturer originated defects in materials or workmanship for a period of twelve (12) months from the date the components are delivered to the owner for installation. The manufacturer shall upon its determination repair, correct or replace any manufacturer originated defects advised in writing to the manufacturer within the referenced warranty period. The use of SWTD components shall be limited to the application for which it was specifically designed.
- 1.7 The SWTD manufacturer shall submit to the Engineer of Record a “Manufacturer’s Performance Certification” certifying that each SWTD is capable of achieving the specified removal efficiencies listed in these specifications. The certification shall be supported by independent third-party research

1.8 No product substitutions shall be accepted unless submitted 10 days prior to project bid date, or as directed by the Engineer of Record. Submissions for substitutions require review and approval by the Engineer of Record, for hydraulic performance, impact to project designs, equivalent treatment performance, and any required project plan and report (hydrology/hydraulic, water quality, stormwater pollution) modifications that would be required by the approving jurisdictions/agencies. Contractor to coordinate with the Engineer of Record any applicable modifications to the project estimates of cost, bonding amount determinations, plan check fees for changes to approved documents, and/or any other regulatory requirements resulting from the product substitution.

2.0 MATERIALS

2.1 Housing unit of stormwater treatment device shall be constructed of pre-cast or cast-in-place concrete, no exceptions. Precast concrete components shall conform to applicable sections of ASTM C 478, ASTM C 857 and ASTM C 858 and the following:

- 2.1.1 Concrete shall achieve a minimum 28-day compressive strength of 4,000 pounds per square-inch (psi);
- 2.1.2 Unless otherwise noted, the precast concrete sections shall be designed to withstand lateral earth and AASHTO H-20 traffic loads;
- 2.1.3 Cement shall be Type III Portland Cement conforming to ASTM C 150;
- 2.1.4 Aggregates shall conform to ASTM C 33;
- 2.1.5 Reinforcing steel shall be deformed billet-steel bars, welded steel wire or deformed welded steel wire conforming to ASTM A 615, A 185, or A 497.
- 2.1.6 Joints shall be sealed with preformed joint sealing compound conforming to ASTM C 990.
- 2.1.7 Shipping of components shall not be initiated until a minimum compressive strength of 4,000 psi is attained or five (5) calendar days after fabrication has expired, whichever occurs first.

2.2 Internal Components and appurtenances shall conform to the following:

- 2.2.1 Screen and support structure shall be manufactured of Type 316 and 316L stainless steel conforming to ASTM F 1267-01;
- 2.2.2 Hardware shall be manufactured of Type 316 stainless steel conforming to ASTM A 320;
- 2.2.3 Fiberglass components shall conform to applicable sections of ASTM D-4097
- 2.2.4 Access system(s) conform to the following:
- 2.2.5 Manhole castings shall be designed to withstand AASHTO H-20 loadings and manufactured of cast-iron conforming to ASTM A 48 Class 30.

3.0 PERFORMANCE

3.1 The SWTD shall be sized to either achieve an 80 percent average annual reduction in the total suspended solid load with a particle size distribution having a mean particle size (d_{50}) of 125 microns unless otherwise stated.

3.2 The SWTD shall be capable of capturing and retaining 100 percent of pollutants greater than or equal to 2.4 millimeters (mm) regardless of the pollutant's specific gravity (i.e.: floatable and neutrally buoyant materials) for flows up to the device's rated-treatment capacity. The SWTD shall be designed to retain all previously captured pollutants addressed by this

subsection under all flow conditions. The SWTD shall be capable of capturing and retaining total petroleum hydrocarbons. The SWTD shall be capable of achieving a removal efficiency of 92 and 78 percent when the device is operating at 25 and 50 percent of its rated-treatment capacity. These removal efficiencies shall be based on independent third-party research for influent oil concentrations representative of storm water runoff (20 ± 5 mg/L). The SWTD shall be greater than 99 percent effective in controlling dry-weather accidental oil spills.

- 3.3 The SWTD shall be designed with a sump chamber for the storage of captured sediments and other negatively buoyant pollutants in between maintenance cycles. The minimum storage capacity provided by the sump chamber shall be in accordance with the volume listed in Table 1. The boundaries of the sump chamber shall be limited to that which do not degrade the SWTD's treatment efficiency as captured pollutants accumulate. The sump chamber shall be separate from the treatment processing portion(s) of the SWTD to minimize the probability of fine particle re-suspension. In order to not restrict the Owner's ability to maintain the SWTD, the minimum dimension providing access from the ground surface to the sump chamber shall be 16 inches in diameter.
- 3.4 The SWTD shall be designed to capture and retain Total Petroleum Hydrocarbons generated by wet-weather flow and dry-weather gross spills and have a capacity listed in Table 1 of the required unit.
- 3.5 The SWTD shall convey the flow from the peak storm event of the drainage network, in accordance with required hydraulic upstream conditions as defined by the Engineer. If a substitute SWTD is proposed, supporting documentation shall be submitted that demonstrates equal or better upstream hydraulic conditions compared to that specified herein. This documentation shall be signed and sealed by a Professional Engineer registered in the State of the work. All costs associated with preparing and certifying this documentation shall be born solely by the Contractor.
- 3.6 The SWTD shall have completed field tested following TARP Tier II protocol requirements

4.0 EXECUTION

- 4.1 The contractor shall exercise care in the storage and handling of the SWTD components prior to and during installation. Any repair or replacement costs associated with events occurring after delivery is accepted and unloading has commenced shall be borne by the contractor.
- 4.2 The SWTD shall be installed in accordance with the manufacturer's recommendations and related sections of the contract documents. The manufacturer shall provide the contractor installation instructions and offer on-site guidance during the important stages of the installation as identified by the manufacturer at no additional expense. A minimum of 72 hours notice shall be provided to the manufacturer prior to their performance of the services included under this subsection.
- 4.3 The contractor shall fill all voids associated with lifting provisions provided by the manufacturer. These voids shall be filled with non-shrinking grout providing a finished surface consistent with adjacent surfaces. The contractor shall trim all protruding lifting provisions flush with the adjacent concrete surface in a manner, which leaves no sharp points or edges.

4.4 The contractor shall removal all loose material and pooling water from the SWTD prior to the transfer of operational responsibility to the Owner.

TABLE 1
Storm Water Treatment Device
Storage Capacities

CDS Model	Minimum Sump Storage Capacity (yd ³)/(m ³)	Minimum Oil Storage Capacity (gal)/(L)
CDS2015-4	0.9(0.7)	61(232)
CDS2015-5	1.5(1.1)	83(313)
CDS2020-5	1.5(1.1)	99(376)
CDS2025-5	1.5(1.1)	116(439)
CDS3020-6	2.1 (1.6)	184(696)
CDS3025-6	2.1(1.6)	210(795)
CDS3030-6	2.1 (1.6)	236(895)
CDS3035-6	2.1 (1.6)	263(994)
CDS3535-7	2.9(2.2)	377(1426)
CDS4030-8	5.6(4.3)	426(1612)
CDS4040-8	5.6 (4.3)	520(1970)
CDS4045-8	5.6 (4.3)	568(2149)
CDS5640-10	8.7(6.7)	758(2869)
CDS5653-10	8.7(6.7)	965(3652)
CDS5668-10	8.7(6.7)	1172(4435)
CDS5678-10	8.7(6.7)	1309(4956)
CDS7070-DV	3.6(2.8)	914 (3459)
CDS10060-DV	5.0 (3.8)	792 (2997)
CDS10080-DV	5.0 (3.8)	1057 (4000)
CDS100100-DV	5.0 (3.8)	1320 (4996)



END OF SECTION

CDS2015-4-C DESIGN NOTES


THE STANDARD CDS2015-4-C CONFIGURATION IS SHOWN. ALTERNATE CONFIGURATIONS ARE AVAILABLE AND ARE LISTED BELOW. SOME CONFIGURATIONS MAY BE COMBINED TO SUIT SITE REQUIREMENTS.

CONFIGURATION DESCRIPTION

- GRATED INLET ONLY (NO INLET PIPE)
- GRATED INLET WITH INLET PIPE OR PIPES
- CURB INLET ONLY (NO INLET PIPE)
- CURB INLET WITH INLET PIPE OR PIPES
- SEPARATE OIL BAFFLE (SINGLE INLET PIPE REQUIRED FOR THIS CONFIGURATION)
- SEDIMENT WEIR FOR NJDEP / NJCAT CONFORMING UNITS



FRAME AND COVER
(DIAMETER VARIES)
N.T.S.



ELEVATION A-A
N.T.S.

SITE SPECIFIC DATA REQUIREMENTS			
STRUCTURE ID			
WATER QUALITY FLOW RATE (CFS OR L/s)		*	
PEAK FLOW RATE (CFS OR L/s)		*	
RETURN PERIOD OF PEAK FLOW (YRS)		*	
SCREEN APERTURE (2400 OR 4700)		*	
PIPE DATA:	I.E.	MATERIAL	DIAMETER
INLET PIPE 1	*	*	*
INLET PIPE 2	*	*	*
OUTLET PIPE	*	*	*
RIM ELEVATION		*	
ANTI-FLOTATION BALLAST	WIDTH	HEIGHT	
	*	*	
NOTES/SPECIAL REQUIREMENTS:			
* PER ENGINEER OF RECORD			

GENERAL NOTES

1. CONTECH TO PROVIDE ALL MATERIALS UNLESS NOTED OTHERWISE.
2. DIMENSIONS MARKED WITH () ARE REFERENCE DIMENSIONS. ACTUAL DIMENSIONS MAY VARY.
3. FOR FABRICATION DRAWINGS WITH DETAILED STRUCTURE DIMENSIONS AND WEIGHTS, PLEASE CONTACT YOUR CONTECH ENGINEERED SOLUTIONS LLC REPRESENTATIVE. www.contechES.com
4. CDS WATER QUALITY STRUCTURE SHALL BE IN ACCORDANCE WITH ALL DESIGN DATA AND INFORMATION CONTAINED IN THIS DRAWING.
5. STRUCTURE SHALL MEET AASHTO HS20 AND CASTINGS SHALL MEET HS20 (AASHTO M 306) LOAD RATING, ASSUMING GROUNDWATER ELEVATION AT, OR BELOW, THE OUTLET PIPE INVERT ELEVATION. ENGINEER OF RECORD TO CONFIRM ACTUAL GROUNDWATER ELEVATION.
6. PVC HYDRAULIC SHEAR PLATE IS PLACED ON SHELF AT BOTTOM OF SCREEN CYLINDER. REMOVE AND REPLACE AS NECESSARY DURING MAINTENANCE CLEANING.

INSTALLATION NOTES


- A. ANY SUB-BASE, BACKFILL DEPTH, AND/OR ANTI-FLOTATION PROVISIONS ARE SITE-SPECIFIC DESIGN CONSIDERATIONS AND SHALL BE SPECIFIED BY ENGINEER OF RECORD.
- B. CONTRACTOR TO PROVIDE EQUIPMENT WITH SUFFICIENT LIFTING AND REACH CAPACITY TO LIFT AND SET THE CDS MANHOLE STRUCTURE (LIFTING CLUTCHES PROVIDED).
- C. CONTRACTOR TO ADD JOINT SEALANT BETWEEN ALL STRUCTURE SECTIONS, AND ASSEMBLE STRUCTURE.
- D. CONTRACTOR TO PROVIDE, INSTALL, AND GROUT PIPES. MATCH PIPE INVERTS WITH ELEVATIONS SHOWN.
- E. CONTRACTOR TO TAKE APPROPRIATE MEASURES TO ASSURE UNIT IS WATER TIGHT, HOLDING WATER TO FLOWLINE INVERT MINIMUM. IT IS SUGGESTED THAT ALL JOINTS BELOW PIPE INVERTS ARE GROUTED.



www.contechES.com
9025 Centre Pointe Dr., Suite 400, West Chester, OH 45069
800-338-1122 513-645-7000 513-645-7993 FAX

CDS2015-4-C
INLINE CDS
STANDARD DETAIL

I:\STORMWATER\COM\OPS\22 STANDARD DRAWINGS\OFFLINE LAYOUTS DWG\OFFLINE CDS-C LAYOUT BYPASS MANHOLE STRUCTURE.DWG 3/12/2013 3:34 PM



THIS PRODUCT MAY BE PROTECTED BY ONE OR MORE OF THE FOLLOWING U.S. PATENTS: 5,788,848; 6,641,720; 6,511,595; 6,581,783; RELATED FOREIGN PATENTS, OR OTHER PATENTS PENDING.

CONTECH
ENGINEERED SOLUTIONS LLC

www.ContechES.com

9025 Centre Pointe Dr., Suite 400, West Chester, OH 45069

800-338-1122 513-645-7000 513-645-7993 FAX

CDS STORMWATER TREATMENT SYSTEM
TYPICAL OFFLINE LAYOUT
WITH BYPASS MANHOLE STRUCTURE

DATE:03/12/13

SCALE: NONE

PROJECT No.: N/A

SEQ. No.: N/A

DRAWN: N/A

CHECKED: N/A

Appendix G – Rational Method Sizing for Storm Drainage

WATERSHED AREAS
800 LONG RIDGE ROAD
STAMFORD, CT

Drainage Area	Impervious (0.9)	Grass (0.3)	Wooded (0.2)	Total Area (Ac.)	Average C	Sum of AxC	Tc
STDA-1	0.454	0.000	0.000	0.454	0.900	0.409	5.00
STDA-2	0.464	0.189	0.335	0.988	0.548	0.541	12.00
STDA-3	0.399	0.176	0.252	0.827	0.559	0.462	9.00
STDA-4	0.142	0.111	0.185	0.438	0.452	0.198	11.00
STDA-5	0.315	0.054	0.000	0.369	0.812	0.300	5.00
STDA-6	0.400	0.183	0.000	0.583	0.712	0.415	5.00
STDA-7	0.147	0.061	0.000	0.208	0.724	0.151	5.00
STDA-8	0.227	0.175	0.000	0.402	0.639	0.257	5.00
STDA-9	0.216	1.105	1.012	2.333	0.312	0.728	14.00
STDA-10	0.052	0.009	0.000	0.061	0.811	0.050	5.00
STDA-11	0.112	0.146	0.000	0.258	0.560	0.145	5.00
STDA-12	0.028	0.118	0.000	0.146	0.415	0.061	5.00
STDA-13	0.064	0.003	0.000	0.067	0.873	0.059	5.00
STDA-14	0.269	0.415	0.000	0.684	0.536	0.367	5.00
STDA-15	0.048	0.185	0.000	0.233	0.424	0.099	5.00
STDA-16	0.100	0.014	0.000	0.114	0.826	0.094	5.00
STDA-17	0.125	0.036	0.000	0.161	0.766	0.123	5.00
STDA-18	0.280	0.637	0.000	0.917	0.483	0.443	5.00
STDA-19	0.036	3.651	0.000	3.687	0.306	1.128	26.00
STDA-20	0.130	0.032	0.160	0.322	0.493	0.159	5.00
STDA-21	0.117	0.114	0.000	0.231	0.604	0.140	5.00
STDA-22	0.037	0.000	0.000	0.037	0.900	0.033	5.00
STDA-23	0.223	0.157	0.000	0.380	0.652	0.248	5.00
STDA-24	0.295	0.314	0.000	0.609	0.591	0.360	5.00
STDA-25	0.084	0.000	0.000	0.084	0.900	0.076	5.00
STDA-26	0.059	0.017	0.000	0.076	0.766	0.058	5.00
STDA-27	0.084	0.000	0.000	0.084	0.900	0.076	5.00

STORM SEWER SYSTEM DESIGN
800 LONG RIDGE ROAD
STAMFORD, CT
25 Year Design Storm

LINE	SEGMENT	TIME TO	TIME IN	ACCUM.	RUNOFF	AREA	SUM OF	ACCUM.	RAINFALL	SYSTEM	PIPE	PIPE (ft)	SLOPE	Vfull	Qfull	N'	CAPACITY	HW/D
SEGMENT	TYPE	INLET	PIPE	TIME	COEFF "C"	(acres)	AxC	AxC	I	Q (cfs)	SIZE (in)	LENGTH	(ft/ft)	(fps)	(cfs)		CHECK	
ROOF TO	I	5.00	0.31	5.00	0.20	0.00												
INFIL (TYP BLDG. N)					0.30	0.00												
(STDA 1)					0.90	0.45												
							0.41	0.41	8.53	3.49	12	100	0.0100	5.36	4.21	0.0110	WITHIN CAPACITY	1.60
CB 2 TO	I	12.00	0.79	12.00	0.20	0.34												
CB-3					0.30	0.19												
(STDA 2)					0.90	0.46												
							0.54	0.54	5.52	2.99	15	255	0.0075	5.39	6.61	0.0110	WITHIN CAPACITY	0.85
CB 3 TO	C	9.00	0.02	12.79	0.20	0.25												
INFIL					0.30	0.18												
(STDA 3)					0.90	0.40												
							0.46	1.00	5.52	5.54	15	5	0.0075	5.39	6.61	0.0110	WITHIN CAPACITY	1.30
CB 4 TO	I	11.00	0.12	11.00	0.20	0.19												
DMH1					0.30	0.11												
(STDA 4)					0.90	0.14												
							0.20	0.20	5.78	1.15	15	72	0.0278	10.37	12.73	0.0110	WITHIN CAPACITY	<0.5
DMH1	C	5.00	0.15	11.12	0.20	0.00												
CB 5					0.30	0.00												
					0.90	0.00												
							0.00	0.20	5.78	1.15	15	94	0.0271	10.24	12.57	0.0110	WITHIN CAPACITY	<0.5
CB 5 TO	C	5.00	0.01	11.27	0.20	0.00												
INFIL					0.30	0.05												
(STDA 5)					0.90	0.32												
							0.30	0.91	5.78	5.28	15	5	0.0100	6.22	7.63	0.0110	WITHIN CAPACITY	1.30
CB 6 TO	I	5.00	0.80	5.00	0.20	0.00												
CB 5					0.30	0.18												
(STDA 6)					0.90	0.40												
							0.41	0.41	8.53	3.54	15	260	0.0075	5.39	6.61	0.0110	WITHIN CAPACITY	0.95
ROOF TO	I	5.00	0.18	5.00	0.20	0.00												
INFIL					0.30	0.00												
(STDA 0)					0.90	0.40												
							0.36	0.36	8.53	3.07	12	50	0.0100	4.54	3.56	0.0130	WITHIN CAPACITY	1.30
EX CB 7 TO	I	5.00	0.77	5.00	0.20	0.00												
EX CB-8					0.30	0.06												
(STDA 7)					0.90	0.15												
							0.15	0.15	8.53	1.28	12	152	0.0053	3.30	2.59	0.0130	WITHIN CAPACITY	0.65

STORM SEWER SYSTEM DESIGN
800 LONG RIDGE ROAD
STAMFORD, CT
25 Year Design Storm

LINE	SEGMENT	TIME TO	TIME IN	ACCUM.	RUNOFF	AREA	SUM OF	ACCUM.	RAINFALL	SYSTEM	PIPE	PIPE (ft)	SLOPE	Vfull	Qfull	N'	CAPACITY	HW/D
SEGMENT	TYPE	INLET	PIPE	TIME	COEFF "C"	(acres)	AxC	AxC	I	Q (cfs)	SIZE (in)	LENGTH	(ft/ft)	(fps)	(cfs)		CHECK	
EX CB 8 TO CB-9 (STDA 8)	C	5.00	0.02	5.77	0.20 0.30 0.90	0.00 0.18 0.23												
							0.26	0.41	8.53	6.08	15	62	0.5450	45.93	56.36	0.0110	WITHIN CAPACITY	1.40
CB 9 TO CB 11 (STDA 9)	C	14.00	0.17	14.00	0.20 0.30 0.90	1.01 1.11 0.22												
							0.73	1.14	5.00	8.28	15	156	0.0620	15.49	19.01	0.0110	WITHIN CAPACITY	2.00
CB 10 TO CB 11 (STDA 10)	I	5.00	0.04	5.00	0.20 0.30 0.90	0.00 0.01 0.05												
							0.05	0.05	8.53	0.42	15	15	0.0100	6.22	7.63	0.0110	WITHIN CAPACITY	<0.5
CB 11 TO CB-12 (STDA 11)	C	5.00	0.15	14.17	0.20 0.30 0.90	0.00 0.15 0.11												
							0.14	1.33	5.00	9.25	15	90	0.0250	9.84	12.07	0.0110	WITHIN CAPACITY	2.50
CB 12 TO EX-DMH (STDA 12)	C	5.00	0.06	14.32	0.20 0.30 0.90	0.00 0.12 0.03												
							0.06	1.39	5.00	12.15	24	75	0.0720	19.32	60.70	0.0130	WITHIN CAPACITY	0.95
CB 13 TO EX-DMH (STDA 13)	I	5.00	0.05	5.00	0.20 0.30 0.90	0.00 0.00 0.06												
							0.06	0.06	8.53	0.50	12	66	0.2530	22.82	17.92	0.0130	WITHIN CAPACITY	<0.5
CB 14 EX CB 15 (STDA 14)	I	5.00	0.14	5.00	0.20 0.30 0.90	0.00 0.42 0.27												
							0.37	0.37	8.53	3.13	12	65	0.0300	7.86	6.17	0.0130	WITHIN CAPACITY	1.30
EX CB-15 EX-DMH (STDA 15)	C	5.00	0.04	5.14	0.20 0.30 0.90	0.00 0.19 0.05												
							0.10	0.47	8.53	18.74	18	28	0.0400	11.89	21.01	0.0130	WITHIN CAPACITY	3.00
EX-DMH EX CB16 (STDA 0)	C	5.00	0.25	14.39	0.20 0.30 0.90	0.00 0.00 0.00												
							0.00	1.91	5.00	14.77	24	216	0.0400	14.40	45.24	0.0130	WITHIN CAPACITY	1.10

STORM SEWER SYSTEM DESIGN
800 LONG RIDGE ROAD
STAMFORD, CT
25 Year Design Storm

LINE	SEGMENT	TIME TO	TIME IN	ACCUM.	RUNOFF	AREA	SUM OF	ACCUM.	RAINFALL	SYSTEM	PIPE	PIPE (ft)	SLOPE	Vfull	Qfull	N'	CAPACITY	HW/D	
SEGMENT	TYPE	INLET	PIPE	TIME	COEFF "C	(acres)	AxC	AxC	I	Q (cfs)	SIZE (in)	LENGTH	(ft/ft)	(fps)	(cfs)		CHECK		
EX CB 16 TO HYDRO-D CB 17 (STDA 16)	C	5.00	0.04	14.64	0.20 0.30 0.90	0.00 0.01 0.10		0.09	2.01	5.00	15.24	24	27	0.0200	10.18	31.99	0.0130	WITHIN CAPACITY	1.20
HYDRO-D CB 17 BASIN B3 (STDA 17)	C	5.00	0.06	14.68	0.20 0.30 0.90	0.00 0.04 0.13		0.12	2.13	5.00	15.86	24	36	0.0200	10.18	31.99	0.0130	WITHIN CAPACITY	1.30
CB 18 DMH (STDA 18)	I	5.00	0.30	5.00	0.20 0.30 0.90	0.00 0.64 0.28		0.44	0.44	8.53	3.78	15	111	0.0100	6.22	7.63	0.0110	WITHIN CAPACITY	0.95
DMH EX YD (STDA 0)	C	5.00	0.27	5.30	0.20 0.30 0.90	0.00 0.00 0.00		0.00	0.44	8.53	3.78	18	110	0.0135	6.91	12.20	0.0130	WITHIN CAPACITY	0.75
EX YD-19 EX CB 21 (STDA 19)	C	26.00	0.09	26.00	0.20 0.30 0.90	0.00 3.65 0.04		1.13	1.57	3.75	8.49	24	126	0.1000	22.77	71.54	0.0130	WITHIN CAPACITY	0.75
EX CB 20 EX CB 21 (STDA 20)	I	5.00	0.07	5.00	0.20 0.30 0.90	0.16 0.03 0.13		0.16	0.16	8.53	1.35	12	20	0.0100	4.54	3.56	0.0130	WITHIN CAPACITY	0.65
EX CB 21 EX CB 23 (STDA 21)	C	5.00	0.09	26.09	0.20 0.30 0.90	0.00 0.11 0.12		0.14	1.87	3.75	9.61	24	126	0.1000	22.77	71.54	0.0130	WITHIN CAPACITY	0.60
EX CB 22 EX CB 23 (STDA 22)	I	5.00	0.02	5.00	0.20 0.30 0.90	0.00 0.00 0.04		0.03	0.03	8.53	0.28	12	15	0.0800	12.83	10.08	0.0130	WITHIN CAPACITY	0.60
EX CB 23 EX CB 25 (STDA 23)	C	5.00	0.06	26.18	0.20 0.30 0.90	0.00 0.16 0.22		0.25	2.15	3.75	13.26	24	72	0.0670	18.64	58.56	0.0130	WITHIN CAPACITY	0.80

STORM SEWER SYSTEM DESIGN
800 LONG RIDGE ROAD
STAMFORD, CT
25 Year Design Storm

LINE	SEGMENT	TIME TO	TIME IN	ACCUM.	RUNOFF	AREA	SUM OF	ACCUM.	RAINFALL	SYSTEM	PIPE	PIPE (ft)	SLOPE	Vfull	Qfull	N'	CAPACITY	HW/D	
SEGMENT	TYPE	INLET	PIPE	TIME	COEFF "C"	(acres)	AxC	AxC	I	Q (cfs)	SIZE (in)	LENGTH	(ft/ft)	(fps)	(cfs)		CHECK		
CB 24	I	5.00	0.03	5.00	0.20	0.00													
EX CB 25					0.30	0.31													
(STDA 24)					0.90	0.30													
							0.36	0.36	8.53	3.07	15	32	0.1500	20.39	25.02	0.0130	WITHIN CAPACITY	0.85	
CB 25	C	5.00	0.11	26.25	0.20	0.00													
EX CB 26					0.30	0.00													
(STDA 25)					0.90	0.08													
							0.08	2.59	3.25	13.60	24	170	0.1350	26.46	83.12	0.0130	WITHIN CAPACITY	0.95	
CB 27	I	5.00	0.02	5.00	0.20	0.00													
EX CB 26					0.30	0.00													
(STDA 27)					0.90	0.08													
							0.08	0.08	8.53	0.64	12	15	0.0700	12.00	9.43	0.0130	WITHIN CAPACITY	<0.5	
CB 26	C	5.00	0.03	26.36	0.20	0.00													
HYDRO-D					0.30	0.02													
(STDA 26)					0.90	0.06													
							0.06	2.72	3.75	15.40	24	25	0.0200	12.04	37.81	0.0110	WITHIN CAPACITY	1.10	
HYDRO-D	C	5.00	0.07	26.39	0.20	0.00													
BASIN					0.30	0.00													
(STDA 26)					0.90	0.00													
							0.00	2.72	3.75	15.40	24	80	0.0500	19.03	59.78	0.0110	WITHIN CAPACITY	1.10	

Appendix H - Outlet Protection Calculations

Culvert Report

Circular Culvert

Invert Elev Dn (ft)	=	100.00
Pipe Length (ft)	=	60.00
Slope (%)	=	7.50
Invert Elev Up (ft)	=	104.50
Rise (in)	=	24.0
Shape	=	Circular
Span (in)	=	24.0
No. Barrels	=	1
n-Value	=	0.012
Culvert Type	=	Circular Culvert
Culvert Entrance	=	Rough tapered inlet throat
Coeff. K,M,c,Y,k	=	0.519, 0.64, 0.021, 0.9, 0.5

Embankment


Top Elevation (ft)	=	110.00
Top Width (ft)	=	40.00
Crest Width (ft)	=	50.00

Calculations

Qmin (cfs)	=	15.90
Qmax (cfs)	=	15.90
Tailwater Elev (ft)	=	(dc+D)/2

Highlighted

Qtotal (cfs)	=	15.90
Qpipe (cfs)	=	15.90
Qovertop (cfs)	=	0.00
Veloc Dn (ft/s)	=	5.54
Veloc Up (ft/s)	=	6.58
HGL Dn (ft)	=	101.72
HGL Up (ft)	=	105.94
Hw Elev (ft)	=	106.85
Hw/D (ft)	=	1.17
Flow Regime	=	Inlet Control



INFIL BASIN 1B3
OUTLET PROTECTION

OUTLET PROTECTION - OUTLET VELOCITY \leq 14 feet/sec

DISCHARGE (cfs)	OUTLET PIPE DIAMETER OR SPAN (in)									
	12	15	18	24	30	36	42	48	54	60
0-5	10	10		USE						
5.5	12	11								
6		12	12				MINIMUM			
7		14	13	12						
8			15	13						
8.5			16	14				LENGTH		
9				14						
10				15	14					
11				16	15					
12				17	15	14				OUTLINED
13				18	16	15				
14				X	17	15	14			
16		USE			18	16	15	14		
18						18	16	15		
20						19	17	16		
22						20	18	16		
24							19	17	16	
26							20	18	17	16
28							21	19	17	16
30							21	19	18	17
32							22	20	18	17
35								21	19	18
40								23	21	19
45								25	23	21
48								26	24	22
50									24	22
55									26	23
60									27	25
63									28	26
65										26
75										HOLE
80										29
										30

Table 8-7.1 - Length - L_a (feet)
Type B or C Riprap Apron

- Notes: 1. Bold face outlined boxes indicate minimum L_a to be used for a given pipe diameter or span.
2. Rounding and interpolating are acceptable.

Q = 15.9 cfs use preformed scow hole

OUTLET PROTECTION
OUTLET VELOCITY > 14 feet/sec or Length of Apron exceeds limits shown on
Tables 8-6.1 and 8-7.1

Preformed Scour Hole										
(See Figure 8-11)	PIPE DIAMETER (in)									
	12	15	18	24	30	36	42	48	54	60
Type 1										
B	5	6	8	10	13	15	18	20	23	25
C	6	8	9	12	15	18	21	24	27	30
d	Depends on riprap type (see Figure 8-11)									
2S_p	2.0	2.6	3.0	4.0	5.0	6.0	7.0	8.0	9.0	10.0
3S_p	3.0	3.9	4.5	6.0	7.5	9.0	10.5	12.0	13.5	15.0
F = 0.5 S_p	0.5	0.625	0.75	1	1.25	1.5	1.75	2	2.25	2.5
Type 2										
B	8	10	12	16	20	24	28	32	36	40
C	9	11	14	18	23	27	32	36	41	45
d	Depends on riprap size (see Figure 8-11)									
2S_p	2.0	2.6	3.0	4.0	5.0	6.0	7.0	8.0	9.0	10.0
3S_p	3.0	3.9	4.5	6.0	7.5	9.0	10.5	12.0	13.5	15.0
F = S_p	1.0	1.3	1.5	2.0	2.5	3.0	3.5	4.0	4.5	5.0

Table 8-8.1 - Dimensions of Preformed Scour Hole (Feet)

Velocity = 5.5 fps. use modified riprap




Figure 8-11 Preformed Scour Hole Type 1 and Type 2

Culvert Report

Circular Culvert

Invert Elev Dn (ft)	= 92.00
Pipe Length (ft)	= 82.00
Slope (%)	= 4.90
Invert Elev Up (ft)	= 96.02
Rise (in)	= 24.0
Shape	= Circular
Span (in)	= 24.0
No. Barrels	= 1
n-Value	= 0.012
Culvert Type	= Circular Culvert
Culvert Entrance	= Rough tapered inlet throat
Coeff. K,M,c,Y,k	= 0.519, 0.64, 0.021, 0.9, 0.5

Embankment


Top Elevation (ft)	= 110.00
Top Width (ft)	= 70.00
Crest Width (ft)	= 50.00

Calculations

Qmin (cfs)	= 15.40
Qmax (cfs)	= 15.40
Tailwater Elev (ft)	= (dc+D)/2

Highlighted

Qtotal (cfs)	= 15.40
Qpipe (cfs)	= 15.40
Qovertop (cfs)	= 0.00
Veloc Dn (ft/s)	= 5.39
Veloc Up (ft/s)	= 6.49
HGL Dn (ft)	= 93.71
HGL Up (ft)	= 97.43
Hw Elev (ft)	= 98.32
Hw/D (ft)	= 1.15
Flow Regime	= Inlet Control



INFIL BASIN 1B4
OUTLET PROTECTION

OUTLET PROTECTION - OUTLET VELOCITY \leq 14 feet/sec

DISCHARGE (cfs)	OUTLET PIPE DIAMETER OR SPAN (in)									
	12	15	18	24	30	36	42	48	54	60
0-5	10	10		<i>USE</i>						
5.5	12	11								
6		12	12				<i>MINIMUM</i>			
7		14	13	12						
8			15	13						
8.5			16	14				<i>LENGTH</i>		
9				14						
10				15	14					
11				16	15					
12				17	15	14				<i>OUTLINED</i>
13				18	16	15				
14				X	17	15	14			
16		<i>USE</i>			18	16	15	14		
18						18	16	15		
20						19	17	16		
22						20	18	16		
24							19	17	16	
26							20	18	17	16
28					<i>PREFORMED</i>		21	19	17	16
30							21	19	18	17
32							22	20	18	17
35								21	19	18
40								23	21	19
45								25	23	21
48						<i>SCOUR</i>		26	24	22
50									24	22
55									26	23
60									27	25
63									28	26
65										26
75								<i>HOLE</i>		29
80										30

**Table 8-7.1 - Length - L_a (feet)
Type B or C Riprap Apron**

- Notes: 1. Bold face outlined boxes indicate minimum L_a to be used for a given pipe diameter or span.
2. Rounding and interpolating are acceptable.

Q = 15.4 cfs, use preformed scour hole

INFIL. BASIN 134
OUTLET PROTECTION

OUTLET PROTECTION
OUTLET VELOCITY > 14 feet/sec or Length of Apron exceeds limits shown on
Tables 8-6.1 and 8-7.1

Preformed Scour Hole										
(See Figure 8-11)	PIPE DIAMETER (in)									
	12	15	18	24	30	36	42	48	54	60
Type 1										
B	5	6	8	10	13	15	18	20	23	25
C	6	8	9	12	15	18	21	24	27	30
d	Depends on riprap type (see Figure 8-11)									
2S_p	2.0	2.6	3.0	4.0	5.0	6.0	7.0	8.0	9.0	10.0
3S_p	3.0	3.9	4.5	6.0	7.5	9.0	10.5	12.0	13.5	15.0
F = 0.5 S_p	0.5	0.625	0.75	1	1.25	1.5	1.75	2	2.25	2.5
Type 2										
B	8	10	12	16	20	24	28	32	36	40
C	9	11	14	18	23	27	32	36	41	45
d	Depends on riprap size (see Figure 8-11)									
2S_p	2.0	2.6	3.0	4.0	5.0	6.0	7.0	8.0	9.0	10.0
3S_p	3.0	3.9	4.5	6.0	7.5	9.0	10.5	12.0	13.5	15.0
F = S_p	1.0	1.3	1.5	2.0	2.5	3.0	3.5	4.0	4.5	5.0

Table 8-8.1 - Dimensions of Preformed Scour Hole (Feet)

Velocity = 5.4 f/s, use mod. sized riprap





Figure 8-11 Preformed Scour Hole Type 1 and Type 2

Appendix I – USDA Soils Mapping

Soil Map—State of Connecticut
(800 Long Ridge Road)



Map Scale: 1:2,830 if printed on A portrait (8.5" x 11") sheet.




Natural Resources
Conservation Service

Web Soil Survey
National Cooperative Soil Survey

7/26/2023
Page 1 of 3

MAP LEGEND

Area of Interest (AOI)

 Area of Interest (AOI)

Soils

 Soil Map Unit Polygons

 Soil Map Unit Lines

 Soil Map Unit Points

Special Point Features



Blowout



Borrow Pit



Clay Spot



Closed Depression



Gravel Pit



Gravelly Spot



Landfill



Lava Flow



Marsh or swamp



Mine or Quarry



Miscellaneous Water



Perennial Water



Rock Outcrop



Saline Spot



Sandy Spot



Severely Eroded Spot



Sinkhole



Slide or Slip



Sodic Spot



Spoil Area



Stony Spot



Very Stony Spot



Wet Spot



Other



Special Line Features

Water Features



Streams and Canals

Transportation



Rails



Interstate Highways



US Routes



Major Roads



Local Roads

Background



Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:12,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service

Web Soil Survey URL:

Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: State of Connecticut

Survey Area Data: Version 22, Sep 12, 2022

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Oct 21, 2022—Oct 27, 2022

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
29B	Agawam fine sandy loam, 3 to 8 percent slopes	0.1	0.5%
51B	Sutton fine sandy loam, 0 to 8 percent slopes, very stony	0.2	0.7%
62C	Canton and Charlton fine sandy loams, 3 to 15 percent slopes, extremely stony	0.2	0.7%
73C	Charlton-Chatfield complex, 0 to 15 percent slopes, very rocky	1.7	7.1%
238C	Hinckley-Urban land complex, 3 to 15 percent slopes	0.0	0.2%
273E	Urban land-Charlton-Chatfield complex, rocky, 15 to 45 percent slopes	5.2	21.1%
306	Udorthents-Urban land complex	16.5	66.8%
W	Water	0.7	3.0%
Totals for Area of Interest		24.7	100.0%

**Appendix J – Draft Standard City of Stamford Drainage
Maintenance Agreement**

Block _____ .

AGREEMENT COVENANT

AGREEMENT made this _____ day of _____ by and between _____ of _____ in the City of Stamford, County of Fairfield and State of Connecticut (hereinafter referred to as "Owner"); and the **CITY OF STAMFORD**, a municipal corporation lying within the County of Fairfield and State of Connecticut, acting herein by its duly authorized Mayor, David R. Martin (hereinafter referred to as the "CITY"), the **ENVIRONMENTAL PROTECTION BOARD OF THE CITY OF STAMFORD**, acting herein by its duly authorized Chairman, Gary H. Stone (hereinafter referred to as the "EPB").

WITNESSETH

WHEREAS, OWNER has commenced the planning and construction of a new _____ on land owned by it and as more particularly described on Schedule "A" annexed hereto and made of part hereof (hereinafter referred to as the "Property"); and

WHEREAS, certain drainage facilities ("Drainage Facilities"), including but not limited to _____ as more particularly described on Schedule "B" attached (the "Construction Plans") shall be installed in connection with the aforesaid construction and in accordance with the Construction Plans and _____ Permit No. _____ issued by the _____ Board of the City of Stamford (_____) issued

therefore, ("Permit") and;

WHEREAS, OWNER, the CITY and EPB share a joint concern that the Drainage Facilities be maintained in a functioning condition so as to avoid pollution of surface and groundwaters, flooding and/or improper drainage.

NOW, THEREFORE, in consideration of ten dollars and other good and valuable consideration receipt of which is hereby acknowledged by the OWNER, it is hereby agreed as follows:

- 1) OWNER shall clean the drainage facilities or cause such facilities to be cleaned by periodic removal of accumulated sediment and debris in a good and workman-like manner, at least two (2) times during every twelve (12) month period, which times shall be in the period between April and June and between October and December and more often as the City may determine to be necessary.
- 2) OWNER shall sweep, or cause to be swept, garage facilities, driveways and roadway surfaces located on the Property at least once per calendar quarter.
- 3) OWNER shall utilize only sand or calcium chloride in connection with the de-icing of areas within the Property meaning and intending that road salt (Sodium Chloride) shall not be used for said purpose.
- 4) OWNER shall repair or replace any defects or defective drainage

facilities so as to maintain the drainage facilities, at all times, in a fully functional capacity.

- 5) OWNER shall file as-built drainage plans with the EPB immediately upon the completion of work. Said plans shall be prepared by a professional engineer/surveyor registered in the State of Connecticut.

- 6) OWNER grants the CITY and/or EPB, its agents, and employees, the right to enter the Property at all reasonable times upon twenty-four (24) hours notice to the OWNER for the purpose of inspecting the Property to determine if OWNER is complying with the requirements hereunder. A representative of the Owner shall have the right to accompany the City and/or EPB on their inspection of the Property.

- 7) If, after an inspection is made pursuant to Paragraph Six (6) hereof, the CITY and/or EPB determines that the owner has failed to comply with the aforesaid undertakings, then the CITY and/or EPB shall give written notice of said determination to the then OWNER of the Property which notice shall also specify the said failure. Said notice shall be sent by registered or certified mail to the last known address of said Owner. If the Owner disputes the claim, he shall give written notice thereof to City and/or EPB within ten (10) days of receipt of said notice, and the EPB shall hold a hearing as promptly as possible to decide the merits of the disputed claim. If the claim is not disputed within

said ten (10) days, the OWNER shall have thirty (30) days from the receipt of said notice to correct said failure, unless it is impossible to cure said defect within said time, in which case, the necessary repairs shall be immediately commenced and diligently pursued to completion within a reasonable time.

- 8) If the said failure is not remedied within the time frame herein stated, the CITY and/or EPB may proceed to cure the same and charge the actual cost thereof to the OWNER of the Property.
- 9) OWNER agrees to reimburse the CITY and/or EPB for reasonable legal fees and court costs if it becomes necessary for the CITY and/or EPB to sue for reimbursement of sums expended by the CITY and/or EPB in performance of OWNER'S obligation.
- 10) OWNER agrees and covenants to indemnify and save harmless the CITY and the EPB against any and all claims, suits, actions or judgments arising out of the delay in the performance of any of their obligations pursuant to this Agreement.
- 11) OWNER agrees that this covenant and restriction shall apply to and run with the land. It shall be binding on all future owners, administrators, executors, successors and assigns.
- 12) The OWNER hereby represents to the CITY and EPB that he/she is the owner, in fee simple, of all of the property described in "Schedule A" attached hereto and made a part hereof.

- 13) OWNER agrees that this Agreement and restrictive covenant upon execution of the same, shall be recorded on the land records at the OWNER'S expense at the time that a permit is issued for the Property herein and while the OWNER is in title.
- 14) OWNER agrees not to assert the invalidity of this document.
- 15) OWNER agrees that nothing herein shall be construed to be a limitation upon the right of the EPB to assert and enforce any rights it may have under federal, state or City statute, ordinance or regulation.
- 16) This agreement shall be governed by the laws of the State of Connecticut.

IN WITNESS WHEREOF, the said parties hereto have hereunto set their hands and seals, the day and year first above written.

WITNESSED:

THE CITY OF STAMFORD

BY: _____

David R. Martin
Its duly authorized Mayor

(ACKNOWLEDGEMENT ON THE FOLLOWING PAGE)

STATE OF CONNECTICUT}
} ss: STAMFORD Date: _____
COUNTY OF FAIRFIELD }

Personally appeared Gary H. Stone, Chairman of the Environmental Protection Board of the City of Stamford, signer and sealer of the foregoing instrument, and acknowledged the same to be his free act and deed and the free act and deed of said Commission, before me.

Commissioner of the Superior Court
or Notary Public

STATE OF CONNECTICUT }
} ss: STAMFORD Date: _____
COUNTY OF FAIRFIELD }

Personally appeared _____, signer and sealer of the foregoing instrument, and acknowledge the same to be _____ free act and deed, before me.

Commissioner of the Superior Court
or Notary Public

Appendix K - DCIA Tracking Worksheet

Directly Connected Impervious Area Tracking Worksheet
City of Stamford Drainage Manual



Note to user: complete all cells of this color *only*

Part 1: General Information	
Project Name	800 Long Ridge Road
Project Address	800 Long Ridge Road, Stamford, CT
Project Applicant	Building & Land Technology
Date of Submittal	10/03/2023
Tax Account Number	

Part 2: Project Details	
1. What type of development is this? (choose from dropdown)	Redevelopment
2. What is the total area of the project site?	1,100,532 ft ²
3. What is the total area of land disturbance for this project?	574,239 ft ²
4. Does project site drain to High Quality Waters, a Direct Waterfront, or within 500 ft. of Tidal Wetlands? (Yes/No)	No
5. What is the <u>current DCIA</u> for the site?	360,066 ft ²
6. Will the proposed development increase <u>DCIA</u> (without consideration of proposed stormwater management)? (Yes/No)	Yes
7. What is the <u>proposed-development total impervious area</u> for the site?	384,562 ft ²

Part 3: Water Quality Target Total	
Does Standard 1 apply based on information above?	Yes
Water Quality Volume (WQV)	32,047 ft ³
Standard 1 requirement	Retain WQV On-Site
Required treatment/retention volume	32,047 ft ³
Provided treatment/retention volume for proposed development	33,626 ft ³

Part 4: Proposed DCIA Tracking	
Pre-development <u>total impervious area</u>	360,066 ft ²
<u>Current DCIA</u>	360,066 ft ²
<u>Proposed-development total impervious area</u>	384,562 ft ²
<u>Proposed-development DCIA</u> (after stormwater management)	384,562 ft ²
Net change in <u>DCIA</u> from <u>pre-development</u> to <u>proposed-development</u>	24,496 ft ²

Part 5: Post-Development (As-Built Certified) DCIA Tracking	
<u>Post-development</u> (per as-built) <u>total impervious area</u>	ft ²
<u>Post-development</u> (per as-built) <u>DCIA</u> (after stormwater management)	ft ²
Net change in <u>DCIA</u> from <u>pre-development</u> to <u>post-development</u>	ft ²

Certification Statement

I hereby certify that the information contained in this worksheet is true and correct.

Engineer's Signature

Date 10/03/23

Engineer's Seal

**Appendix L - Checklist for Stormwater Management
Report & Plan**



Checklist for Stormwater Management Report

I. Project Report

A. Applicant / Site Information

X	Applicant name, legal address, contact information (email & phone)
X	Engineers name, legal address, contact information (email & phone)
X	Site address and legal description
X	Current / proposed zoning and land use
X	Site vicinity map (8.5" x 11")

B. Project Description and Purpose

X	Project description including proposed project elements and anticipated construction schedule
---	---

C. Existing Conditions Description

X	Site area, ground cover, vegetation, features (roads, buildings, utilities, etc.)
X	Site topography, slopes, drainage patterns, conveyances systems (swales, storm drains, etc.), stormwater discharge locations
X	Receiving waterbody information including stormwater impairments and TMDL information (See the most recent State of Connecticut Integrated Water Quality Report)
X	Site soils information including soil types, hydrologic soil group, bedrock / outcroppings, groundwater elevation, significant geologic features
X	Provide NRCS Soils Mapping
X	Resource protection areas (wetlands, streams, lakes, etc.), buffers, floodplains, floodways

D. Summary of Applicable General Design Criteria

X	Methodology, design storm frequency
X	Hydrologic design criteria
X	Hydraulic design criteria
X	Flood hazard areas

X	Applying under "Lite" Stormwater Management: Skip to Section I (Refer to Flow Chart on page vii of the City of Stamford Stormwater Drainage Manual)
----------	---

E. Project Type in Accordance with Standard 1 Definitions

X	Area of disturbance, receiving waterbody classification (High Quality, Tidal Wetlands, Direct Waterfront)
X	Project type (development, redevelopment, linear development)
X	Pollutant reduction standard per flowchart Section 2.4



F. Summary of LID Site Constraints

X	Description of sensitive areas for protection
X	Mature tree inventory, which shall include 8-inch (dbh) diameter trees or greater
X	Steep slopes
	Ledge and bedrock depth
	Seasonal high groundwater elevation
	Pollutant hotspots
X	Summary of infiltration rates

G. Summary of Proposed Stormwater Treatment Practices

X	Proposed LID controls (i.e. minimize impervious, minimize DCIA, minimize disturbance, increase time of concentrations, other LID controls and strategies)
X	Location, size, types
X	Design criteria and references
X	Stormwater treatment practice, drainage area characteristics / details

H. Summary of Compliance with Standards 1

X	Required pollutant reduction criteria
X	Provided pollutant reduction (WOV) by stormwater treatment practice
X	Summary of compliance with Standard 1

I. Summary of Compliance with Standards 2, 3, and 4

X	Description of proposed stormwater management system
X	Pre-development site hydrology with delineation of each watershed area and sub-basin
X	Post-development site hydrology with delineation of each watershed area and sub-basin
X	Comparison table of pre- and post-development hydrology, peak flow, volume, and percent difference
X	Summary table of watershed areas and sub-basin areas, time of concentration and runoff coefficients
X	Summary table demonstrating the 2-year, 24-hour post development peak flow rate is less than or equal to the lowest of either: - The pre-development 1-year, 24-hour storm peak flow rate - 50 percent of the pre-development 2-year, 24-hour storm peak flow rate
X	Conveyance protection, emergency outlet sizing
	Hydraulic grade line summary and tail water elevation used in analysis
X	Construction erosion and sediment control description, Standard 3
X	Operation and Maintenance, maintenance tasks and schedule on construction plans per Standard 4



City of Stamford
 Engineering Bureau
 888 Washington Boulevard, 7th Floor Stamford, CT 06901
 Phone 203-977-4189

J. Summary of Compliance with Applicable Drainage Facility Design Requirements

X	Description of applicable design requirements and compliance
X	Description of proposed drainage facilities and compliance

K. Stormwater Management Report

X	Signed and stamped by professional engineer licensed in the State of Connecticut
X	Drainage impact statement in accordance with Standard 5B.

II. Supporting Calculations (as appendix to Project Report)

<u>Applying under "Lite" Stormwater Management: Skip to Section N</u>	
--	--

L. Water Quality Volume / Water Quality Flow Calculations

X	Calculations demonstrating the total Water Quality Volume generated by the post-development site and the required retention/treatment volume per Standard 1 in cubic feet.
X	Calculations demonstrating the total Water Quality Volume retained/treated by each stormwater treatment practice and the total Water Quality Volume generated by the post-development contributing drainage area to each stormwater treatment practice

M. Stormwater Treatment Practice Sizing Calculations

X	Calculations demonstrating how each stormwater treatment practice has been designed and sized in accordance with the Structural Stormwater BMP Design references in Appendix B. Calculations will vary by stormwater treatment practice, but a minimum, applicants shall provide calculations in accordance with design criteria from the Connecticut Stormwater Quality Manual.
---	--

N. Hydrologic and Hydraulic Design Calculations

X	Stream channel protection, Standard 2A
X	Conveyance protection, Standard 2B
X	Peak flow control (1-year, 2-year, 5-year, 10-year, 25-year, and 50-year storms), Standard 2C
X	Inlet analysis
	Gutter flow (Site by site basis as requested by Engineering Bureau)
X	Storm sewers and culverts (velocities, capacity, hydraulics)
	Hydraulic grade line required when pipe is flowing at full capacity <ul style="list-style-type: none"> o Provide existing and proposed summary table o Provide existing and proposed mapping, label structures
X	Detention facilities (outlet structure, stage/storage, freeboard)
X	Emergency outlet sizing, safely pass the 100 year storm, Standard 2D
X	Outlet protection calculations, based on conveyance protection (i.e. riprap, energy dissipater)



City of Stamford
 Engineering Bureau
 888 Washington Boulevard, 7th Floor Stamford, CT 06901
 Phone 203-977-4189

O. Hydrologic and Hydraulic Model, Existing and Proposed

X	Drainage routing diagram
X	Summary
X	Storage pond input

P. Downstream analysis (Site by site basis as required by the Engineering Bureau)

	Downstream analysis, Standard 2E
--	----------------------------------

III. Supporting Mapping (as appendix to Project Report)

O. Pre-Development Drainage Basin Area Mapping

X	11" x 17" or 8.5" x 11" sheet size
X	Topography, drainage patterns, drainage area boundaries and sub basins, flow paths, times of concentration
X	Locations of existing stormwater discharges
X	Perennial and intermittent streams, wetlands, and floodplain / floodways
X	NRCS soil types, locations, boring locations, infiltration testing locations
X	Vegetation and groundcover
X	Existing roads, buildings, driveways, parking areas, walks, patios, pools and other impervious surfaces, decks and other structures
X	Location, size, type of existing structural stormwater controls, facilities and conveyance systems

R. Post-Development Drainage Basin Area Mapping

X	11" x 17" or 8.5" x 11" sheet size
X	Topography, drainage patterns, drainage area boundaries and sub basins, flow paths, times of concentration
X	Locations of proposed stormwater discharges
X	Perennial and intermittent streams, wetlands, and floodplain / floodways
X	NRCS soil types, locations, boring locations, infiltration testing locations
X	Vegetation, ground cover and proposed limits of clearing/disturbance
X	Proposed, roads, buildings, driveways, parking areas, walks, patios, pools and other impervious surfaces, decks and other structures
X	Location, size, type of proposed structural stormwater controls, facilities and conveyance systems

IV. DCIA Tracking Worksheet (as appendix to Project Report)

X	DCIA Tracking Worksheet (Use form found in Appendix E)
---	--



City of Stamford
 Engineering Bureau
 888 Washington Boulevard, 7th Floor Stamford, CT 06901
 Phone 203-977-4189

V. Proposed LID Review Map

	Applying under "Lite" Stormwater Management - Proposed LID Review Map <u>NOT</u> required.
--	---

A. General

X	Site address
X	Applicant name, legal address, contact information
X	Engineers name, address, contact information
X	North arrow, bar scale, horizontal and vertical datum
X	Drawing scale shall be set at 1"=20' or 1"=40' when possible
X	Signed and stamped by a Licensed Professional Engineer in the State of Connecticut
X	11" x 17" or 24" x 36" sheet size unless otherwise approved
X	Existing and proposed contours based on NAVD 88 at 2 foot contour interval or 1 foot contour interval when slope is flatter than 2 percent
X	Locations of existing stormwater discharges
X	Roads, buildings, driveways, parking areas, walks, patios, pools and other impervious surfaces, and decks and other structures
X	Location, size, ownership of stormwater conveyance systems (swales, pipes, etc.)

B. LID Constraints:

	Boring / test pit locations
	Infiltration testing locations and results
X	Vegetation and proposed limits of clearing / disturbance
X	NRCS soils mapping
X	Steep slopes
X	Surface waters / Perennial and intermittent streams
X	Resource protection areas and buffers, wetlands, floodplain / floodways
	Existing vegetation and mature trees, which shall include 8-inch (dbh) diameter trees or greater
	Poor soils (HSG C & D)
	Shallow bedrock / ledge
	Seasonal high groundwater elevation
	Other site constraints (e.g. brownfield caps)

C. Proposed Stormwater Treatment Measures:

X	Location, size, type, limits, and WQV provided by each proposed stormwater treatment practices
X	Drainage area to each proposed stormwater treatment practice (total area, impervious area, WQV)

D. Site Summary Table:

X	Total site area, disturbed area, pre- and post-development impervious areas
X	Required pollutant reduction volume (retention or detention)
X	Provided pollutant reduction volume (retention or detention)



City of Stamford
Engineering Bureau
888 Washington Boulevard, 7th Floor Stamford, CT 06901
Phone 203-977-4189

Checklist for Stormwater Management Plan / Construction Plans

A. General

X	Site orientation, address and legal description
X	Applicant name, legal address, contact information
X	Engineers name, address, contact information
X	North arrow, bar scale, horizontal and vertical datum
X	Drawing scale shall be set at 1" = 20' or 1" = 40' when possible
X	Stamped by a Licensed Professional Engineer in the State of Connecticut
X	24" x 36" sheet size unless otherwise approved

B. Site Development Plans

X	City of Stamford Standard Notes
X	As required by the Drainage Maintenance Agreement, provide a written narrative describing the nature of the proposed development activity and the program for operation and maintenance of drainage facilities and control measures throughout the life of the project.
X	Existing and proposed contours based on NAVD 88 at 2 foot contour interval or 1 foot contour interval when slope is flatter than 2 percent
X	All required spot elevations to clearly depict positive pitch
X	Top and bottom elevation of all walls
X	Roads, buildings, driveways, parking areas, walks, patios, pools and other impervious surfaces, and decks and other structures
X	All utilities and easements
X	Location, size, maintenance access, type of proposed structural stormwater controls and facilities with elevations and inverts
X	Location, size, maintenance access, type of proposed non-structural stormwater controls and facilities with elevations and inverts
X	Location, size, type of proposed stormwater infrastructure, inlets, manholes, infiltration and detentions systems, control structures with elevations and inverts
X	Location, size, ownership of stormwater conveyance systems (swales, pipes, etc.) with elevations and inverts
X	Identify roof leaders, curtain drains and foundation drains with elevations and inverts
X	Proposed water quality treatment systems, size and model type
X	Final stabilization measures which may include slope stabilization

C. Erosion and Sedimentation Control Plan

X	Phasing and schedule
X	Construction access and staging and stock pile areas
X	Operation and maintenance of erosion and sedimentation controls
X	Tree protection
X	Downstream protection such as location of silt fencing
X	Limit of disturbance
X	Construction fencing



City of Stamford
Engineering Bureau
888 Washington Boulevard, 7th Floor Stamford, CT 06901
Phone 203-977-4189

D. Construction Details

X	Standard City of Stamford details
X	Infiltration system details
X	Control structure details
X	Water quality treatment details
	Infiltration testing results

Checklist for Certificate of Occupancy






	Final Improvement Location Survey
	Stormwater Management Certification Form
	Final DCIA Tracking Worksheet
	Standard City of Stamford Drainage Maintenance Agreement (Agreement Covenant)



Other Certifications at the discretion of the Engineering Bureau and/or EPB

	Wall Certification
	Landscape Certification
	Landscape Maintenance Agreement
	Waiver Covering Storm Sewer Connection
	Waiver Covering Granite Block, Depressed Curb, and Driveway Aprons
	Flood Certification

Appendix M - LID Review Map


LEGEND

-  PROPERTY LINE
-  BUILD-TO LINE
-  PROPOSED EDGE OF PAVEMENT
-  EXISTING EDGE OF PAVEMENT TP REMAIN
-  EXISTING & PROPOSED BIT. PAVEMENT
-  CONCRETE SIDEWALK/PAVER AREA
-  PROPOSED LAWN/LANDSCAPED AREA
-  EX. WOODED/LAWN/LANDSCAPED AREAS TO REMAIN
-  PROPOSED STORMWATER BMP



NO.	REVISION	DATE

Previous Editions Obsolete




BUILDING AND LAND TECHNOLOGY
 100 WASHINGTON BLVD.
 SUITE 200
 STAMFORD, CT 06902

LID REVIEW MAP

800 LONG RIDGE ROAD

STAMFORD CONNECTICUT



CIVIL C1

CORNERSTONE PROFESSIONAL PARK, SUITE D-101
 43 SHERMAN HILL ROAD
 WOODBURY CONNECTICUT (203) 266-0778

DATE: 29 SEP 23
 PROJ. NO.: 4084
 CAD FILE NAME: 4084_LID_MAP
 DRAWING NO.: **1 OF 1**